



Lake Transit Authority Bus Passenger Facility Plan

Final December 2019



Table of Contents

Chapter 1 Ir	ntroduction	on	1-1
1.1	Plan O	verview	1-1
1.2	Plan O	rganization	1-1
1.3	Comm	unity Outreach	1-1
	1.3.1	Public Survey	1-1
	1.3.2	Community Workshops	1-2
Chapter 2 E	xisting C	Conditions	2-1
2.1	Introdu	oction	2-1
2.2	Literatu	ure Review	2-1
	2.2.1	Lake Transit Hub Location Plan, 2017	2-1
	2.2.2	Lake County Transit Development Plan and Marketing Plan, 2015	2-1
	2.2.3	Lake County 2014-2015 Coordinated Public Transit – Human Services Transportation Plan	2-3
	2.2.4	Lake County Transit Energy Use Reduction Plan, 2015	2-4
	2.2.5	Lake County Transit Development Plan Study, 2008	2-4
	2.2.6	Transit Passengers Facilities Development Plan for Lake County, 2006	2-4
	2.2.7	SR 53 Corridor Studies (TJKM–2011 and Caltrans–2014)	2-5
	2.2.8	Transportation Concept Report (TCR) Route 20 East	2-6
	2.2.9	Transportation Concept Report Route 29	2-6
	2.2.10	Lake County General Plan, 2008	2-6
	2.2.11	Lake County Regional Transportation Plan, 2017	2-7
	2.2.12	Lake County Active Transportation Plan, 2016	2-7
	2.2.13	Middletown Community Action Plan, 2014	2-7
	2.2.14	Highway 20 Traffic Calming and Beautification Plan, 2005	2-10
	2.2.15	Lake County Area Plans	2-10
	2.2.16	City of Clear Lake General Plan, 2017	2-11
	2.2.17	City of Lakeport General Plan, 2009	2-11

		2.2.18	Lakeshore Drive Downtown Corridor Plan, 2014	2-11
	2.3	Lake T	ransit Lake County Bus Stop Facility Inventory	2-12
		2.3.1	List of Bus Stops	2-13
		2.3.2	Data Organization	2-14
Chap	ter 3 De	esign St	andards	3-1
	3.1	Introdu	oction	3-1
	3.2	Minimu	ım Sidewalk and Bicycle Facility Parameters	3-1
		3.2.1	Sidewalks	3-1
		3.2.2	Bicycle Facilities	3-2
	3.3	Bus Pu	ıllout Design Parameters	3-2
	3.4	Bus St	op Design Parameters	3-3
	3.5	Lake T	ransit Authority	3-4
	3.6	Recom	mended LTA Design Parameters	3-4
		3.6.1	Bus Pullouts	3-4
		3.6.2	Bus Loading Area	3-6
		3.6.3	Passenger Amenities	3-6
		3.6.4	Shelter	3-6
		3.6.5	Bench	3-7
		3.6.6	Accessible Pad Location	3-8
		3.6.7	Curb and Sidewalk	3-8
		3.6.8	Signs	3-8
		3.6.9	Trash Receptacles	3-9
		3.6.10	Lighting	3-9
		3.6.11	Bicycle Parking	3-9
	3.7	Bus Sto	op Spacing	3-9
	3.8	Bus St	op Placement	3-10
Chap	ter 4 Ca	•	provement Plan	
	4.1	Introdu	ction	4-1
	4.2	Transit	Facilities Capital Improvement Plan	4-1
		4.2.1	Systemwide Improvements	4-2
		4.2.2	Bus Stop Conceptual Designs and Estimates	4-3
	4.3	Canital	Improvement Plan Financial Flement	4-6

	4.3.1	Potential Costs for Implementation of Near- and Long-Term Bus Stop Improvements	4-6
	4.3.2	Potential Capital and Operating Funding Sources	4-8
	4.3.3	Additional Funding Strategies and Approaches	4-11
Tables			
Table 2-1	Bus Stop ID Numbers2-1		
Table 3-1	AASHTO Bus Bay Dimensions3-2		
Table 4-1	Near-Term Systemwide Bus Stop Improvements by Type and Total4-2		
Table 4-2	Long-Term Systemwide Bus Stop Improvements4-		
Appendices	;		
Appendix A	Publi	c Survey Summary	
Appendix B	Public Meeting Display Boards		
Appendix C	Bus S	Stop Facility Inventory and Existing Conditions	
Appendix D	City o	of Clearlake Design and Construction Standards	
Appendix E	Lake	County Bus Stop Design Standards	
Appendix F	Syste	emwide Recommended Improvements at Individual Bus Stops	
Appendix G	Conceptual Design Plans and Cost Estimates for Three Primary Bus Stops		
Appendix H	Estim Bus S	nated Unit Costs for Systemwide Recommended Improvements at I Stops	ndividual

This page intentionally left blank

Chapter 1 Introduction

1.1 Plan Overview

The Lake Area Planning Council (LAPC) has been awarded a California Department of Transportation (Caltrans) Sustainable Transportation Planning Grant to develop a Bus Passenger Facility Plan (Plan) to identify a strategy and priorities for improvements to bus passenger facilities in Lake County. This Plan provides an overview of existing conditions, analysis of design standards to be adhered to for bus stop improvements, and an analysis and conceptual site designs for three priority sites, as well as estimated capital and operations costs.

1.2 Plan Organization

The Plan is composed of the following four chapters:

- Chapter 1 Introduction
 - o Provides an overview of the Plan and community outreach activities performed.
- Chapter 2 Existing Conditions
 - Presents a literature review of recent plans and policy documents that impact transit facilities in Lake County, and an inventory of existing Lake County bus stops that includes surrounding roadway conditions and safety features.
- Chapter 3 Design Standards
 - Presents the design parameters to be applied to this study, including sidewalk and bicycle facilities, bus pullout design, and passenger amenity design.
- Chapter 4 Capital Improvement Plan
 - Details the capital and maintenance needs of bus stops in the Lake County project area; the conceptual bus stop designs for key stop locations; and identifies available potential funding sources to implement the proposed improvements.

1.3 Community Outreach

1.3.1 Public Survey

LAPC invited riders, local jurisdictions, Caltrans, and other stakeholders to participate in the planning process. LAPC developed a Bus Passenger Facility Plan Public Survey, which was open from August 13, 2018 to September 28, 2018. The survey contained questions regarding riders' preferences and priorities related to on-time performance, number of bus stops, bus stop amenities, bus stop locations, and bus stop safety improvements. The survey received 169 total responses; a summary of responses is included in Appendix A.

1.3.2 Community Workshops

In addition, LAPC held two public workshops on September 18, 2018 in the City of Lakeport, and September 27, 2018 in the City of Clearlake. The meetings provided an opportunity for interested stakeholders to learn more about the project, visit display stations, take the survey, and submit their comments and responses. Meeting materials from these workshops are provided in Appendix B.

Chapter 2 Existing Conditions

2.1 Introduction

The purpose of this chapter is to present background and existing conditions information regarding transit passenger facilities in Lake County, California, served by the Lake Transit Authority (LTA). This includes:

- A review of existing plans and documents regarding transit passenger facilities
- A detailed inventory of existing bus stop conditions
- A summary of available existing data regarding passenger activity by stop

2.2 Literature Review

This section presents a summary of recent plans and other policy documents that impact the provision of transit passenger facilities in Lake County. These documents include the pertinent transit plans, roadway plans, bicycle/pedestrian plans, general plans, and community plans. Documents were particularly reviewed for any recommended changes to roadways or facilities impacting transit stops, as well as policies that address transit stops.

2.2.1 Lake Transit Hub Location Plan, 2017

The 2017 Lake Transit Hub Location Plan is a study geared towards siting a new and enhanced transit hub, replacing the existing transfer point at the former Ray's Food Place. It provides a summary of existing site conditions; an evaluation of potential project sites; and recommendations for a preferred site, alternative site, and back-up site for a new transfer hub. The plan identifies a preferred site at the county-owned property along the western side of Dam Road Extension south of South Center Drive. Two potential site designs include a corner option and a mid-block option.

There are two other sites that the document also identifies as having potential. The report prioritizes them as the "alternative" and "back-up" sites:

- The Old Airport Site (Site #1) (alternative site)
- The lot adjacent to the Burns Valley Shopping center (Site # 5) (back-up site)

2.2.2 Lake County Transit Development Plan and Marketing Plan, 2015

The primary purpose of the *Transit Development Plan and Marketing Plan, 2015* (TDP) is to guide the development of Lake Transit services to provide improved mobility for Lake County residents and visitors over a 5-year period. This document also includes a marketing plan. The document notes that the expanded Route 1/8 schedule, with additional runs to North Shore and

expanded evening service, was implemented in January 2015. The TDP calls for provision of schedule information panels in FY 2015/2016 at the following key passenger activity centers:

- Clearlake
 - Ray's
 - Lakeshore & Old Highway 53
 - Austin Park/City Hall
 - Burns Valley Mall
 - Yuba College
- Lakeport
 - o 3rd & Main
 - Mendocino College
 - o Kmart
- Sutter-Lakeside Hospital
- Middletown Highway 29 & Young Street
- Kit's Corner

In FY 2017/2018, the plan calls for the elimination of Route 5 and termination of Nightrider service.

The discussion on stakeholder outreach noted that the bus stop improvement at St. Helena Hospital needs to be a partnership between St. Helena Hospital and Lake Transit. The document noted, "there are expensive improvements required to both the bus stop itself as well as an ADA-compliant path from the bus stop to the entrance of the Hospital."

Long-term improvements that include route expansions (and potentially require new bus stops) are:

- Extending Route 1 to Konocti Vista Casino, which would include the elimination of Route 8 (to be replaced with a local community service route), and extension of Route 1
- Possible expansion of Route 1 to Cache Creek Casino
- Consider connecting Lake Transit to Santa Rosa and Cloverdale

Improvements to bus stops was a major theme raised at the interviews and focus groups. Identified needs included the following:

- Many bus stops are not signed.
- There is a need for posting of route destinations and departure times at bus stops.
- High-volume stops need benches and shelters.
- Bus stop spacing needs to be closer for seniors or people with disabilities, it is hard to get to the bus stop. Also, sidewalks are needed.
- The bus stop at Clearlake St. Helena Hospital is in need of upgrade. The bus stop is just a patch of dirt with no pad, bench, or shelter. There is just a broken sign. Hospital has a shelter they would provide for installation. Improvements to this stop need to be a

collaboration between Lake Transit and St. Helena Hospital. In addition to access improvements, there is a need for improvements from the bus stop to the door of the hospital.

- Bus stop at St. Helena Clinic in Clearlake. A doctor has requested the bus enter the parking lot and come up to the door of the clinic.
- Job Zone bus stop has high usage and no amenities.

In the financial plan, the complexities of addressing bus stop improvements was mentioned, noting that in many cases, drainage and right-of-way issues need to be addressed to determine whether a bus stop can be upgraded to American with Disabilities Act (ADA) Paratransit standards. A map provided in this plan shows the relative usage of different bus stops.

2.2.3 Lake County 2014-2015 Coordinated Public Transit – Human Services Transportation Plan

The Coordinated Public Transit – Human Services Transportation Plan (Coordinated Plan) focuses on serving transportation-disadvantaged populations, and is linked to three grant programs: Job Access and Reverse Commute; the Enhanced Mobility of Older Adults and Individuals with Disabilities capital program; and the New Freedom grant program. A key theme identified by stakeholders is that bus stop signage, amenities, and path-of-access concerns limit riders' access to and knowledge of existing Lake Transit services. Detailed comments on this theme are summarized in the *Transit Development Plan and Marketing Plan, 2015.*

The Coordinated Plan includes the following projects:

- 1.1.3 Seek funding for and implement a bus stop improvement program of improved stop signage, bus stop amenities (including shelters and lighting) and paths of access that support the mobility needs of older adults, persons with disabilities and persons of low-income.
- 3.2.1 Identify special needs stop improvement projects within Lake County, such as at Clearlake St. Helena Hospital, which will help Coordinated Plan target groups to better and more safely use Lake Transit for medical trip purposes.

This plan identifies the need to improve the signage and information provided at Lake Transit bus stops. At a minimum, each stop should have a clear sign identifying that it is indeed a bus stop. Furthermore, Lake Transit should provide information regarding which buses service each stop, and scheduling information at—most if not all—bus stops.

2.2.4 Lake County Transit Energy Use Reduction Plan, 2015

The plan identifies the following recommendations to reduce Lake Transit's energy use:

- Implement indoor and outdoor light replacements and ultraviolet film installation¹
- Investigate feasibility of solar installation (in form of bus canopy at current facilities)
- Acquire four electric buses (and associated charging station)
- Investigate feasibility of full or partial conversions to propane and/or natural gas

2.2.5 Lake County Transit Development Plan Study, 2008

The 2008 Lake County Transit Development Plan identifies issues in the community regarding transit, determines the public's need for service, considers the strengths and weaknesses of the current transit service, and defines solutions to improve transit in Lake County. The plan recommends financially constrained and financially unconstrained alternatives:

Financially Constrained

- Implement a three-route Clearlake Service to improve service quality
- Expand Route 3 by adding two more runs daily to serve commuters and improve connections to intercity services

Financially Unconstrained

- Implement a local fixed-route in Lakeport
- Expand Route 1 during commute hours
- Support Senior Transportation Programs in coordination with the Social Services Transportation Advisory Committee

2.2.6 Transit Passengers Facilities Development Plan for Lake County, 2006

The *Transit Passengers Facilities Development Plan* provides transit improvement standards appropriate to the specific conditions of the LTA service area. The standards are intended to guide government agencies, commercial and residential developers, employers, and others in their efforts to provide attractive and safe transit facilities for the County's transit patrons. The plan also presents a recommended program of transit passenger facilities improvements. This program was based on an extensive inventory of existing stops throughout Lake County, a review of existing traffic conditions, the pertinent elements of the ADA, and findings regarding the most effective overall strategy for improving the quality of service provided to LTA's passengers.

¹ The project has since been completed.

The plan identifies design guidelines for the following categories:

- Bus stop area, bus landing pads, and accessible paths
- Bus stop spacing
- Bus stop placement
- Bus pullouts
- Signs
- Passenger amenities (shelters, benches, trash receptacles, lighting, bicycle parking)
- Park-and-ride/multimodal facilities
- Turning radii

The plan also identified a priority implementation list for each community area based on various factors, including the presence and condition of a bus stop sign, safety, traffic volumes on the adjacent roadway, and boarding and alighting counts at each stop. These factors were used to prioritize bus stop facility improvements. A detailed list of priority bus stops and recommended improvements is included in the plan. In addition, for each community, there is a list and/or map showing which bus stops require signage, improved accessibility, pullouts, street furniture, and bus landing pads.

2.2.7 SR 53 Corridor Studies (TJKM-2011 and Caltrans-2014)

The study, completed in 2011 by TJKM, notes that a 4-lane freeway/expressway along State Route (SR) 53 would be necessary to accommodate the increased traffic volumes by approximately 2028. A *Caltrans Transportation Concept Report* (TCR) was completed in March 2014 to further define this project. Recommendations identified in the TJKM study that could impact transit stops include:

Year 2020 – Minor Improvements:

- SR 53/Olympic Drive: signalize intersection and add eastbound right-turn lane.
- SR 53/40th Avenue: add northbound left-turn lane.
- SR 53/Dam Road/Old Highway 53: add northbound right-turn lane.
- Dam Road Walmart Driveway: add roundabout control and a northbound left-turn lane.

Year 2020 – Major Improvements:

SR 20/SR 53 Roundabout: improve intersection with roundabout.

Year 2030 - Minor Improvements:

- SR 53/40th Avenue: add eastbound and westbound left-turn lanes and a northbound left-turn lane.
- SR 53/18th Avenue: add east and westbound left-turn lanes and a northbound right-turn lane.

- SR 53/Dam Road/Old Highway 53: add northbound left-turn lane and westbound rightturn lane.
- Dam Road/Walmart Driveway: add eastbound left-turn lane.
- SR 53/SR 29/Main Street: add southbound right-turn lane.

Year 2030 - Major Improvements:

- Yuba College Access Road Tight Diamond Alternative (preferred alternative); or
- 18th Avenue/SR 53 Tight Diamond Interchange (acceptable but not preferred).

The Caltrans *Transportation Concept Report* also identified a "Tight Diamond Interchange" at Route 53 and Center Drive as a promising alternative location for an interchange.

2.2.8 Transportation Concept Report (TCR) Route 20 East

The TCR for Route 20 East identifies a facility concept for the four different segments of the roadway, defined as:

- Segment 1 Junction US 101 to the Mendocino/Lake County line
- Segment 2 Mendocino/Lake County line to Junction SR 29
- Segment 3 Junction SR 29 to Junction SR 53
- Segment 4 Junction Route 53 to Lake/Colusa County line

The facility concept for Segments 1 and 2 is a 4-lane freeway or expressway. The facility concept for Segment 3 is a 2-lane conventional highway. Additional Complete Streets treatments may be necessary in communities along Route 20 East. The facility concept for Segment 4 is a 2-lane conventional highway with passing lanes.

2.2.9 Transportation Concept Report Route 29

The Caltrans TCR for Route 29 noted that in 2013, a project to widen an 8-mile stretch of Route 29 (LAK-29-23.80/31.60) between Lower Lake and Kelseyville was programmed. An Environmental Impact Report has subsequently been prepared, and funding for the initial phase of construction is included in Caltrans' *Draft 2018 Interregional Transportation Improvement Program*.

2.2.10 Lake County General Plan, 2008

The Lake County General Plan includes a Transportation and Circulation section establishing the goals, policies, and implementation programs covering Roads and Highways, Public Transportation, Aviation, Bicycle and Trails, Transmission Lines and Pipelines, Boating, and Implementation Measures. The policies under the goals for each section are general policies that support the safe and efficient use of the different transportation facilities. There is also a set of implementation measures related to coordination among agencies, maximizing funds and

developing public outreach processes. There are no roadway or transit projects specified. One policy related directly to the provision of transit:

Policy T-2.3 Support Transit within the Regional Transportation Plan – The County should support the list of priorities for development of transit services outlined in the Regional Transportation Plan and Transit Development Plan. Efforts should be directed first towards: encouraging new and improving existing transportation services for the elderly and disabled; serving the high density areas of Lakeport and Clearlake; providing intercommunity services around Clear Lake; and supporting efforts to expand intercity transit carriers, particularly to Ukiah and the Central Valley.

2.2.11 Lake County Regional Transportation Plan, 2017

The Lake County Regional Transportation Plan covers a 20-year horizon with an overall goal of promoting the safe and efficient management, operation, and development of a multi-modal transportation system that, when linked with appropriate land use planning, will serve the mobility needs of people and goods movement throughout the region. The plan identifies roadway, transit, bicycle and pedestrian, and other transportation projects. There are several policies related to transit or transit stops:

- 2.1 Coordinate with local agencies and organizations (including the Social Services
 Transportation Advisory Council (SSTAC) and Lakeport's Disability Advisory Committee)
 to identify needs and opportunities to improve services and facilities
- 3.1 Support implementation of the Transit Passenger Facilities Development Plan
- 3.2 Coordinate with local agencies, organizations and businesses to improve and install transit passenger facilities, including bus stop, turnouts, benches and shelters along existing and new routes
- 3.7 Improve streets and road conditions, including drainage, along transit routes

2.2.12 Lake County Active Transportation Plan, 2016

The Lake Area Planning Council developed the *Active Transportation Plan* in coordination with the County of Lake, the City of Lakeport, the City of Clearlake, and the LTA. The plan provides a regional vision for improving and integrating the bicycle and pedestrian network, including a list of planned projects, and a description of how bicycling, walking, and transit support each other.

2.2.13 Middletown Community Action Plan, 2014

The following is a list of future improvements on SR 29 through the downtown area of Middletown identified in the *Community Action Plan* that could impact transit stop planning or improvements, as contained in the SR 29 South Corridor Engineered Feasibility Study. Lake Transit's Route 3 traverses Highway 29 in Middletown.

Future Improvements

- Shoulder Widening and Center Left-Turn Lane from Wardlaw Street to Butts Canyon Road
- Bike Lanes, On-Street Parking, and Sidewalks from Douglas Street to Lake Street
- Sidewalk Bulbouts and Decorative Crosswalks at Callayomi Street, Douglas Street, Armstrong Street, Main Street (SR 175), Young Street, and Wardlaw Street
- Sidewalk from Wardlaw Street to Bible Church Driveway (west side)
- Eastbound and Westbound Left-Turn Lanes at Main Street (SR 175)
- Roundabout at Wardlaw Street
- Roundabout or Traffic Signal at Butts Canyon Road

There are also improvements to improve school safety and traffic:

- Southbound right-turn lane at the Wardlaw Street/SR 29 intersection
- Closure of driveway on Wardlaw Street just west of SR 29
- Revisions to on-campus student drop-off areas
- Revisions to driveway access directions (i.e., inbound and outbound)

Sidewalk bulbouts and decorative crosswalks are included at the following locations on SR 29 in the downtown plan:

- Callayomi Street
- Douglas Street
- Armstrong Street
- Main Street (SR 175)
- Young Street
- Wardlaw Street

Sidewalks are proposed on the following streets where there may be bus stops:

- SR 29 Wardlaw Street to Bible School Driveway (west side)
- SR 29 Young Street to Callayomi Street (various locations west and east sides)
- Wardlaw Street SR 29 to Washington Street (south side)

New paved on-street parking is planned for:

SR 29 – Douglas Street to Lake Street (west and east sides of highway)

The downtown plan includes the following bike facility improvements that coincide with the bus routes:

- Calistoga Street (SR 29) Wardlaw Street to Hill Street (Class II bike lanes)²
- Main Street (SR 175) Santa Rosa Road to Washington Street (Class III bike route)

Streetscape improvements have been identified to create a sense of place in the downtown area.

These streetscape improvement areas include improvements to both existing sidewalk corridors and new streetscape zones. These high-priority projects are as follows:

Existing Sidewalk Corridors

Calistoga Street (SR 29) – Wardlaw Street to Armstrong Street

New Streetscape Zones

- Calistoga Street (SR 29) Armstrong Street to Lake Street
- Main Street (SR 175) Washington Street to Barnes Street

Streetscape improvements in these areas would consist of the following:

- Wide Sidewalks Zones
- Decorative Street Lighting
- Street Trees
- Benches
- Banners on Street Lights
- Commemorative Street Tree Covers

Transit Improvements

New sidewalks along the southern side of Douglas Street are also included in the plan to connect the new transit stop to the Senior Center. The fixed-route bus routes that would service this location include buses from Hidden Valley, Cobb Mountain, and housing areas along SR 29 south of Middletown. Parking on SR 29 adjacent to the existing northbound transit stop at the Hardester's Market should be removed to allow buses to stop adjacent to the curb. Additional new northbound and southbound transit stops are recommended at or near the following locations:

- SR 29 at Wardlaw Street (southern side)
- Bush Street and Hill Street (across from park and ride)
- Central Park Road (adjacent to Calpine Center)

There are also improvements planned south of downtown, including shoulder widening on SR 29 from Dry Creek cut-off to Lake Street to accommodate bicycles.

² For downtown concept plan Option A only.

2.2.14 Highway 20 Traffic Calming and Beautification Plan, 2005

The purpose of the *Highway 20 Traffic Calming and Beautification Plan* as it passes along the northern shore of Clear Lake is to facilitate and encourage improvements that help realize the community's vision for the Highway 20 Corridor. The study is conceptual in nature, and focuses on improving the overall appearance, as well as establishing a strong mix of traffic calming measures to create a more pedestrian-friendly "main street" feeling than a thoroughfare. The plan outlines beautification elements for various segments of road through each community along Highway 20, identifying elements like striped crosswalks, in-pavement crosswalk light installation, bulbouts, pedestrian islands, shorter median segments, streetlights in the commercial core, and bus stop improvements at the busiest transit stops.

The Highway 20 Northshore Traffic Calming Plan and Engineered Feasibility Study project will evaluate the needs, priorities, and feasibility of traffic calming measures through four lakefront communities along Clear Lake's north shore: Nice, Lucerne, Glenhaven, and Clearlake Oaks. It is intended in part as an update to the 2005 Highway 20 Traffic Calming and Beautification Plan, although its primary purpose is to analyze current conditions and formulate traffic calming projects, including bicycle-, pedestrian-, and transit-friendly options to improve the attractiveness and overall livability of the area.

2.2.15 Lake County Area Plans

Lake County has developed a series of eight area plans that complement the General Plan. Each Area Plan allows for refined planning decisions based on community values and priorities of the residents of that planning area. The Area Plans address natural resources, public safety, and community development. Most of the Area Plans make little mention of transit, or cite documents already summarized here. Specific mentions of transit and bus stops include:

Lakeport Area Plan

- Policy 5.3.1.b: Encourage bus stops along arterials and Rural Minor Collectors in the planning area to facilitate public transit use
 - Implementation Program: Encourage Lake Transit Authority to build bus stops/shelters and place signs

Middletown Area Plan

• Policy 5.3.3b: Encourage bus stops near population centers in the Planning Area to facilitate public transit use

Rivieras Area Plan

- Policy 5.3.2b: Encourage bus stops near population centers in the planning area to facilitate public transit use
 - Implementation Program: Encourage Lake Transit Authority to build bus stops/shelters and place signs

2.2.16 City of Clear Lake General Plan, 2017

The City of Clear Lake General Plan has a goal to have a high-quality transit system that serves the needs of all residents. Related policies and objectives include:

- Objective CI 3.1
 - o Develop and maintain adequate transit facilities throughout the City
- Policy CI 3.1.1
 - The City should encourage Lake Transit Authority to maintain safe and widely accessible transit facilities
- Program CI 3.1.1.1
 - The City should encourage Lake Transit Authority to extend the hours of service and improve service frequency for the transit system

2.2.17 City of Lakeport General Plan, 2009

The plan has the following relevant policies related to transit:

- Policy T 34.1: Design Guidelines for Public Transit. The City will coordinate with Lake Transit Authority and establish design guidelines for residential and commercial development to facilitate future public transit service.
 - Program T 34.1-a: The City will coordinate with Lake Transit Authority and establish design guidelines in the Zoning Ordinance to facilitate the future public transit service. Consider identifying areas for the location of future bus stops, right-of-ways for bus turnouts, and facilities in high density residential developments to facilitate future use of public transit.
 - Responsibility: Community Development and Public Works Departments

2.2.18 Lakeshore Drive Downtown Corridor Plan, 2014

The Lakeshore Drive Downtown Corridor Plan (Corridor Plan) provides a set of specific design recommendations and potential projects for Lakeshore Drive that may be implemented through future planning efforts. The Corridor Plan notes that Lakeshore Drive is served by three transit routes with high ridership. Currently, bus stop amenities—such as benches, shelters, landing pads, and signage—are limited. Buses often must block the shoulder used by pedestrians and bicyclists to drop off and pick up riders.

This plan focuses on how to provide bike lanes, sidewalks, and on-street parking with a variety of patterns such as back-in versus head-in versus parallel parking. Specific to transit, the plan identifies the following needs:

• Stop Spacing — Most of the stops are roughly ¼-mile apart, which is the recommended distance that best balances pedestrian access against transit efficiency and tends to minimize travel times for the greatest number of users. The exception is the spacing

between the stops at Howard and Golf. Eastbound there is only one stop at Java Express, which is too close to Golf and too far from Howard. Westbound there are two stops, one at Java Express and one at Burger Time. Here the spacing is slightly too dense for optimal transit efficiency. Lake Transit might consider relocating the eastbound stop to Williams Jewelry on the south side of Lakeshore Drive, as this would put the stop roughly equidistant from the stops on either side. Lake Transit might also consider consolidating the two westbound stops into a single stop outside One Stop Automotive.

• Stop Amenities — Lake Transit has identified several places to make access improvements for passengers. Their focus on providing concrete landing pads to accommodate wheelchair loading/unloading is particularly welcome. These landing pads should ideally be connected by a sidewalk to the nearest crosswalk – for example the eastbound stop at Nott's Liquor has neither a sidewalk nor a landing pad.

Under "Policies and Programs," the *Corridor Plan* calls for updating the transit ridership survey to prioritize bus stop improvements.

2.3 Lake Transit Lake County Bus Stop Facility Inventory

LTA operates ten transit routes (1, 2, 3, 4, 4a, 7, 8, 10, 11, and 12) in Lake County, and connecting routes to Ukiah in Mendocino County (Route 7) and Calistoga in Napa County (Route 3). Bus stop amenities have a large degree of variation between stop locations. Although some stops have bus shelters, large bus bays, and wheelchair loading pads, others are not even identified with a sign. The project team conducted an inventory of bus stop facilities in Lake County with the assistance of Lake Transit staff between May 26 and May 28, 2018. Stops along all ten routes were surveyed. The stops outside Lake County are included in the inventory for informational purposes, but are not included in the summary, because they are not the responsibility of local Lake County jurisdictions. Flex stops, which are only serviced when called or specially requested, were also not included in this study.

Lake Transit staff drove a surveyor to each bus stop. This was done to ensure that the location of each bus stop was accurate. At each bus location, several pictures were taken, and the stop was evaluated for the following amenities and conditions:

- Amenities Presence and condition of:
 - o Sign
 - o Pole
 - o Bench
 - o Shelter
 - Shade

Setting/Roadway Condition:

- Presence of bus bay and pavement
- Presence of raised curb and ramps
- Presence of sidewalk
- Presence of wheelchair pad
- Number of travel lanes

Speed limit of roadway

Safety:

- Presence of cross walk
- Presence of a trip generator across the street that would generate pedestrian crossing activity
- Presence of lighting at bus stop
- Driver sight distance
- Overall identification of safety issues

2.3.1 List of Bus Stops

The tables included in Appendix C provide a comprehensive database of all bus stops that were evaluated. These include not only the major time point locations listed in the published schedule, but also the lesser stops along each route. The bus stops organized by route can be found in Appendix C, Table C-1. Each stop was given a stop identification number (ID). The stop ID numbers are based on route number and direction of travel. The first two-digit number represents the route and direction of travel. The second two-digit number (represented by the "xx" below), is the individual stop number, in the order which they appear. The stop ID numbers are correlated to the routes as shown in Table 2-1.

Table 2-1 Bus Stop ID Numbers

Route	ID	Route	ID
1 WB	10.xx	7 WB	70.xx
1 EB	11.xx	7 EB	71.xx
2 SB	20.xx	8 NB	80.xx
2 NB	21.xx	8 SB	81.xx
3 SB	30.xx	10	100.xx
3 NB	31.xx	11	110.xx
4 WB	40.xx	12	120.xx
4 EB	41.xx		
4A WB	50.xx		
4A EB	51.xx		

Because the routes share many of the same stop locations, many bus stops on the lists by individual routes are duplicated. These duplicated or shared stops were then combined. However, it should be noted that if a stop location provides service on both sides of the roadway (in both directions), it is considered two individual stops. A master list of bus stops was created that takes into account shared stops, as well as stops on opposite sides of the road. This list can be found in Appendix C, Table C-2. The original or historical name of each stop is retained, which typically describes the landmark or business the stop is in front of. Once the shared stops were eliminated, a total of 311 unique bus stops was tallied, of which 304 are in Lake County, 4 in Mendocino County, and 3 in Napa County.

Existing passenger boarding counts were obtained from LTA. Boarding and alighting values were collected for Routes 1, 2, 3, 4, and 7 for three months (July 2016, October 2016, and March 2017). Data for Routes 8, 10, 11, and 12 were drawn from the three months of May through July 2015. The proportion of total ridership at each stop in each route was then identified, and factored by the total average daily ridership by route for Fiscal Year 2017-2018, to provide the best available estimate of boardings by stop for the most recent fiscal year. Note that these estimates reflect stops in Lake County only.

These counts were conducted for route segments that contained generally 2 to 13 stops per segment. It is therefore not possible to specify passenger boarding figures for each stop, except for a very few key stops. The project team used the available data to categorize passenger activity based on the data; and considered the transit trip generators served by each stop, and evidence of use at specific stops. An estimation of low, medium, or high ridership was then assigned to each bus stop. In general, the low category corresponds to 7 or fewer passenger boardings per day, the medium category corresponds to 8 to 15 boardings per day, and the high category to more than 15 daily boardings. Table C-2 presents the overall relative passenger activity over all routes serving each stop, and Table C-5 (discussed below) provides the relative ridership by individual route. Overall, 4 stops are considered to generate relatively high ridership, 33 a medium level of ridership, and 267 a low level of ridership.

2.3.2 Data Organization

Each bus stop was evaluated on site for the amenities and conditions. Although some of the data can be provided as a simple yes or no, the passenger amenity condition data fields are provided by an A through F rating system (Appendix C, Table C-5). As with the typical A through F rating conventions, A's and B's are good, whereas D's and F's are poor. C is acceptable; and in fields where condition of amenities is evaluated, C ratings were applied to note elements with noticeable wear, graffiti, or slight damage, but that are still functional.

Field notes were then organized and compiled electronically into a spreadsheet. In some cases, the A through F field ratings were then evaluated and simplified into a "yes or no" or "good, acceptable, or poor" result, as discussed below.

The results were then organized and presented by route in three categories:

- Location Information, as shown in Appendix C, Table C-3
- Roadway Conditions, as shown Appendix C, Table C-4
- Passenger Amenities, as shown in Appendix C, Table C-5

Locations

The location tables (Appendix C, Table C-3) document the physical location of each stop, and include the following fields: area, street, cross street, and Global Positioning System (GPS) coordinates.

Roadway Conditions

The roadway conditions table (Appendix C, Table C-4) includes fields related to the orientation of the bus stops relative to the roadway. A discussion of each of the surveyed fields follows:

- Lanes Total number of lanes on the road where the bus stop is located. An odd
 number of lanes typically includes a center turn lane or a two-way left-turn lane. In a few
 instances, only one lane is recorded. This occurs on small, narrow rural roads where no
 center striping is marked.
- Speed Limit –The speed limit is typically recorded based on the observed posted speed limit. Often, the speed limit is not posted, and an estimate of typical vehicle speeds is recorded.
- Can Bus Pull Out of Travel Lane –The results of this field have been simplified to a Yes or No answer. In the event that the bus can partially pull out of the travel lane, the surveyor determined if the bus can pull far enough out of the travel lane to not interfere with or block traffic. Overall, 69 percent of stops allow the stopped bus to not block a travel lane. Note that it is typically considered to be acceptable for buses to block travel lanes if 1) the traffic levels on the street are relatively low; 2) there is no driver sight distance problem; and 3) the passenger activity is relatively low.
- Trip Generator Across the Street/Crosswalk Pedestrian safety at bus stop locations is a major concern, particularly when the transit trip generator requires the passenger to cross a major street. This field records if there is a trip generator or clear reason why a pedestrian would want to cross the street. The presence of a crosswalk at or near the bus stop is recorded. It is up to the surveyor's discretion whether to record a Yes or a No in this field, based on the distance from the crosswalk and the various nearby land uses. Overall, 39 percent of stops were found to have a transit trip generator on the opposite side of the street; of these, 65 percent did not have a designated crosswalk.
- **Driver Sight Distance** The sight distance ratings of good, acceptable, and poor reflect several forms of sight distance evaluations. The two primary concerns are: 1) if the bus driver has adequate sight distance, as they pull back onto the travel lane, to see oncoming vehicles with enough time to avoid a crash; and 2) if oncoming drivers have adequate sight distance to avoid a collision with a bus as it pulls back onto the roadway. Windshield surveys were performed to evaluate sight distance evaluations; however, they were not performed according to the California Department of Transportation (Caltrans) standards. Additional considerations were made for vehicles turning out from side streets, driveways, and parking lot aisles. In total, 72 percent of stops were found to have good sight distance in all directions; 18 percent were found to have acceptable sight distance; and 10 percent were found to have poor sight distance in one or more directions.

Passenger Amenities

The passenger amenities inventory can be found in Appendix C, Table C-5. A discussion of each of the surveyed fields follows, and is summarized in Appendix C, Table C-6:

- Signs The identification of bus stop locations with a Lake Transit sign is the most basic amenity provided to transit users. A sign allows new users to the transit system to locate bus stops that are not time-point locations listed on the schedule. It also helps passengers to know where to wait, bus drivers to know where to stop, and provides a marketing function by providing a "presence" on the street. The A through F ratings for signs were determined as follows: A's and B's are good, C is acceptable (i.e., sign is heavy faded), D reflects damage or vandalized with graffiti and should be repaired or cleaned, and an F rating indicates that the sign needs to be replaced. Exactly half of the individual stops were found to be signed. Of these, most (81 percent) were in relatively good (A or B) condition. A total of 9 percent of the signs was found to be substantially blocked from view by vegetation.
- Sign Mounting Poles Transit stop signs were found mounted on individual poles, poles shared with other signs, and directly affixed to the side of buildings or fences. The A through F ratings for poles were determined as follows: A-good condition, B-loose pole, C-bent or slightly damaged, F-extremely bent or out of the ground and requiring replacement. Some poles/signs were suspected of being been cut and stolen. Poles were found at 48 percent of the stops. Of these, 94 percent were found to be in good (A or B) condition.
- Benches Most benches were found inside a shelter or provided as part of an adjacent business. Makeshift benches or seating provided by local residents who frequent the bus stops were not included in the evaluation. The A through F ratings for benches were determined as follows: A's and B's are good, whereas D's and F's are poor. C is acceptable; this rating was assigned to note noticeable wear, vandalized with graffiti, or slight damage, but still functional. A total of 65 stops (21 percent) was found to have benches, with 87 percent in good (A or B) condition; however, 11 percent were in poor (D) condition. Of the total number of benches, 44 are provided by Lake Transit (31 in shelters and 13 without a shelter).
- Shelters Lake Transit–provided shelters are prefabricated metal-framed units with either Plexiglas or corrugated metal panels. Shelters at business locations are often a covered walkway along the building. The A through F ratings for shelters were determined as follows: A's and B's are good, whereas D's and F's are poor. C is acceptable; this rating was assigned to note noticeable wear, vandalized with graffiti, or slight damage, but still functional. Shelter is provided at a total of 58 locations, including 31 shelters provided by Lake Transit, and 27 other locations where shelter is available. Many of the shelters (55 percent) are in very good (A) condition, but 6 are in poor (D) condition, and one is in F condition.
- **Street Lighting** Ambient street lighting is important for personal security reasons, given that Lake Transit hours of operation extend into the winter evenings. Only 21 percent of

- stops were considered to have a streetlight close enough to provide the ability to discern the presence of other persons at a stop in the dark.
- Wheelchair Accessibility –ADA guidelines state that a 5-foot (parallel with the bus) x 8-foot (perpendicular to the bus) hard surface pad is required for wheelchair loading. Wheelchair accessibility is recorded as a Yes or No to indicate whether a wheelchair or mobility scooter can load/unload at the bus stop. Lake Transit staff noted that in some instances, an ADA pad is not adequate to load a large mobility scooter due to space constraints involving maneuvering and ramp placement. In other instances, where a pad does not exist but the bus stop resides at a large, level area of firm dirt with drainage, wheelchair accessibility is noted as being available. Just under half of all stops (47 percent) were found to have an adequate wheelchair loading area. Note that this assessment is based on a simple observation only, and did not include quantitative evaluation of design details such as slope. Therefore, it should not be considered a definitive evaluation of whether specific stops meet the full requirements of the ADA. In addition, many stops have a nearby opportunity to board a wheelchair not specifically at the stop (such as at a nearby driveway), which is not reflected in this inventory.
- Shade Given the warm, sunny climate of Lake County, the presence of shade at bus stop locations is important to passengers. Trees and buildings at some stop locations provide shade, while bus shelters provide shade at others. In some instances, a shelter was provided, but adequate shade was not guaranteed. Due to the angle of the sun and the relatively small covering of a shelter, transit users could be exposed to direct sunlight while in a shelter. The availability of shade was rated with an A through F scale as follows: A-Abundant natural shade; B-Partial shade or shelter; C-Some, but not ideal; D-Shade available nearby; F-no shade. A wide range of conditions was found at the various stops, with 23 percent of stops having no opportunity for shade, and 48 percent with good (A or B) shade conditions.

This page intentionally left blank

Chapter 3 Design Standards

3.1 Introduction

This chapter presents design parameters to be applied in the Bus Passenger Facility Plan regarding the design of bus stop improvements. Sidewalk and bicycle facilities are first discussed, followed by a discussion of bus pullout design and passenger amenity design. Finally, bus stop spacing and location factors are discussed.

3.2 Minimum Sidewalk and Bicycle Facility Parameters

3.2.1 Sidewalks

Americans with Disabilities Act Standards

All facilities must conform to the standards required by the ADA, as well as the associated *Proposed Guidelines for Pedestrian Facilities in the Public Right-of-Way* published by the United States Access Board.

ADA sidewalk widths require a minimum of 4 feet of width. Where sidewalks are less than 5 feet in width, a passing area at least 5 feet long and 5 feet wide is required at least every 200 feet. Any drop greater than 0.5 inch and any surface steeper than 1:20 (5 percent) requires a ramp.

Obstacles that protrude into the access path might restrict wheelchair movements. Obstacles that are higher than 27 inches or lower than 80 inches may cause problems for a person with a vision impairment, who may not be able to detect an obstacle with a cane.

Local Standards

The City of Clearlake standards call for a minimum sidewalk width of 4.5 feet adjacent to roadways, or 5 feet minimum if detached.

State Standards

The Caltrans Highway Design Manual (September 22, 2016 revision) indicates the following regarding sidewalk width (Section 105.2): "The minimum width of a sidewalk should be 8 feet between a curb and a building when in urban and rural main street place types. For all other locations the minimum width of sidewalk should be 6 feet when contiguous to a curb or 5 feet when separated by a planting strip."

Caltrans has also adopted standards to implement the ADA requirements, as documented in *Design Information Bulletin 82-05: Pedestrian Accessibility Guidelines for Highway Projects.* These parameters are consistent with those of the ADA.

3.2.2 Bicycle Facilities

Bicycle Iane (Class II) width is governed by the California Highway Design Manual (December 15, 2016), for all public streets, which states (Section 301.3) that:

The minimum Class II bike lane width shall be 4 feet, except where:

- Adjacent to on-street parking, the minimum bike lane should be 5 feet.
- Posted speeds are greater than 40 miles per hour, the minimum bike lane should be 6 feet. or
- On highways with concrete curb and gutter, a minimum width of 3 feet measured from the bike lane stripe to the joint between the shoulder pavement and the gutter shall be provided.

3.3 Bus Pullout Design Parameters

Bus Pullout Design Specifications

The Caltrans *Highway Design Manual* defers to the American Association of State Highway and Transportation Officials (AASHTO) guidelines. These guidelines are presented in the *Guide for Geometric Design of Transit Facilities on Highways and Streets*, published in July 2014. They call for a minimum pullout width of 12 feet, with length dimensions as shown in Table 3-1.

Length in Feet Thru Speed **Entrance** Decel. Stopping Accel. (mph) **Taper** Area Lane **Exit Taper** Lane Total 30 5:1 min 50 None 3:1 max 130 min None 250 35 170 185 50 170 825 40 190 265 50 400 190 1095 45 700 210 360 50 210 1530

Table 3-1 AASHTO Bus Bay Dimensions

Source: Guide for Geometric Design of Transit Facilities on Highway sand Streets, AASHTO, July 2014

The Caltrans *Highway Design Manual* (December 16, 2016 revision) Section 626.4 indicates that concrete bus pads shall be a minimum of 4 feet wider than the width of the bus, and a minimum of 20 feet longer than the length of the bus. If the bus pad extends into the travel way, it should extend to the full width of the travel lane. The Highway Design Manual also refers the reader to the *Guide for Geometric Design of Transit Facilities on Highways and Streets* (American Association of State Highway and Transportation Officials, July 2014).

Other design specifications regarding the bus loading area are as follows:

• Curb heights should be no less than 4 inches and no more than 8 inches to minimize passenger falls when boarding or alighting from a bus.

- A minimum horizontal clearance of 2 feet should be provided between the curb and any obstruction (such as a bus stop sign).
- Trees should be trimmed at least 11.5 feet above the roadway pavement for the length of the bus stop.

3.4 Bus Stop Design Parameters

Minimum ADA Requirements for Bus Stops

Minimum ADA design implications for bus stop areas, bus landing pads, and accessible pedestrian access ways include the following¹:

- The ADA and associated regulations require that wheelchair loading pads be a minimum of 5 feet (parallel to roadway) by 8 feet (perpendicular to roadway). The grade perpendicular to the roadway cannot be more than 2 percent, while the grade parallel to the roadway should match the roadway grade. The surface shall be "firm, stable and slip resistant."
- Bus shelters must provide a clear space within the shelter for wheelchair users, with
 minimum dimensions of 2.5 feet by 4.0 feet (separate from other passenger seating and
 circulation areas). The opening to a shelter must be a minimum of 3 feet in width, and the
 minimum vertical dimension within a bus shelter is 6 feet 8 inches. The wheelchair pad
 and shelter must be connected with an accessible path, with a minimum width of 4 feet.
- A minimum clear passage width of 48 inches is recommended by the Access Board's guidelines for the public right-of-way. This is especially important next to a curb drop-off.
- An accessible route from the public transportation stops to the route that is accessible for both people with disabilities as well as for the general public.
- The *running slope* of the accessible pathway shall not be steeper than 1:20 while the *cross slope* shall not be steeper than 1:48 (2 percent).
- Parallel to the roadway, the slope of boarding and alighting area shall be the same as the roadway (to the maximum extent practicable). The maximum slope perpendicular to the roadway shall not exceed 1:48 (2 percent).
- The bus landing pad, when installed alone on a shoulder in a rural area, must be elevated 6 inches above road grade for safety and accessibility purposes.
- Stable, firm, and slip-resistant ground and floor surfaces.
- Grating spaces, or drainage grates, which are necessary for water drainage, should be
 no greater than 9.5 inches long in one direction. Spaces longer than this would impede
 the use of a wheelchair.

All paths from the bus stop to major destinations should be examined for obstacles that may interfere with access to or from the stop. Obstacles that protrude into the access path might

-

¹ADA Accessibility Guidelines for Buildings and Facilities (ADAAG).

restrict wheelchair movements. Obstacles that are higher than 27 inches may cause problems for a person with a vision impairment, who may not be able to detect an obstacle with a cane. Despite their training, it may be possible that a guide dog or other service animal may lead a person with vision impairment off of the path to get around the obstacle. Even though it may not be generally considered the responsibility of the transit agency to address accessibility problems along the entire access path, the agency staff should keep in mind that an obstacle may make a path inaccessible for potential patrons who have disabilities.

Local Standards

The City of Clearlake design standards are presented in the *Design and Construction Standards* (Revised June 2012) in Appendix D. In sum, these standards call for a concrete bus pad 10 feet in width by 50 feet in length, with 60 feet of transition on either side of the bus stop location.

Lake County's adopted bus stop design standards are presented in Appendix E. They are consistent with the City of Clearlake's standard. In addition, Chapter 19, Article IV Section 19-34.1 of the County Code identifies specific bus stop locations in the unincorporated county, and indicates that "The Road Commissioner is hereby authorized and directed to provide for the designation of said bus stops by painting the curbs or by clear markings or signs that areas are designated as bus stops as authorized herein."

The City of Lakeport is currently developing a comprehensive set of design standards. In the interim, the City relies on the Caltrans *Standard Plans and Standard Specifications (May 2006)* in the design of most capital projects.

3.5 Lake Transit Authority

LTA does not currently have adopted design standards. The 2015 *Transit Development Plan and Marketing Plan For Lake County/City Area Planning Council* does not include specific standards or criteria for bus stops. However, it includes the results of a passenger survey, in which passengers gave the highest importance to "shelters at more bus stops," with 63 percent ranking this potential improvement as very important (5 on a scale of 1 to 5). This was followed by 61 percent that ranked "Bus stop sign with information" as very important.

3.6 Recommended LTA Design Parameters

Summarizing the discussion above, the following design parameters are recommended as standard for improvements to LTA stops throughout Lake County. Note that all pertinent ADA and ADAAG requirements apply to all elements.

3.6.1 Bus Pullouts

Bus stops may be designed with a pullout, which is a specially constructed area off the normal roadway section provided for bus loading and unloading that allows the transit vehicle to board and alight passengers in an area outside the traveled way.

Pullouts are appropriate where traffic conditions prohibit conventional on-facility placement of bus stops. Pullouts are also recommended in locations where it is likely to be hazardous for a bus to stop in the travel lane, and are provided primarily on high-volume and/or high-speed arterials. The decision to construct a bus turnout should include an evaluation of the impact on public transportation, as well as private vehicle operations. Too many or poorly designed bus pullouts can actually impede the performance of the transit system (and other vehicles), because buses may have greater difficulty pulling out into traffic. As with most improvements, pullouts should be coordinated between transit staff and the local jurisdiction.

For stops at low-speed, low-volume roadways without unusually high passenger activity, it is appropriate for transit buses to stop in the travel lane. This condition applies to many of the LTA stops off of the state highways or urban arterial roadways.

Based on design guidelines in various rural areas throughout the country, roadways adjacent to bus stops with a speed limit of 35 miles per hour or higher and a peak-hour volume of 250 or higher in the lane of travel warrant a bus turnout². Assuming a typical traffic pattern in which 10 percent of daily traffic occurs in the peak hour and daily volumes are balanced between the two directions, this corresponds to an average daily traffic volume of 5,000 for a two-lane roadway, and 10,000 for a four-lane roadway.

Pullouts are also appropriate in the following circumstances:

- When the potential for conflicts between transit and passenger vehicles warrants separation of the two. For example, a bus stop in a travel lane of a signalized intersection often requires a turnout to prevent the stopped bus from causing traffic to queue through the intersection.
- Under conditions with high or increasing bus or passenger volumes or on high speed roads.

Recommended bus pullout standards are as follows:

- 10-foot minimum width (can include gutter pan)
- Minimum of 60 feet of transition prior to bus stop
- 50-foot bus stop
- Minimum of 60 feet of transition beyond bus stop
- Red curb zone through all dimensions cited
- 50- to 100-foot radius on curb horizontal curves, except the curb radius immediately in front of the bus stop should be 25 to 50 feet
- Concrete pavement

²The Oregon Department of Transportation, *Design Guidelines for Public Transportation*, Chapter 12, 12-6.

3.6.2 Bus Loading Area

At a minimum, all new construction should include a concrete wheelchair pad 5 feet (parallel to curb) by 8 feet (perpendicular to curb), located to align with the lift/ramp location of all transit vehicles serving the stop. Slope parallel to the roadway shall match that of the roadway, while cross-slope shall not exceed a maximum of 2 percent.

3.6.3 Passenger Amenities

Passenger amenities are significant elements in attracting public transportation users. Shelters provide protection from the elements and benches add comfort; trash receptacles, lighting, bicycle parking facilities, and other amenities add convenience and safety. The recommended standards with respect to the need for furniture at a bus stop are as follows:

- 1. Less than 5 passengers boarding per day No furniture recommended
- 2. Between 5 and 9 passenger boardings per day Bench
- 3. 10 or more passenger boardings per day Shelter with Bench

Note that these standards consider only boarding activity, because passengers alighting from a bus usually do not use the street furniture. Other considerations may include the potential of a bench or shelter to attract additional riders based on surrounding activities.

A minimum horizontal clearance of 2 feet should be provided between the curb (if provided) or edge of pavement (if curb not provided) and any obstruction (such as a bus stop sign). Trees should be trimmed at least 11.5 feet above the roadway pavement for the length of the bus stop.

3.6.4 Shelter

A bus shelter provides protection from the elements, as well as seating. Typically, a shelter is constructed of clear side-panels for visibility and safety. Standardized shelters are available that accommodate various site demands and passenger volumes. Existing LTA shelters are typically 9 feet by 5 feet. In a few locations, such as transfer points, larger shelters or multiple shelters may be warranted. A typical transit standard is to provide a minimum of 10 square feet per person waiting at the stop at peak times.

Minimum ADA design implications apply to the installation of new or replacement bus shelters, and include the following:

- A minimum clear floor area of 30 inches by 48 inches, entirely within the perimeter of the shelter.
- Maintain shelter openings to be a minimum of 36 inches to allow a wheelchair to pass through.
- Bus stop shelters should be connected by an accessible route to the bus stop landing pad.

- Bus stop shelters should be connected by an accessible route to the bus stop landing pad.
- Bus stop shelters should not be placed on the wheelchair landing pad.
- General ADA mobility clearance guidelines should be followed around the shelter, and between the shelter and other street furniture.
- In addition to the number of boardings per day, other factors that LTA may wish to consider when evaluating the installation of a shelter include:
 - Climate (wind, rain, heat, etc.), which may lead to recommendations regarding whether or not to have side panels or the need for air circulation, heating, or cooling systems.
 - Vandalism (broken or scribed glazings).
 - o The number of transfers at a stop.
 - The availability of space to construct a shelter and waiting area.
 - The number of elderly individuals or people with disabilities in the area.
 - The proximity to major activity centers.
 - The frequency of service.
 - Adjacent land uses.

A shelter pad at least 16 feet (parallel to the travel lane) by 6 feet (perpendicular to the travel lane) should be provided. This pad is in addition to the wheelchair pad, and in addition to any required sidewalk. A minimum distance between the front edge of the bench and the edge of the curb or traveled way of 5 feet should be provided, which can include any required sidewalk. An accessible path of travel (with a minimum width of 36 inches and adequate slope and surface) shall be provided, connecting the wheelchair pad and shelter pad.

3.6.5 Bench

Current LTA benches are either 6 feet or 8 feet in length. Minimum ADA design considerations apply to the installation of new or replacement benches and include the following:

- Clear floor or ground space for wheelchairs.
- 20 inches minimum to 24 inches maximum in "overall" depth for benches with backrests.
- Seat height: 17 inches minimum to 19 inches maximum above the floor or ground.
- Back support: Extends from a point 2 inches maximum above the seat to a point 18 inches minimum above the seat.
- Structure supporting vertical or horizontal forces of 250 pounds applied at any point on the seat, fastener, mounting device, or supporting structure.
- Exposed benches should be slip-resistant and designed to shed water.

A pad at least 8 feet (parallel to the travel lane) by 3 feet (perpendicular to the travel lane) should be provided. This pad is in addition to the wheelchair pad, and in addition to any required

sidewalk. A minimum distance between the front edge of the bench and the edge of the curb or traveled way of 5 feet should be provided, which can include any required sidewalk. An accessible path of travel (with a minimum width of 36 inches and adequate slope and surface) shall be provided, connecting the wheelchair pad and bench pad.

3.6.6 Accessible Pad Location

A key design parameter for bus stops is to ensure that the ADA wheelchair loading areas align with the location of ramps or lifts on the vehicles. The current LTA fleet includes a total of 32 vehicles, composed of 10 individual vehicle types. Most vehicles have a wheelchair loading location immediately behind the front ambulatory passenger door. However, because fleet replacement and new air emission rules will require new vehicles in the fleet in the future, bus stops should be designed to allow the flexibility of obtaining buses with wheelchair loading in the middle or rear of the bus.

3.6.7 Curb and Sidewalk

Curb or curb and sidewalk shall be constructed as part of the bus stop improvements along roadways with existing or planned curb/sidewalk. Curb heights should be no less than 4 inches and no more than 8 inches. Sidewalk width shall be determined by the individual jurisdiction. Local or Caltrans standards should be applied to the design of sidewalks and bicycle facilities. ADA and ADAAG requirements discussed above also apply.

3.6.8 Signs

It is recommended that signs be posted at all bus stops. Signed stops are a key element in informing passengers where service is available. In addition, bus stop signs provide a permanent "presence" on the street that substantially increases public awareness of the transit program—among riders and non-riders alike.

The bus stop sign should, wherever possible, be placed even with the location where the operator is trained to stop the front door of the bus, to let patrons know where to stand. Signs closer to the curb should be positioned to face toward the sidewalk to prevent bus mirrors from hitting the signs. Placement in an existing sidewalk of 4 feet in width or less should be avoided wherever possible. Signs can be on existing poles, such as streetlights or other traffic information signs. Unprotected sign posts should be of the break-away type to minimize injuries and damage resulting from motor vehicle accidents.

Minimum ADA design implications apply to the installation of new or replacement signs. The bottom of the sign should be at least 7 feet from the ground, and the sign should not be closer to the curb than 3 feet. In the areas where there are sidewalks, allow at least 36 inches of clear path on the sidewalk.

3.6.9 Trash Receptacles

Litter at a bus stop is a negative image for the transit agency, as well as the community. The installation of trash receptacles at bus stops can alleviate this problem. Not all bus stops require trash receptacles; the decision to include a receptacle at a stop is typically based on boarding counts. If litter is a problem at a particular stop (due, perhaps, to the presence of a fast-food outlet or a convenience store near the stop), a trash receptacle should be installed regardless of boarding counts. Trash receptacles should only be placed at those stops that the transit agency can reliably schedule for trash pickup.

In some instances, communities require maintenance of transit receptacles as a condition of nearby development. There is a mutually beneficial relationship between businesses and transit, and the need to work together with the community, particularly fast-food restaurants, to service trash receptacles.

3.6.10 Lighting

The lighting at a bus stop affects the safety of patrons and the use of the stop by patrons and non-patrons in the hours after sunset. A well-lit bus stop enhances the waiting passengers' comfort and security, while a dimly lit or unlit stop encourages non-patrons to loiter at the stop. It is recommended that from 2- to 5-foot-candles of illumination be provided at all bus stops that will be in use after daylight hours. Lighting fixtures should be vandal-proof and easily maintained; the use of exposed bulbs and other elements that can be easily tampered with or destroyed should be avoided. When possible, bus stops should be sited near existing streetlights, because this is a cost-effective method of providing adequate lighting. Another option is the use of solar power to illuminate bus shelters. Typically, the power system mounts to a pole, which makes it compatible with any shelter and maximizes the solar energy harvest.

3.6.11 Bicycle Parking

It is appropriate to provide bicycle parking at some bus stops. The provision of bike parking facilities discourages bicycle riders from locking their bikes to the bus stop structures or to structures on adjacent properties, and reduces visual clutter by locating bikes together in one area. Bicycle parking facilities should be located away from other activities, to reduce congestion and improve safety. At lighted stops, the bike parking should be near the lighting to offer protection from theft. The bike parking should not restrict views into the bus stop area. It is recommended that racks for bike parks be provided at bus stops where there is the potential for a high level of patron access by bike, such as near educational facilities.

3.7 Bus Stop Spacing

Bus stop spacing should depend on passenger convenience, ridership levels, and operational considerations. It is recommended that the range of spacing between each stop of Lake County be between 660 and 880 feet on all routes in developed areas. This measurement is a guideline only, and other factors should be considered when planning the actual location of bus stops,

including the availability of pedestrian access and the location of major trip generators. Bus stops shall be placed close to subdivision access points, and within one block of activity centers such as shopping centers, schools, health care facilities, social service offices, apartment complexes, and mobile home parks. In rural areas, stops should be placed to serve specific transit trip generators and cross-streets, but typically not closer together than 0.25 mile.

Studies have shown that transit use begins to drop off when potential users must walk more than 1,000 feet. A survey from the *Lake County Transit Development Plan (2004)* found that a majority (55 percent) of users who walked to the bus walked 0 to 2 blocks, while 76 percent walked 0 to 4 blocks. It has also been found that too many stops can impede performance of the transit system by making it unnecessarily slow.

3.8 Bus Stop Placement

Bus stops can be located on the far-side of an intersection, near-side of an intersection, or mid-block.

Far-Side Bus Stops are located immediately after an intersection, and are recommended at intersections where sight distance or signal capacity problems exist, where parking conditions are critical, where right or left turns by general traffic are heavy, and where buses make left turns. In general, transit agencies and traffic engineers prefer to standardize on far-side stops, unless conditions indicate that near-side or mid-block is required because standardization benefits the visually impaired.

Near-Side Bus Stops are located immediately before an intersection, and are typically the preferred alternative where buses make right turns. They shall also be an alternative at intersections where transit flows are heavy, but traffic and parking conditions are not critical.

Mid-Block Bus Stops are located between intersections, and are typically an alternative in strip commercial areas where the block faces are longer, with multiple destinations served within the block; in downtown areas where multiple routes require long loading areas that might extend an entire block; or where traffic, physical, or environmental conditions prohibit near- or far-side stops.

Resources and References

- American Planning Association. 1995. *Bicycle Facility Planning*, Planning Advisory Service, Report Number 459, APA Research Department, Chicago, Illinois.
- Americans with Disabilities (ADA) Access Board. 2005. Revised Draft Guidelines for Accessible Public Right-of-Way. November 23.
- California Department of Transportation. 1995. *Highway Design Manual, 5th Edition*, as amended.
- California Department of Transportation. 2013. *Design Information Bulletin 82-05: Pedestrian Accessibility Guidelines for Highway Projects*. October 1.
- CGA Consulting Services, Inc. 1995. Planning Intermodal and Operations Facilities for Rural and Small Urban Transit Systems: Workshop Manual, U.S. Department of Transportation, Technology Sharing Program, DOT-T-96-08.
- Glatting Jackson Kercher Anglin Lopez Rinehart, Inc. in association with Herbert Halback and Associates, Inc. 2000. *Central Florida Mobility Design Manual*, LYNX, The Central Florida Regional Transportation Authority. November.
- Griffin, Kenneth W. 2004. Building Type Basics for Transit Facilities.
- Monterey Salinas Transit. 2006. Designing for Transit, Monterey, California.
- Orange County Transportation Authority. 2004. *Bus Stop Safety and Design Guidelines*, Orange, California.
- Regional Transportation Commission of Washoe County. 1992. *Planning for Transit: A Guide for Community and Site Planning*, Reno, Nevada.
- Transportation Research Board. 2006. *Bus Transit Service in Land Development Planning*, Transit Cooperative Research Program, TCRP Synthesis 67, Washington, D.C.
- Transportation Research Board. 1996. *Guidelines for the Location and Design of Bus Stops,*Transit Cooperative Research Program, Report 19, National Academy Press,
 Washington D.C.
- United States Access Board. *Proposed Guidelines for Pedestrian Facilities in the Public Right-of-Way*. Available: https://www.access-board.gov/guidelines-and-standards/streets-sidewalks/public-rights-of-way/proposed-rights-of-way-guidelines. Accessed on August 2018.

This page intentionally left blank

Chapter 4 Capital Improvement Plan

4.1 Introduction

The purpose of this chapter is to detail the capital and maintenance needs of LTA bus stops in the Lake County project area; provide detailed conceptual bus stop designs for key stop locations; and identify available funding sources to implement and maintain the proposed capital improvements.³ The Transit Facilities Capital Improvement Plan (CIP) builds on previous analysis of the project area to identify and prioritize facility and access improvements for bus stops systemwide. The 2006 Lake County Transit Passenger Facilities Development Plan (2006 Plan) provided general design guidelines aimed at incorporating various safety and accessibility elements into all bus stop designs, to ensure all stop locations are appropriately usable for all riders.4 These elements focused on providing an unimpeded pathway to all transit stops and transit vehicles, including the positioning of street furniture, landscaping, and other obstacles; avoiding or reducing grade-level changes in sidewalks and platforms; providing a simple and consistent layout; ensuring each stop has an unbroken path of travel from the sidewalk to the bus boarding platform; and ensuring adequate illumination where necessary. In addition to focusing on these elements, this CIP further includes high-level conceptual designs and cost estimates at three primary bus stops in the LTA service area, focusing on more comprehensive modifications to improve the overall bus passenger experience.

4.2 Transit Facilities Capital Improvement Plan

The purpose of the Transit Facilities CIP is to identify and prioritize improvements for bus stops systemwide in Lake County as part of the LTA Bus Passenger Facility Plan. The prioritization approach includes identifying the timeframes for each improvement, either near-term (within 1 to 3 years) or long-term (within 3 to 10 years), as well as agencies responsible for implementation.

The LTA Bus Passenger Facility Plan project team has identified bus stop improvements that can be generally categorized as systemwide incremental stop improvements, and redesigned bus stops. Systemwide improvements would upgrade bus stop features, including replacing bus stop signs, sign posts, benches, and shelters; adding lighting; and constructing bus pull-outs and ADA-compliant curb ramps. In addition, one bus stop in each of the three LTA jurisdictions (Clearlake, Lakeport, and unincorporated Lake County) has been identified for a more comprehensive redesign with accompanying conceptual-level designs and cost estimates to a detail suitable to pursue grant funding. Both recommended systemwide and bus stop—specific capital improvements are detailed below.

³ Lake Transit Authority provides service to Lake County and portions of Napa and Mendocino Counties. Stops in Napa and Mendocino Counties are excluded from the scope of this study.

⁴ Transit Passenger Facilities Plan for Lake County, California, September 2006.

4.2.1 Systemwide Improvements

The project team completed a study field inventory of bus stops throughout the project area in 2018. This inventory identified locations for installing or replacing individual bus stop elements and can be found in Appendix F. These measures could be implemented in the near term to benefit system riders. Table 4-1 below quantifies the near-term improvements by type. Overall, the LTA Bus Passenger Facility Plan recommends installation of 141 new bus stop sign panels and replacement of 8 existing sign panels; installation of 149 new sign poles, replacement of 5 existing poles, and repair of 58 poles; installation of 17 new benches and replacement of 5 benches; and 13 locations to trim vegetation to enhance bus stop visibility and accessibility for riders and operators. Each of these items is considered a low-cost enhancement that can be implemented in the near-term, defined as within the next 1 to 3 years. Based on workshops conducted with LTA and the three LTA-member jurisdictions staff, it is anticipated that local Public Works sign shops would be able to furnish sign panels and posts, as well as employ local maintenance staff for tree trimming. Additionally, LTA can procure benches for installation at bus stops.

Table 4-1 Near-Term Systemwide Bus Stop Improvements by Type and Total

Improvement Type	New	Replace	Repair	Total
Sign Plates	141	8	N/A	149
Sign Poles	149	5	58	212
Trim Vegetation	13	N/A	0	13
Benches	17	5	N/A	22

Source: CHS Consulting Group (2019).

N/A = Not Applicable.

Table 4-2 presents systemwide improvements that can be implemented over a long-term time horizon, defined as between 3 and 10 years. These improvements would require local staff to conduct additional planning and engineering, and pursue funding sources for design and construction. These improvements include the replacement of 12 bus shelters, new lighting fixtures at 17 locations, 34 new bus pullouts, and ADA accessibility improvements at 146 locations. ADA accessibility improvements include constructing concrete level landings with curb ramps and yellow-truncated domes. LAPC is currently working with LTA member jurisdictions on a plan to identify and phase more specific ADA improvements at these locations.

Table 4-2 Long-Term Systemwide Bus Stop Improvements

Improvement Type	New	Replace
Shelters	N/A	12
Lighting	17	N/A
Bus Pullouts	34	N/A
ADA Improvements	146	N/A

Source: CHS Consulting Group (2019).

N/A = Not Applicable

4.2.2 Bus Stop Conceptual Designs and Estimates

Based on the evaluation of bus stop inventory locations throughout the project area, the LTA Bus Passenger Facility Plan project team identified a few bus stops with high ridership and access to key destinations as "example" candidates for more detailed conceptual design and cost estimation. The goal was to identify for LTA and its member jurisdictions a range of possible improvements that could be implemented to enhance the bus rider experience and improve rider access. Subsequently, LTA and member agencies could either apply for grants to implement these stop-specific improvements, or could be incarnated into upcoming local Public Works roadway projects. The candidate locations developed by the LTA Bus Passenger Facility Plan project team were further vetted with local Public Works departments in interactive workshops that the project team conducted in 2019 with LTA and Public Works staff from Clearlake, Lakeport, and Lake County. The primary outcome was selection of three bus stop locations, with one in each of the three jurisdictions, to be advanced to conceptual design. This section details those designs, and provides preliminary costs for implementation.

Lakeport – South Main Street at Lakeport Boulevard

City of Lakeport staff identified the bus stops on both sides of South Main Street in front of Grocery Outlet, because they serve multiple LTA routes, including Route 4, Route 4A, and Route 8. The stops facilitate transfers between these routes at least four times per day. The existing southbound bus stop consists of a shelter, bench, and trash can surrounded by eight concrete bollards. The existing southbound design requires buses to stop in the wide southbound travel lane on South Main Street, resulting in blocked traffic. The northbound bus stop similarly requires buses to stop in the travel lane, thereby blocking traffic. Furthermore, the northbound bus stop does not have available right-of-way to accommodate a bus pull-out. Lakeport staff expressed a desire to reconfigure and relocate the existing northbound and southbound bus stops, with a goal of avoiding blocked travel lanes on South Main Street. Based on this staff input, two conceptual design options were created.

Option 1 would construct a new bus boarding island in the Grocery Outlet parking lot that would accommodate both northbound and southbound buses and remove them from the South Main Street curbside. The conceptual design includes concrete bus pads in both directions, new

bollards to provide rider protection between the South Main sidewalk and proposed southbound bus pad, new bus shelter, new sign plates and poles, Class 2 bicycle parking, trash can, and lighting. This option would require the removal of some parking lot trees, relocation of existing parking lot signage, and modification to the existing parking lot striping that would remove 10 parking spaces.

The estimated construction cost subtotal for Option 1 improvements is \$147,570. Adding a 25 percent contingency of \$36,892, the total estimated cost would be \$184,462. Detailed conceptual design plans and cost estimates for Lakeport Option 1 are provided in Appendix G.

Option 2 would construct a new bus pull-out for southbound buses along South Main Street, allowing southbound buses to pull out of the travel lane to pick up and drop off passengers. The northbound bus stop would be moved from South Main Street to the Grocery Outlet parking lot. Operationally, northbound buses would reroute into the parking lot via a new curb cut directly south of the new bus pull-out, and reenter South Main Street north of the new pull-out. This design would similarly include a bus pad for both directions, new bus shelter, new sign plates and poles, Class 2 bicycle parking, trash can, and lighting.

The Option 2 design would require a partial restriping of the Grocery Outlet parking lot to accommodate onsite circulation and a new concrete pad for northbound buses, which would remove three parking spaces. To enhance pedestrian and ADA access, Option 2 would also restripe the three existing crosswalks at the intersection of South Main Street and Lakeport Boulevard, and install an ADA-compliant curb ramp at the southwestern corner. Pullout construction would require land acquisition from the Grocery Outlet property. This option would include new bollards between the sidewalk and parking lot, along with new bus shelters, trash cans, Class 2 bicycle parking rack, and lighting.

The estimated construction cost subtotal for Option 2 improvements is \$236,280. Adding a 25 percent contingency of \$59,070, the total estimated cost would be \$295,350. Detailed conceptual design plans and cost estimates for Lakeport Option 2 are provided in Appendix G.

It is important to note that both option cost estimates exclude land acquisition costs that Lakeport staff would need to negotiate with the Grocery Outlet property owner, as well potential costs for LTA to acquire a permanent easement that enables buses to operate daily on Grocery Outlet property.

Lake County – Kit's Corner

Lake County staff identified the existing Kit's Corner store and gas station at the northwestern corner of SR 29 and SR 281 in the Kelseyville community as their primary bus stop location for improvement. The property owner has permitted LTA buses to pick up and drop off passengers in the parking lot on the western side of the property. Bus passenger amenities are minimal, consisting of a wooden bus shelter with few other basic rider amenities. However, the Kit's Corner stop supports informal park-n-ride activities, and is a key transfer point for riders throughout the County being served by Route 2, Route 4, and Route 4A. In the future, it is anticipated that this stop may need to accommodate up to three buses at any one time.

The Kit's Corner bus facilities conceptual design would remove the existing wooden bus shelter and adjacent curb in the parking lot, and construct a new multi-bus boarding island with a sawtooth design that would accommodate up to three buses simultaneously, along with three new bus shelters, trash can enclosures, Class 2 bicycle parking racks, new sign plates and poles, and lighting. The multi-bus design would better facilitate passenger transfers between bus routes, and provide better amenities for waiting passengers.

The construction cost subtotal for all Kit's Corner bus stop improvements is \$182,410. Adding a 25 percent contingency of \$45,602, the total estimated cost would be \$228,012. Detailed conceptual design plans and cost estimates for the Kit's Corner stop are provided in Appendix G. It should be noted that the estimated costs do not include possible land acquisition costs that LTA staff would need to negotiate with the Kit's Corner property owner, nor LTA easement costs to operate on Kit's Corner Property.

<u>Clearlake – Austin Park</u>

Clearlake staff identified the bus stop on northbound Lakeshore Drive just north of Austin Road as their primary bus stop location improvement, and proposed to move the existing bus stop approximately 50 to 60 feet north of the existing location, across from the play structure.

The current bus stop location on northbound Lakeshore Drive is just north of Austin Road, at the southwestern corner of Austin Park. The stop serves riders on LTA Routes 11 and 12. The existing stop consists of basic passenger amenities, including a wooden bench and bus stop sign plate and pole. This stop is approximately 30 feet north of a crosswalk across Lakeshore Drive. Due to the stop location, northbound buses can periodically block the crosswalk when picking up and discharging passengers. Buses currently stop within the 10-foot-wide northbound shoulder, which is shared with bicyclists, and requires bicyclists to use the 11-foot-wide northbound travel lane to bypass stopped buses.

In response to Clearlake staff input, the project team prepared a conceptual design for the proposed Clearlake bus stop that would construct a 145-foot-long bus pullout that includes a 75-foot-long, full-width concrete bus pad and two 35-foot tapers transitioning back to existing curb. The design would avoid an existing drainage curb inlet on northbound Lakeshore Drive. At full width, the pullout would be 10 feet wide. The design would move the existing northbound sidewalk back 5 feet to accommodate the pullout, meaning the full width from curb line to the existing white stripe would be 15 feet. Subtracting 10 feet for the full-width bus pad, this would leave a 5-foot shoulder width available to bicyclists. The new sidewalk would retain an ADA-accessible transit stop waiting pad design, with a clear minimum of 8 feet deep by 5 feet wide to accommodate wheelchair loading activities.

Additionally, sections of the Austin Park perimeter fence would be removed, replaced, and relocated adjacent to the new back of sidewalk resulting from bus pullout construction. Existing pedestrian openings in the fence would be retained, as would the existing midblock crosswalk across Lakeshore Drive to the south. Primary amenities for the new bus stop would include a new shelter with bench, reconstructed sidewalk, and new street lighting.

The total estimated construction cost of this relocated bus stop in Clearlake is \$104,512. This estimate includes a subtotal of \$83,610 for all stop improvements, and a 25 percent contingency of \$20,902. Key construction items included in this cost are the reconstructed sidewalk with curb and gutter (\$24,390), concrete bus pad (\$15,420), new street lighting (\$13,000), new bus shelter with bench (\$8,000), replacement and relocation of perimeter fence (\$2,500), and relocation of existing bus stop sign assemblies (\$300). Estimated construction costs also include mobilization (\$10,000), traffic control (\$5,000), and stormwater management and erosion control (\$5,000). Appendix G provides both the bus stop conceptual design plan and cost estimate.

4.3 Capital Improvement Plan Financial Element

The purpose of the Transit Facilities CIP Financial Element is to identify potential costs to implement the recommended improvements in Section 2 (Transit Facilities CIP), available funding sources for implementation, and additional funding strategies and approaches for ongoing maintenance.

4.3.1 Potential Costs for Implementation of Near- and Long-Term Bus Stop Improvements

The LTA Bus Passenger Facility Plan project team developed conceptual-level cost estimates for the implementation of near-term and long-term recommended bus stop improvements identified in Section 2 (Transit Facilities CIP). Unit costs are based on LTA Bus Passenger Facility Plan Team research, and experience with typical engineering cost items from California Department of Transportation (Caltrans) and rural California Public Works agencies implementing similar improvements. These unit costs were further reviewed with LTA member agencies' Public Works staff in multiple study workshops to ensure consistency with their local experience. Recommended near-term bus stop improvements include new bus stop signs and poles, benches, shelters, bus pull-outs, landscaping, lighting, and ADA-accessible curb ramps. Appendix F lists these near-term improvements by individual bus stop location. Unit cost estimates for these improvements are provided below. Detailed near-term unit cost estimates are provided in Appendix H.

• The estimated cost to add or replace a bus stop sign can vary depending on available materials, quantity, and whether the sign is installed new or replaced. New bus stop sign panels (without a pole) cost approximately \$100 each, and replacing an existing bus stop sign panel costs approximately \$200 (including \$100 for removal of existing sign panel). In terms of sign poles, the cost to install a new pole is approximately \$200, while replacement of an existing sign pole costs approximately \$300, and repairing an existing sign pole is approximately \$100. Based on these unit costs, the cost to install a new bus stop sign and pole together would be approximately \$300 each (\$100 + \$200). New bus stop sign panels have been identified for installation at 141 bus stops in the project area, and the replacement of existing bus stop sign panels have been identified at an additional eight locations.

New sign poles have been identified for 149 locations, replacement of sign poles

have been identified for 5 locations, and 58 existing sign poles have been identified for repair in the project area. Based on these quantities, the total cost to install new sign panels (\$14,100), new sign poles (\$29,800), replace existing sign panels (\$1,600), replace existing sign poles (\$1,500), and repair existing sign poles (\$5,800) is estimated to be \$52,800 systemwide.

- The estimated cost to install a new bus transit bench is approximately \$800, while the cost to replace an existing bench is \$900 (includes \$100 for removal of existing bench). New transit benches have been identified for 17 locations in the project area, with another 5 locations identified for replacement. In total, the installation of new transit benches (\$13,600) and replacement of existing transit benches (\$4,500) is estimated to cost \$18,100 systemwide.
- The cost of constructing a replacement bus stop shelter is estimated at \$8,000 per location, and typically includes installation of one transit bench.
 Replacement bus shelters have been identified for 12 locations in the project area, which

is estimated to cost \$96,000 systemwide.

- For transit agencies, vegetation and landscaping must meet basic requirements that allow for access to all bus stops, including minimum sidewalk clearance, minimum clearance between any bus stop shelter and utility object (e.g., power poles), proper clearance between bus shelter and edge of curb, and a minimum ADA-accessible landing area. This includes trimming of any trees and removal of any vegetation that might obscure a clear path to system bus stops. The estimated average cost of tree trimming and vegetation removal is approximately \$300 per location, which assumes the work would be part of local Public Works staff routine maintenance activities.

 Tree trimming and other vegetation removal has been identified for 13 locations in the project area, which would cost approximately \$3,900 systemwide.
- Bus pull-out requirements can vary depending on existing site conditions, including the presence of curb and gutter, power poles and other utilities, drainage concerns, and availability of an at-grade shoulder. Consequently, some sites may only require paving an existing shoulder, while other sites may require more extensive engineering work. Typical bus pull-out improvements would include removal of existing asphalt pavement (\$6 per square foot); new vertical curb or curb and gutter (\$40 per linear-foot); new concrete sidewalks (\$10 per square-foot); concrete bus pads (\$10 per square-foot); and new storm drain inlets with connections to existing storm drains (approximately \$10,000 each). Although each location would require site-specific designs, the LTA Bus Passenger Facility Plan project team has conservatively assumed all the above elements are included in the pull-out unit cost. Therefore, the average bus pull-out is estimated to cost approximately \$56,180 each.
 - New bus pull-outs have been identified for 34 locations in the project area, which is estimated to cost approximately \$1.9 million systemwide.
- Lighting improvements would include furnishing and installing new luminaires and poles (approximately \$4,500 each), new luminaire pole foundations (approximately \$1,500 each), new pull boxes (approximately \$1,000 each), and the installation of conduit and

conductors to and from each new luminaire (estimate \$6,000 each). Similar to bus pull-outs, the lighting improvements would vary based on site-specific designs. However, based on improvements identified in Section 2 (Transit Facilities CIP), the average lighting improvements are estimated to cost approximately \$13,000 per location. New lighting improvements have been identified for 17 locations in the project area, which would cost approximately \$221,000 systemwide.

- ADA accessibility needs can vary widely depending on the specific needs at each bus stop. For conservative estimating purposes, ADA unit cost estimates include constructing new passenger waiting areas, assuming none are currently provided due to lack of sidewalk, lack of wheelchair level landing area, or related constraints. Typically, a minimum dimension for wheelchair level landing area is 8 feet by 5 feet. Consistent with practice in other California transit districts serving rural areas, the ADA unit cost estimate assumes constructing an 8-foot by 35-foot concrete sidewalk that provides passenger waiting areas, in addition to wheelchair level landing area (approximately \$6,563), two new curb ramps (\$4,000), and mobilization and traffic control (\$10,000), for a total estimated unit cost of \$20,563 without contingencies. It should be noted that these costs exclude right-of-way and land acquisition, as well as construction of sidewalk extensions that would connect to the nearest existing sidewalk or adjacent property.
- ADA improvements have been identified for 146 locations in the project area, with a collective estimated cost of slightly more than \$3 million (\$20,563 * 146 locations). One potential approach to address these locations is for LTA and local Public Works agencies to collaboratively identify and implement these improvements in phases, setting a goal to complete an agreed-on number of locations each year. Completion would depend on availability of future funding sources that can be used toward ADA improvements. As a supplement to this approach, local City and County Public Works staff can additionally seek opportunities to integrate identified ADA improvements into ongoing and future local roadway and transportation projects that are under planning or design. As a next step for the LTA Bus Passenger Facility Plan, LAPC, LTA, and local agencies will finalize an approach to the ADA improvements, which subsequently will be detailed in the LTA Bus Passenger Facility Plan Administrative Draft Report.

Based on the average unit costs described in this section, the collective estimated cost to implement all identified near-term improvements systemwide would be approximately \$5.3 million. It is important to note that this estimate excludes costs relative to potential land acquisition or right-of-way easements associated with these improvements.

4.3.2 Potential Capital and Operating Funding Sources

The LTA Bus Passenger Facility Plan project team researched current available public transportation funding sources, including the Federal Transit Administration (FTA) and Caltrans, which may be used to implement capital improvements or fund ongoing maintenance and services. Many FTA funding sources were first identified in the 2006 Plan. Since 2006, additional Federal legislation has been reauthorized and created, and FTA has consolidated some of its funding programs. Below is an overview of potential Federal funding sources applicable to the LTA Bus Passenger Facility Plan improvements, as well as similar State

funding sources that may be used for the improvements identified in the LTA Bus Passenger Facility Plan.

FTA Section 5310 – Enhanced Mobility of Seniors and Individuals with Disabilities Program

FTA Section 5310 funds are available to states, local governments, or public transportation operators to help fulfill the transportation needs of elderly adults and people with disabilities when other public transportation services do not meet their needs. Funds are apportioned based on each state's share of these two eligible service populations. Formula funds are then apportioned to direct recipients chosen by the state Department of Transportation (Caltrans), for rural and small urban areas, or the governor, for large urban areas. These funds are intended to improve access to transit facilities for these two service populations with investments beyond those typically allocated for ADA paratransit services.

Eligible capital investments for Section 5310 projects include purchase of buses and vans; wheelchair lifts, ramps, and securement devices; transit-related information technology systems; mobility management programs; and acquisition of transportation services under a contract, lease, or other arrangement. At least 55 percent of Section 5310 program funds must be used on traditional capital projects. The remaining 45 percent of programs' funds can be used for non-traditional projects, as was covered by the recently discontinued 5317 New Freedom program.⁵

Other eligible operating and capital investments include training, volunteer driver programs, building an accessible path to a bus stop (including curb-cuts, sidewalks, accessible pedestrian signals, or other accessibility features), improved signage or way-finding, and mobility management programs. The Federal share of eligible capital costs may not exceed 80 percent, and operating assistance may not exceed 50 percent.⁶

FTA Section 5311 – Formula Grants for Rural Areas

FTA Section 5311 has been retained under the FAST Act and remains a core program for rural public transportation. Historically, Section 5311 has represented a significant share of funding for LTA operations. This program provides capital, planning, and operating assistance to states and federally recognized Indian tribes to support public transportation in rural areas with populations under 50,000 residents. Section 5311 funds are distributed to the regions on a non-urbanized area formula. Eligible activities for fund recipients include planning, capital improvements, operations, job access and reverse-commute projects, and the acquisition of public transportation services. The Federal share of funding is limited to 80 percent for capital

Final - December 2019

⁵ Fact Sheet: Enhanced Mobility of Seniors and Individuals with Disabilities: https://www.transit.dot.gov/sites/fta.dot.gov/files/docs/funding/grants/37971/5310-enhanced-mobility-seniors-and-individuals-disabilities-fact-sheet.pdf. Accessed April 2019.

⁶ Source: https://www.transit.dot.gov/funding/grants/enhanced-mobility-seniors-individuals-disabilities-section-5310. Accessed April 2019.

⁷ Fact Sheet: Formula Grants for Rural Areas: https://www.transit.dot.gov/sites/fta.dot.gov/files/docs/funding/grants/40621/5311-rural-program-fact-sheet-fast.pdf. Accessed April 2019.

projects and ADA non-fixed route paratransit service, and limited to 50 percent for operating assistance.

FTA Section 5339 – Grants for Buses and Bus Facilities

FTA Section 5339, created under MAP-21, provides Federal funding available to states and local agencies to replace, rehabilitate, and purchase buses and related equipment and to construct bus-related facilities. Funding is provided through formula allocations and competitive grants. State and local operators of fixed-route bus service that have been eligible for Section 5307 and 5311 grants can now also apply for Section 5339 grants. The Federal share of eligible capital costs is 80 percent of the net capital project costs, and may exceed 80 percent for certain projects related to ADA, the Clean Air Act, and certain bicycle projects.

<u>US Department of Housing and Urban Development – Community Development Block Grant</u> Program

The Community Development Block Grant (CDBG) is a program that provides communities with resources to address a wide range of unique community development needs, including local public transportation. In the LTA Bus Passenger Facility Plan workshops, LTA and member agency staff identified CDBGs as a funding source they have used historically, and are open to continue doing so. The CDBG program is run by the U.S. Department of Housing and Urban Development. The CDBG program provides annual grants to local and state governments based on a formula composed of serval measures of community need, such as the extent of poverty and population growth lag in relationship to other metropolitan areas.⁹

State of California Transportation Development Act

The Transportation Development Act provides funding for transit and non-transit related purposes that comply with regional transportation plans through two separate funding sources: the Local Transportation Fund (LTF) and the State Transit Assistance (STA) fund. For counties such as Lake County with a population under 500,000, LTF funds can be used not only for transit, but also local street construction and maintenance. STA funds are allocated specifically for transportation planning and mass transportation purposes. The Road Repair and Accountability Act of 2017 increased overall funding for the STA program.¹⁰

State of California Road Repair and Accountability Act

Enacted in 2017, the Road Repair and Accountability Act (also known as Senate Bill 1) provides additional revenue sources for transit maintenance, rehabilitation, and capital projects through the STA fund originally developed from the Transportation Development Act. This increased investment in public transit is referred to as the State of Good Repair (SGR) Program, and

Lake Transit Authority Bus Passenger Facility Plan

⁸ Fact Sheet: Grants for Bus and Bus Facilities: https://www.transit.dot.gov/sites/fta.dot.gov/files/5339%20Bus%20and%20Bus%20Facilities%20Fact%20Sheet.pdf. Accessed April 2040.

⁹ Community Development Block Grant Program – CDBG: https://www.hud.gov/program offices/comm planning/communitydevelopment/programs. Accessed April 2019.

¹⁰ Transportation Development Act: http://dot.ca.gov/drmt/sptda.html. Accessed April 2019.

requires that participating agencies comply with various reporting requirements. ¹¹ The California State Controller's Office (SCO) and Caltrans manage the SGR Program and administer funds under the State Transit Agency (STA) Program formula, with 50 percent allocated according to proportion of local to state population, and the remaining 50 percent allocated according to the proportion of each transit operators' revenues relative to total statewide operator revenues. These funds may be used for transit capital projects or services to maintain or repair an operator's transit vehicle fleet or transit facilities. ¹²

Low Carbon Transit Operations Program

As one of several programs established in 2014 under Senate Bill 862, the Low Carbon Transit Operations Program (LCTOP) was created to provide operating and capital assistance for transit agencies to reduce greenhouse gas emissions while improving mobility. Agencies with program oversight include Caltrans, the California Air Resource Board, and the SCO. These funds are available for bus and rail services; expanding intermodal transit facilities; and may be used for equipment acquisition, fuel, maintenance, and other operating costs associated with reducing greenhouse gas emissions. The LTA has applied for LCTOP funds in the past, applying for approximately \$68,000 in capital improvement funds in FY 2015-2016 for bus stop signs, and in FYs 2016-2017 and 2017-2018 to upgrade transit facilities at several stop locations.

For transit agencies with service areas including disadvantaged communities, at least 50 percent of funds requested through LCTOP must be apportioned to projects that will benefit the disadvantaged communities. Funds are allocated based on prior use of STA funds, with 50 percent allocated to regional entities, based on the ratio of population served by a jurisdiction to the total state population. The remaining 50 percent is allocated to transit operators, based on a ratio of each operator's total revenue to total revenue for all operators in the state.¹³

4.3.3 Additional Funding Strategies and Approaches

Advertising

As previously recommended in 2006, Lake Transit may continue to consider placing advertisements on transit vehicles and facilities as a source of ongoing operating revenue. Many public transportation systems nationwide generate a substantial level of transit funding through exterior bus advertising programs. Some systems lease space in fixed racks on the sides and rear of transit vehicles, while others allow full bus "wraps" made of a plastic film. A disadvantage of this option is that some may find the vehicles unattractive, and the "image" of the public transportation program may suffer. Prior issues have arisen in some jurisdictions over whether certain advertising is appropriate on public transit vehicles (such as alcohol or tobacco ads). There is also a nominal amount of staff time needed to administer the program. On the other hand, the amount of potential revenue could be significant, and LTA would have complete

¹¹ Road Repair and Accountability Act of 2017: http://dot.ca.gov/drmt/spstasgr.html. Accessed April 2019.

¹² Source: http://dot.ca.gov/drmt/docs/spsgr/finalguidelines.pdf. Accessed April 2019.

¹³ Source: http://www.dot.ca.gov/drmt/docs/lctop/fy1819quidelines-revised.pdf. Accessed April 2019.

flexibility in how it is spent. Annual income from this source would vary according to the number of buses affixed with advertising.

Bus Stop Maintenance Items


Although there are several funding sources available to invest in capital improvements and ongoing maintenance, a number of low-cost maintenance tasks can be administered by local Public Works staff, subject to available department maintenance resources, such as:

- Tree trimming and general maintenance of a clear path to all bus stops and shelters in the project area
- Removal or relocation of existing sign panels and poles
- Removal or installation of benches
- Removal or installation of trash can enclosures
- Removal or installation of Class 2 bike racks
- Basic cleaning and maintenance of bus stops and shelters, such as removal of graffiti

Appendix A
Public Survey Summary


Q1 As a bus rider, which of the following is more important to you?





ANSWER CHOICES	RESPONSES	
Buses arriving on time	79.08%	121
Buses stopping at a high number of locations	20.92%	32
TOTAL		153

Q2 Please rank the importance of the following bus stop amenities on a scale of 1 to 5 (1 being "not important" and 5 being "very important"):



	1 - NOT IMPORTANT	2	3 - MODERATELY IMPORTANT	4	5 - VERY IMPORTANT	TOTAL	WEIGHTED AVERAGE
Shelters	5.81% 9	3.23% 5	18.71% 29	16.77% 26	55.48% 86	155	4.13
Bus stop signs	5.26% 8	3.29% 5	13.82% 21	15.79% 24	61.84% 94	152	4.26
Benches	3.18% 5	7.64% 12	21.02% 33	17.83% 28	50.32% 79	157	4.04
Trash bins	15.86% 23	11.03% 16	19.31% 28	11.72% 17	42.07% 61	145	3.53
Lighting	13.33% 20	5.33% 8	20.00% 30	18.67% 28	42.67% 64	150	3.72
Shade	5.19% 8	5.84% 9	23.38% 36	16.23% 25	49.35% 76	154	3.99
Bicycle parking	28.47% 39	21.90% 30	21.17% 29	8.76% 12	19.71% 27	137	2.69
Schedule information	2.01%	2.68%	12.75% 19	18.12% 27	64.43% 96	149	4.40

Q3 Are there are any locations you would like to see a bus stop? If so, please list in order of priority.

Answered: 105 Skipped: 64

#	RESPONSES	DATE
1	Safeway	10/18/2018 4:32 PM
2	I would like buses to run on Sundays & holiday	10/18/2018 4:30 PM
3	Everywhere you all make it to hard to locate a bus	10/18/2018 4:28 PM
4	You need to run on Sunday. If you can holidays.	10/18/2018 4:25 PM
5	no	10/18/2018 4:21 PM
6	Bus sign at Rotten Robbies The nursery	10/11/2018 3:51 PM
7	Point Lakeview in Kelseyville Riviera	10/11/2018 3:45 PM
8	The 36 Ave move back so bus is not blocking the driveway & a shelter	10/11/2018 3:34 PM
9	Buses arriving on time, not ahead of time. New locations that fit "pull-off parameters" so you can stop at "personal pull-offs." Trash bins at kiosks. Schedule behind glass so people can see when next bus comes through. Solar shelters are not working.	9/28/2018 12:48 PM
10	At Oak & Oakmont Drive	9/28/2018 12:43 PM
11	Sr. Centers; In terms of bus stop on and off safety, at the bus stop near the high school in Kelseyille, northbound is a 1 and southbound is a 10.	9/20/2018 3:05 PM
12	In front of project restoration in Lower Lake	9/20/2018 2:51 PM
13	I don't ride the bus.	9/20/2018 2:50 PM
14	Yes; M'Town by library	9/20/2018 2:47 PM
15	Maybe Sunday buses	9/20/2018 2:46 PM
16	End of Dam Rd. Olympic and 53.	9/20/2018 2:44 PM
17	Oglin Canyon, Strawberry Patch in Upper Lake	9/20/2018 2:42 PM
18	Old Robinson Rancheria. Also, if a bus driver sees a customer waving and walking/running towards bus please wait. Thank you.	9/20/2018 2:17 PM
19	Buses stopping at a high number of locations at night.	9/20/2018 2:07 PM
20	Watter Compane Oaks	9/20/2018 2:05 PM
21	Not that I can think of but it's nice when drivers on the 11 let us off at 32nd and Irving so we don't have to walk back one block. There used to be a stop here way long time ago.	9/20/2018 2:20 AM
22	I have never seen any unsafe bus stop in this county. People working transit city, county and state dont get to ride their buses. They get off work too late. Later buses for them.	9/19/2018 3:33 PM
23	Use transit to go places when I don't have a ride.	9/19/2018 3:19 PM
24	Need of express bus routes, especially for north shore.	9/19/2018 3:08 PM
25	Sayre Street, Nice. Not all drivers stop there.	9/19/2018 2:34 PM
26	I would like the bus service to run later, especially on Saturdays	9/19/2018 11:12 AM
27	Mendo Mill/Napa Auto - S. Main, Lakeport	9/19/2018 11:10 AM
28	Bus #3 Clearlake to Middletown @ 11 am and returning @ 11:45 am from Twin Pines to Clearlake so the kids @ the Charter School can get the bus on half days.	9/19/2018 10:56 AM
29	So far this is my first experience and so far it is good	9/19/2018 10:29 AM

30	Electronic schedule at bus stop showing updates	9/19/2018 10:14 AM
31	Olson on 20	9/19/2018 10:10 AM
32	Costco in Ukiah	9/19/2018 10:08 AM
33	I would like to see a bus on every corner even in front of my house.	9/19/2018 10:07 AM
34	Cypress to dark in the morning. Burns Valley Mall - seats. King Fisher Mobile Park - seats. Regarding posting schedule on website- no computer or cell phone.	9/19/2018 9:57 AM
35	Bench at Highland and Hwy 53. You already stop at the corner at ? apartments & need repair	9/18/2018 4:46 PM
36	Lakeview Collier Ave. in Nice Shelter & bench Bruno's in Lakeport	9/18/2018 1:54 PM
37	None that I know of	9/18/2018 1:49 PM
38	No, I think you have a good array of stops. I do not know the Hwy 20 Corridor but that might be a good area to add more stops.	9/17/2018 11:52 AM
39	Olympic Drive in Clearlake	9/15/2018 3:56 PM
40	Move the Austin Park sign to Austin Park #10 x- fer to the #12	9/14/2018 6:03 PM
41	No	9/14/2018 5:48 PM
42	The Keys Blvd. stop is perfect. Great system, great drivers. Steve and Jeff Thank you	9/14/2018 5:38 PM
43	No	9/14/2018 5:15 PM
44	None	9/14/2018 5:05 PM
45	n/a	9/12/2018 10:50 AM
46	N/a	9/11/2018 2:45 PM
47	Negative. P.S. The Greyhound connection at CDF Airport connection was stuck there for 2 nights. Not cool.	9/11/2018 1:43 PM
48	The bench at Rotten Robbie. The bench at the nursery.	9/11/2018 1:38 PM
49	Some people don't have internet (related to posting schedule on website) Homeless and drunk hang out at these two bus stops: VA Clinic and AH Clinic (related to stop safety rating)	9/11/2018 1:22 PM
50	Make more stops to Konocti	9/11/2018 1:14 PM
51	Make less stops 1/2 mile ratio. Bus drivers are not cops, tell them! (white/guy) drivers.	9/11/2018 1:13 PM
52	Corner of Lakeshore and Collier or Lakeshore and Hammond in Nice	9/11/2018 1:08 PM
53	I personally wish the 3 bus, which goes to Hidden Valley, would run more frequent in the day.	9/11/2018 1:00 PM
54	I don't know	9/11/2018 12:58 PM
55	None at this time	9/11/2018 12:40 PM
56	No complaints	9/11/2018 12:33 PM
57	Whaylen Way in Lakeport	9/11/2018 12:32 PM
58	Stop at Mendo Mills, Northbound 8 closer to turn off Main Street. Stop at Sears. Stop accross from WIC.	9/11/2018 12:21 PM
59	Need more stops on Olympic	9/11/2018 12:18 PM
60	Lake side of the Austin Park in Clearlake	9/11/2018 12:12 PM
61	Sunday bus service. One very late bus around the lake.	9/11/2018 11:53 AM
62	It's pretty good	9/11/2018 11:45 AM
63	Government St., Upper Lake, Country Club, Lucerne	9/11/2018 11:35 AM
64	Closer to Quail Run more often	9/11/2018 11:18 AM
65	Napa Auto/Mendo Mill	9/11/2018 11:14 AM
66	No	9/11/2018 10:41 AM

67	Closer to Botnum in Lower Lake, far walk to nearest stop.	9/11/2018 10:27 AM
68	No. It would be really helpful to have later service again.	9/11/2018 10:23 AM
69	Next to Safeway & across from Safeway on Old Hwy. 53	9/11/2018 10:21 AM
70	Spring Valley, Hwy 53 & Olympic	9/11/2018 10:19 AM
71	McDonalds	9/11/2018 10:13 AM
72	Woodland street in clearlake park and at at Napa auto parts in clearlake.	9/11/2018 7:37 AM
73	N/A	9/10/2018 6:01 PM
74	N/A	9/10/2018 5:48 PM
75	N/A	9/10/2018 5:46 PM
76	All good	9/10/2018 5:37 PM
77	Clearlake, Olympic and 53 on way to Walmart. More close to each other because I am 65 and have a hard time making it to some stops.	9/10/2018 5:25 PM
78	Not currently	9/10/2018 5:05 PM
79	Across from Dollar General, near Butler St.	9/10/2018 5:01 PM
80	Mendo Mill, Wasson Memorial	9/10/2018 2:52 PM
81	Put bus stop in across street from Power Mart going into Clearlake. There should be straight shot bus from Upper Lake to Clearlake. We need more signs that are clear where to stop on both sides of road. Streets more shelters covered. Need Lake Co. bus sign at the stop Ukiah at Pear Tree.	9/10/2018 2:42 PM
82	Bring back the 3 bus route to Twin Pines Casino. 10 a.m. at Walmart to Twin Pine for Senior Tournement Play	9/10/2018 2:20 PM
83	No	9/10/2018 2:16 PM
84	Unknown	9/10/2018 2:14 PM
85	None that I can think of at this time	9/10/2018 2:08 PM
86	At North Shore Villas Senior Apts. on Hwy 20 in Lucerne between 1st Street and Foothill Rd. There's plenty of room on the side of the road to pull off there heading both east and west.	9/10/2018 1:54 PM
87	When the bus stops at Senior Center after going through town it should stop back at the Tribal Health again before going to Bell Vista	9/10/2018 1:42 PM
88	Williams (Colusa)	9/10/2018 1:39 PM
89	I don't use the bus but am concerned for elderly and/or disabled folks who need bus shelters	9/10/2018 1:31 PM
90	Austin Rd.	9/10/2018 1:28 PM
91	By parks	9/10/2018 1:20 PM
92	Bus from Clearlake or Lakeport to Santa Rosa	9/10/2018 1:17 PM
93	More bus stops for elderly patients	9/10/2018 1:16 PM
94	Not at the moment	9/10/2018 1:15 PM
95	Hwy. 50, Foothill/Grove Lucerne, CA	9/10/2018 1:13 PM
96	West Road/ East Road in Middletown	9/6/2018 7:38 AM
97	Main St, & Martin A better one at Safeway (too much pushing and shoving)	8/31/2018 2:33 PM
98	More buses more often in Clearlake Oaks! Buses that literally go through the Oaks to Walmart and from Walmart to the Oaks more often. Library in Clearlake, CA Cheaper monthly passes for kids who have to ride the bus. More stops in Lakeport, CA.	8/30/2018 3:34 PM
99	N/A	8/30/2018 12:04 PM
100	Yes! Their should be More Bus Stops with agreements by the City of: Clearlake, to be put there,	8/30/2018 11:24 AM

101	1) Eastbound route 1 at Hudson St & Hwy 20. 2) Northbound route 8 at Bevins st & Bevins court. (farside) But, I would really like to see the bus stops that are NO longer in service be taken out (In Clearlake) Eastbound Olympic Dr at old Hwy 53 (CVS Pharmacy) and Olympic at Jefferson and Olympic and Garfield. Westbound Olympic at Amber. In Lucerne All along Country Club Dr. And also make 13th and Country Club at "request" only stop. In Nice Eastbound route 1 the stop across from Hwy 20 and Keeling (the bat house) should be taken out since you have a stop at Hwy 20 and Sayre st and one at Dollar General.	8/29/2018 7:07 PM
102	Hidden Valley Hardester's Market	8/29/2018 3:11 PM
103	Near 1111 Whalen Way, at Lake County Probation Dept DRC	8/29/2018 1:37 PM
104	Spring Valley!	8/29/2018 8:22 AM
105	Dam Road by Cache Creek Apartments Parallel Drive Lakeport next to DMV and Social Security and the Old Mendocino Collage	8/26/2018 11:47 AM

Q4 Which bus stop(s) do you use most frequently? Please list them (up to five).

Answered: 142 Skipped: 27

	- augusta-a		
ANSWE	R CHOICES	RESPONSES	
Bus stop	1	99.30%	141
Bus stop	2	83.80%	119
Bus stop	3	65.49%	93
Bus stop	0.4	36.62%	52
Bus stop	5	29.58%	42
#	BUS STOP 1		DATE
1	Walmart		10/18/2018 4:34 PM
2	Walmart		10/18/2018 4:32 PM
3	Cache Creek		10/18/2018 4:30 PM
4	18th Ave./Boyel		10/18/2018 4:25 PM
5	18th boyles		10/18/2018 4:21 PM
6	Grocery Outlet		10/11/2018 3:51 PM
7	Kit's Corner		10/11/2018 3:45 PM
8	36 Ave		10/11/2018 3:34 PM
9	All of Upper Lake		9/28/2018 12:48 PM
10	Highlands Senior		9/28/2018 12:44 PM
11	Lakeport Main St.		9/20/2018 3:05 PM
12	Kingfisher		9/20/2018 2:58 PM
13	Main St. Lower Lake		9/20/2018 2:53 PM
14	Lower Lake		9/20/2018 2:51 PM
15	Walmart to Lucerne		9/20/2018 2:49 PM
16	Glenheaven		9/20/2018 2:46 PM
47			0/00/00/00 0 0 1/1 51/1

9/20/2018 2:44 PM

9/20/2018 2:42 PM

9/20/2018 2:29 PM

9/20/2018 2:17 PM

9/20/2018 2:07 PM

9/20/2018 2:05 PM

9/20/2018 2:20 AM

9/19/2018 3:33 PM

9/19/2018 3:08 PM

9/19/2018 3:01 PM

9/19/2018 2:34 PM

17

18

19

20

21

22

23

24

25

26

27

Walmart

3rd Main

1 Northshore

Red amd White

Lakeview/Collier Ave.

Henman Park, Nice

32nd Ave and Phillip's Ave both ways

4A

Nice

Walmart

Fifth in Lucerne

28	Sentry	9/19/2018 2:21 PM
29	4	9/19/2018 2:14 PM
30	Animal Hospital, Lakeshore Dr.	9/19/2018 2:13 PM
31	dial a ride	9/19/2018 11:45 AM
32	Bush and 2nd St.	9/19/2018 11:12 AM
33	Main St./20, Upper Lake	9/19/2018 11:10 AM
34	Corner of Frontage/Oak Crest, Lucerne	9/19/2018 11:08 AM
35	10-11-12	9/19/2018 11:05 AM
36	Senior Center	9/19/2018 11:03 AM
37	12	9/19/2018 10:56 AM
38	Just 4 to Kelseyville	9/19/2018 10:29 AM
39	Walmart	9/19/2018 10:19 AM
40	College stop Lakeport Parallel Dr.	9/19/2018 10:16 AM
41	Walmart	9/19/2018 10:14 AM
42	10	9/19/2018 10:10 AM
43	Walmart bus stop	9/19/2018 10:08 AM
14	8	9/19/2018 10:00 AM
45	Cypress	9/19/2018 9:57 AM
46	HWY 29 YOUNG MIDDLETOWN	9/18/2018 9:31 PM
17	Highland Ave.	9/18/2018 4:46 PM
18	Wal Mart	9/18/2018 2:00 PM
49	Grocery Outlet	9/18/2018 1:54 PM
50	Walmart parking lot	9/15/2018 3:59 PM
51	Walmart parking lot	9/15/2018 3:56 PM
52	Bus 11	9/14/2018 6:06 PM
53	Walmart	9/14/2018 6:03 PM
54	Bus 1 Lucerne	9/14/2018 5:48 PM
55	VA Building & Clinic	9/14/2018 5:46 PM
56	Clearlake Apts.	9/14/2018 5:40 PM
57	Walmart	9/14/2018 5:17 PM
58	Oaks Red & White	9/14/2018 5:15 PM
59	13th and Country Club	9/14/2018 5:07 PM
60	Lakeshore, Nice	9/14/2018 4:58 PM
61	VA clinic	9/13/2018 9:48 AM
62	Walmart/(Old Ray's) Hub	9/12/2018 11:33 AM
63	n/a	9/12/2018 10:50 AM
64	N/a	9/11/2018 2:45 PM
65	Kmart	9/11/2018 1:45 PM
66	Kelseyville Fire Station	9/11/2018 1:43 PM
67	Grocery Outlet	9/11/2018 1:38 PM
68	Lake St. at Main St., Lower Lake	9/11/2018 1:22 PM

69	Route 7 Pear Tree Center	9/11/2018 1:16 PM
70	Lakeport	9/11/2018 1:14 PM
71	Robinsons	9/11/2018 1:13 PM
72	Hwy 20 and Collier in Nice	9/11/2018 1:08 PM
73	Animal Clinic Lakeshore Dr.	9/11/2018 1:05 PM
74	Indian Beach	9/11/2018 1:03 PM
75	10 Austin Park	9/11/2018 1:00 PM
76	Lower Lake	9/11/2018 12:58 PM
77	Route 4	9/11/2018 12:40 PM
78	Clearlake Oaks Keys Club	9/11/2018 12:37 PM
79	Haverty Field	9/11/2018 12:33 PM
80	5th Ave. & Hwy. 20, Lucerne	9/11/2018 12:32 PM
81	1	9/11/2018 12:23 PM
82	Grocery Outlet	9/11/2018 12:21 PM
83	Walmart	9/11/2018 12:18 PM
84	#10	9/11/2018 12:12 PM
85	3rd & Main Street	9/11/2018 11:53 AM
86	Clearlake Oaks	9/11/2018 11:49 AM
87	Bella Vista	9/11/2018 11:45 AM
88	1st. Ave, Lucerne	9/11/2018 11:35 AM
89	Upper Lake	9/11/2018 11:32 AM
90	Bus 8 to McDonalds	9/11/2018 11:20 AM
91	Upper Lake Library	9/11/2018 11:18 AM
92	Main Street, Upper Lake	9/11/2018 11:14 AM
93	Lucerne Riviera	9/11/2018 11:05 AM
94	Lakeshore & Lange	9/11/2018 10:43 AM
95	Walmart	9/11/2018 10:41 AM
96	Twin Pine	9/11/2018 10:23 AM
97	Cypress/King Fisher	9/11/2018 10:21 AM
98	Hidden Valley	9/11/2018 10:19 AM
99	9th, Lucerne	9/11/2018 10:13 AM
100	Third and Main	9/11/2018 10:11 AM
101	Knotts Ligure	9/11/2018 7:37 AM
102	3rd and Main	9/10/2018 6:06 PM
103	Main and 4th, Kelseyville	9/10/2018 6:01 PM
104	Napa Auto, Kelseyville	9/10/2018 5:52 PM
105	3rd and Main	9/10/2018 5:48 PM
106	Kit's Corner	9/10/2018 5:46 PM
107	Knotts Liquor Route 10	9/10/2018 5:40 PM
108	13th and County Club	9/10/2018 5:37 PM
109	Mendocino College	9/10/2018 5:05 PM

110	Dollar General	9/10/2018 5:01 PM
111	The old Red Cross	9/10/2018 2:54 PM
112	Rainbow Mobile Home Park, Lakeport	9/10/2018 2:52 PM
113	Stops in Lucerne heading to Lakeport	9/10/2018 2:42 PM
114	3rd and Main Lakeport	9/10/2018 2:29 PM
115	Upper Lake High School	9/10/2018 2:26 PM
116	Store 24 Kelseyville	9/10/2018 2:20 PM
117	Lakeview Rd., Nice	9/10/2018 2:16 PM
118	Lucerne Market	9/10/2018 2:14 PM
119	Lakeside Health Clinic	9/10/2018 2:00 PM
120	Foothill Rd. in Lucerne	9/10/2018 1:54 PM
121	3rd and Main	9/10/2018 1:45 PM
122	Senior Center	9/10/2018 1:42 PM
123	USB Rentals (Rotten Robbie)	9/10/2018 1:39 PM
124	Walmart/Big 5	9/10/2018 1:28 PM
125	Beach Lane Lakeport	9/10/2018 1:24 PM
126	Kelseyville	9/10/2018 1:20 PM
127	Lakeshore & Large	9/10/2018 1:18 PM
128	3rd and Main Lakeport	9/10/2018 1:15 PM
129	Toyon at Arrowhead	9/6/2018 10:23 AM
130	Pomo elementary	9/6/2018 7:38 AM
131	Ray's food place	9/5/2018 3:32 AM
132	Main byMartin	8/31/2018 2:33 PM
133	1st Stop in Clearlake Oaks, CA coming from Lakeport, CA	8/30/2018 3:34 PM
134	Big 5 area stop	8/30/2018 12:04 PM
135	The Olympic Villa Apartments Bus Stop	8/30/2018 11:24 AM
136	Big 5	8/29/2018 7:07 PM
137	Main and 1st, Lucerne	8/29/2018 7:07 PM
138	Employment Services on Hwy 53	8/29/2018 3:11 PM
139	Near Lake County Jail	8/29/2018 1:37 PM
140	N/A	8/29/2018 8:22 AM
141	In Clearlake at the Wal-Mart Tractor Supply and Big 5 Sporting Goods	8/26/2018 11:47 AM
#	BUS STOP 2	DATE
1	College	10/18/2018 4:32 PM
2	Walmart	10/18/2018 4:25 PM
3	ICC Woodland	10/18/2018 4:21 PM
4	Third and Main	10/11/2018 3:51 PM
5	Lakeport Grocery Outlet	10/11/2018 3:45 PM
6	Clinet	10/11/2018 3:34 PM
7	3rd and Main	9/28/2018 12:48 PM
8	Kelseyville near high school	9/20/2018 3:05 PM

9	Rays	9/20/2018 2:58 PM
10	CPD	9/20/2018 2:53 PM
11	Walmart	9/20/2018 2:51 PM
12	Lower Lake/Walmart	9/20/2018 2:49 PM
13	Clearlake	9/20/2018 2:46 PM
14	Burns Valley	9/20/2018 2:44 PM
15	1st in Lucerne	9/20/2018 2:42 PM
16	4	9/20/2018 2:29 PM
17	Safeway	9/20/2018 2:17 PM
18	2	9/20/2018 2:07 PM
19	Running Creek	9/20/2018 2:05 PM
20	Walmart	9/20/2018 2:20 AM
21	Upper Lake	9/19/2018 3:33 PM
22	Lakeport Main St.	9/19/2018 3:08 PM
23	Third and Main	9/19/2018 3:01 PM
24	Safeway, Lakeport	9/19/2018 2:34 PM
25	Upper Lake Hight	9/19/2018 2:21 PM
26	Clearlake Clinic, Lakeshore Dr.	9/19/2018 2:13 PM
27	Burns Valley Mall	9/19/2018 11:12 AM
28	Grocery Outlet-Lakeport	9/19/2018 11:10 AM
29	Mendocino College	9/19/2018 11:08 AM
30	Safeway	9/19/2018 11:03 AM
31	11	9/19/2018 10:56 AM
32	Store 24 Kelseyville	9/19/2018 10:19 AM
33	11th and Bush	9/19/2018 10:14 AM
34	Mendocino College	9/19/2018 10:08 AM
35	1	9/19/2018 10:00 AM
36	Burns Valley Mall	9/19/2018 9:57 AM
37	Austin Apartments	9/18/2018 4:46 PM
38	Senior Citizen Center (Clealake).	9/18/2018 2:00 PM
39	Brunos	9/18/2018 1:54 PM
40	3rd and Main in Lakeport	9/15/2018 3:59 PM
41	Robinson Rancheria	9/15/2018 3:56 PM
42	Bus 10	9/14/2018 6:06 PM
43	Woodland & Lakeshore #10	9/14/2018 6:03 PM
44	Bus 10 Walmart	9/14/2018 5:48 PM
45	Walmart	9/14/2018 5:46 PM
46	Walmart	9/14/2018 5:40 PM
47	32nd	9/14/2018 5:17 PM
48	Power Mart, Lucerne	9/14/2018 5:15 PM
49	Sentry Market, Nice	9/14/2018 4:58 PM

50	40th & Philips	9/13/2018 9:48 AM
51	Kit's Corner	9/12/2018 11:33 AM
52	n/a	9/12/2018 10:50 AM
53	N/a	9/11/2018 2:45 PM
54	Walmart	9/11/2018 1:45 PM
55	Lakeport Nursery	9/11/2018 1:43 PM
56	Third and Main Street	9/11/2018 1:38 PM
57	VA Clinic, Clearlake	9/11/2018 1:22 PM
58	Lucerne	9/11/2018 1:14 PM
59	Tower Mart	9/11/2018 1:13 PM
60	Sutter Lakeside Hospital	9/11/2018 1:08 PM
61	Burns Valley Mall to Clearlake Park	9/11/2018 1:05 PM
62	Brun Valley Mall	9/11/2018 1:03 PM
63	3 Walmart	9/11/2018 1:00 PM
64	Route 11	9/11/2018 12:40 PM
65	Walmart	9/11/2018 12:37 PM
66	Walmart transfer	9/11/2018 12:33 PM
67	Sentry Market	9/11/2018 12:32 PM
68	8	9/11/2018 12:23 PM
69	Walmart	9/11/2018 12:21 PM
70	Burns Valley Mall	9/11/2018 12:18 PM
71	#4	9/11/2018 12:12 PM
72	Safeway, Clearlake	9/11/2018 11:49 AM
73	Main & D, Lakeport	9/11/2018 11:45 AM
74	Running Creek	9/11/2018 11:35 AM
75	Lucerne	9/11/2018 11:32 AM
76	McDonalds, Lakeport	9/11/2018 11:18 AM
77	3rd and Main Street, Lakeport	9/11/2018 11:14 AM
78	Sutter Hospital	9/11/2018 11:05 AM
79	Bruno's	9/11/2018 10:43 AM
80	Robinson Casino	9/11/2018 10:41 AM
81	After Clearlake Park Post Office	9/11/2018 10:23 AM
82	Safeway	9/11/2018 10:21 AM
83	Walmart	9/11/2018 10:19 AM
84	Safeway	9/11/2018 10:13 AM
85	Lake County Library	9/11/2018 10:11 AM
86	Walkmart	9/11/2018 7:37 AM
87	Lower Lake Fosters Freeze	9/10/2018 6:06 PM
88	Third and Main, Lakeport	9/10/2018 6:01 PM
89	Kelseyville Lumber, Kelseyville	9/10/2018 5:52 PM
90	Walmart	9/10/2018 5:48 PM

91	Downtown Lakeport	9/10/2018 5:46 PM
92	Walmart Route 4	9/10/2018 5:40 PM
93	Grocery Outlet, Lakeport	9/10/2018 5:37 PM
94	Lakeport Campus	9/10/2018 5:05 PM
95	Woodland/Lakeshore	9/10/2018 2:54 PM
96	ShopSmart, Lakeport	9/10/2018 2:52 PM
97	All stops in Nice and Lakeport	9/10/2018 2:42 PM
98	Alpine Park Lucerne	9/10/2018 2:29 PM
99	Mendocino College	9/10/2018 2:26 PM
100	Walmart	9/10/2018 2:20 PM
101	Walmart	9/10/2018 2:16 PM
102	Hinmin Park, Nice	9/10/2018 2:14 PM
103	Safeway	9/10/2018 2:00 PM
104	Robinson Casino	9/10/2018 1:54 PM
105	3rd and Main	9/10/2018 1:42 PM
106	Kanocti Casino	9/10/2018 1:39 PM
107	Post office	9/10/2018 1:28 PM
108	Bruno's	9/10/2018 1:24 PM
109	Clearlake Safeway	9/10/2018 1:20 PM
110	Sutter Lakeside Hospital	9/10/2018 1:18 PM
111	Burns Valley Mall	9/6/2018 10:23 AM
112	28th Ave	9/6/2018 7:38 AM
113	1St & Martin	8/31/2018 2:33 PM
114	Walmart	8/30/2018 3:34 PM
115	The Walmart Bus Stop	8/30/2018 11:24 AM
116	Keys Blvd (Clearlake Oaks)	8/29/2018 7:07 PM
117	Konocti Harbor	8/29/2018 7:07 PM
118	Walmart shopping center	8/29/2018 3:11 PM
119	Burns Valley Maul next to Safeway in Clearlake	8/26/2018 11:47 AM
#	BUS STOP 3	DATE
1	Olympic	10/18/2018 4:34 PM
2	18th	10/18/2018 4:32 PM
3	Safeway	10/18/2018 4:25 PM
4	Kmart	10/11/2018 3:51 PM
5	Riviera Market	10/11/2018 3:45 PM
3	Vetren	10/11/2018 3:34 PM
7	Grocery Outlet	9/28/2018 12:48 PM
8	clinic	9/20/2018 3:05 PM
9	Safeway	9/20/2018 2:51 PM
10	3rd and Main	9/20/2018 2:44 PM
11	Robinsons	9/20/2018 2:42 PM

12	Walmart	9/20/2018 2:17 PM
13	3	9/20/2018 2:07 PM
14	Twen	9/20/2018 2:05 PM
15	Twin Pines Casino	9/20/2018 2:20 AM
16	Lucerne	9/19/2018 3:33 PM
17	Tribal Health	9/19/2018 3:08 PM
18	3rd & Main, Lakeport	9/19/2018 2:34 PM
19	Lucerne 5th Street	9/19/2018 2:21 PM
20	Burns Valley Mall, Olympic Dr.	9/19/2018 2:13 PM
21	Walmart	9/19/2018 11:12 AM
22	Kmart	9/19/2018 11:10 AM
23	3rd & Main, Lakeport	9/19/2018 11:08 AM
24	Yuba College	9/19/2018 11:03 AM
25	10	9/19/2018 10:56 AM
26	Lakeport	9/19/2018 10:19 AM
27	2 Jacks (Kelseyville)	9/19/2018 10:14 AM
28	Costco	9/19/2018 10:08 AM
29	5	9/19/2018 10:07 AM
30	4	9/19/2018 10:00 AM
31	King Fisher Mobile Park	9/19/2018 9:57 AM
32	Clearlake Post Office	9/18/2018 4:46 PM
33	Austin Park	9/18/2018 2:00 PM
34	Safeway	9/18/2018 1:54 PM
35	Bus 4	9/14/2018 6:06 PM
36	Arrowhead & Toyon #10	9/14/2018 6:03 PM
37	Clearlake Mall	9/14/2018 5:48 PM
38	Burns Valley Mall	9/14/2018 5:46 PM
39	Main Street, Lower Lake	9/14/2018 5:40 PM
40	Foods	9/14/2018 5:17 PM
41	Power Mart, Oaks	9/14/2018 5:15 PM
42	3rd and Main, Lakeport	9/14/2018 4:58 PM
43	Old hwy 53 & austin	9/13/2018 9:48 AM
44	n/a	9/12/2018 10:50 AM
45	N/a	9/11/2018 2:45 PM
46	Kelseyville Bank	9/11/2018 1:45 PM
47	OCC, Ukiah to Lake County	9/11/2018 1:43 PM
48	Kmart	9/11/2018 1:38 PM
49	AH Clinic, Clearlake	9/11/2018 1:22 PM
50	Upper Lake	9/11/2018 1:14 PM
51	Park	9/11/2018 1:13 PM
52	Parallel Dr Lakeport	9/11/2018 1:08 PM

53	Walmart	9/11/2018 1:03 PM
54	Route 3	9/11/2018 12:40 PM
55	Nice Post Office	9/11/2018 12:33 PM
56	Whaylen Way, Lakeport	9/11/2018 12:32 PM
57	Lakeport Nursery	9/11/2018 12:21 PM
58	VA Hospital	9/11/2018 12:18 PM
59	#1	9/11/2018 12:12 PM
60	3rd and Main Street	9/11/2018 11:35 AM
61	Lakeport	9/11/2018 11:32 AM
62	Burger King, Lakeport	9/11/2018 11:18 AM
63	Sutter, Lakeport	9/11/2018 11:14 AM
64	Austin Park	9/11/2018 10:23 AM
35	Walmart	9/11/2018 10:21 AM
66	Calistoga	9/11/2018 10:19 AM
67	Power Mart, Lucerne	9/11/2018 10:13 AM
68	Running Creek Casino	9/11/2018 10:11 AM
69	Yuba college	9/11/2018 7:37 AM
70	Walmart	9/10/2018 6:06 PM
71	Safeway	9/10/2018 6:01 PM
72	3rd and Main, Lakeport	9/10/2018 5:52 PM
73	Mendocino College	9/10/2018 5:48 PM
74	Ukiah - Pear Tree	9/10/2018 5:46 PM
75	Safeway, Lakeport Route 4	9/10/2018 5:40 PM
76	Walmart	9/10/2018 5:37 PM
77	Pomo School	9/10/2018 2:54 PM
78	Clearlake Ave., Lakeport	9/10/2018 2:52 PM
79	Stops in Lucerne heading to Clearlake	9/10/2018 2:42 PM
30	Twin Pine	9/10/2018 2:20 PM
31	Castle Donuts	9/10/2018 2:16 PM
32	Power Mart (Lucerne)	9/10/2018 2:00 PM
33	Sentry Market	9/10/2018 1:54 PM
34	Safeway	9/10/2018 1:39 PM
35	Grocery Outlet	9/10/2018 1:24 PM
36	Walmart	9/6/2018 10:23 AM
37	Burns Valley Mall	9/6/2018 7:38 AM
38	by Clearlake Club	8/31/2018 2:33 PM
39	DJs Pizza in Lower Lake, CA	8/30/2018 3:34 PM
90	The Senior Center Bus Stop	8/30/2018 11:24 AM
91	Power Market (Lucerne)	8/29/2018 7:07 PM
92	Kmart, Lakeport	8/29/2018 7:07 PM
93	Dam Road by Cache Creek Apartments in Clearlake	8/26/2018 11:47 AM

#	BUS STOP 4	DATE
1	The Nursery	10/11/2018 3:51 PM
2	3rd/Main	10/11/2018 3:45 PM
3	Hospital	10/11/2018 3:34 PM
4	All of Lucerne	9/28/2018 12:48 PM
5	Safeway	9/20/2018 3:05 PM
6	Running Creek	9/20/2018 2:42 PM
7	5	9/20/2018 2:07 PM
8	Walmat	9/20/2018 2:05 PM
9	Burns Valley Mall Clearlake	9/20/2018 2:20 AM
10	Lakeport	9/19/2018 3:33 PM
11	Walmart	9/19/2018 3:08 PM
12	Kits Corner, Kelseyville	9/19/2018 2:34 PM
13	Lucerne between 8th and 9th	9/19/2018 2:21 PM
14	Walmart	9/19/2018 2:13 PM
15	Main St., Uppper Lake	9/19/2018 11:08 AM
16	3	9/19/2018 10:56 AM
17	Third and Main	9/18/2018 1:54 PM
18	Lakeshore & Park #10	9/14/2018 6:03 PM
19	Austin Park	9/14/2018 5:48 PM
20	VA	9/14/2018 5:40 PM
21	Wal-Mart	9/13/2018 9:48 AM
22	n/a	9/12/2018 10:50 AM
23	N/a	9/11/2018 2:45 PM
24	Kits Corner	9/11/2018 1:38 PM
25	Burns Valley Mall	9/11/2018 1:22 PM
26	Nice	9/11/2018 1:14 PM
27	Clearlake	9/11/2018 1:13 PM
28	Safeway, Lakeport	9/11/2018 12:32 PM
29	Sutter Hospital	9/11/2018 12:21 PM
30	Kits Corner	9/11/2018 12:18 PM
31	#4A	9/11/2018 12:12 PM
32	Walmart	9/11/2018 11:35 AM
33	Lincoln Bridge, Calistoga	9/11/2018 10:23 AM
34	Walmart	9/11/2018 10:11 AM
35	Lakeshore and Lang lakeport	9/11/2018 7:37 AM
36	Sentry	9/10/2018 6:06 PM
37	Kmart, Lakeport	9/10/2018 5:52 PM
38	Main St., Upper Lake	9/10/2018 5:37 PM
39	Safeway	9/10/2018 2:54 PM
40	Safeway	9/10/2018 2:52 PM

41	All stops between Lake Co. and Ukiah	9/10/2018 2:42 PM
42	Running Creek Casino	9/10/2018 1:54 PM
43	Main St., Lakeport	9/10/2018 1:39 PM
14	Safeway	9/10/2018 1:24 PM
15	Foods	9/6/2018 10:23 AM
16	Middletown Young and 29th	9/6/2018 7:38 AM
47	by Old Courthouse	8/31/2018 2:33 PM
48	Burns Valley Mall	8/30/2018 3:34 PM
49	The Nott's Liquor Bus Stop	8/30/2018 11:24 AM
50	Sutter Hospital (Lakeport)	8/29/2018 7:07 PM
51	Walmart	8/29/2018 7:07 PM
52	Ruuning Creek Casino In Upper Lake	8/26/2018 11:47 AM
‡	BUS STOP 5	DATE
l	Boyles	10/18/2018 4:34 PM
2	Rotten Robbies	10/11/2018 3:51 PM
3	Walmart	10/11/2018 3:45 PM
1	Burns Vally	10/11/2018 3:34 PM
5	Nice near Dollar General	9/28/2018 12:48 PM
3	Dollar General Clearlake Oaks	9/20/2018 2:42 PM
7	4	9/20/2018 2:07 PM
3	Twer	9/20/2018 2:05 PM
)	Sutter Hospital Lakeport	9/20/2018 2:20 AM
10	Clearlake	9/19/2018 3:33 PM
11	Indian Beach, Glenhavin	9/19/2018 2:21 PM
12	Sewer-plant stop by park Rte #10	9/19/2018 2:13 PM
13	Corner of Bruster/Oak Crest, Lucerne	9/19/2018 11:08 AM
14	4	9/19/2018 10:56 AM
15	Senior Center	9/18/2018 1:54 PM
16	Park Post Office #10	9/14/2018 6:03 PM
17	Main Street	9/14/2018 5:48 PM
18	Safeway	9/14/2018 5:40 PM
19	n/a	9/12/2018 10:50 AM
20	N/a	9/11/2018 2:45 PM
21	Walmart	9/11/2018 1:38 PM
22	Grocery Outlet and Tribal Health	9/11/2018 12:32 PM
23	North Shore	9/11/2018 12:18 PM
24	#3	9/11/2018 12:12 PM
25	Robinsons	9/11/2018 11:35 AM
26	Foods, etc.	9/11/2018 10:23 AM
27	Clearlake VA Clinic	9/11/2018 10:11 AM
28	Burns Valley Mall	9/11/2018 7:37 AM

29	Mendocino Health	9/10/2018 6:06 PM
30	Pogo's Pizza, Kelseyville	9/10/2018 5:52 PM
31	Running Creek	9/10/2018 5:37 PM
32	Walmart	9/10/2018 2:54 PM
33	3rd and Main	9/10/2018 2:52 PM
34	Most stops in Clearlake	9/10/2018 2:42 PM
35	1st and Hwy. 20 in Lucerne	9/10/2018 1:54 PM
36	Kmart	9/10/2018 1:24 PM
37	Hospital	9/6/2018 10:23 AM
38	Hidden Valley	9/6/2018 7:38 AM
39	Safeway	8/31/2018 2:33 PM
40	The Clearlake City Hall Bus Stop	8/30/2018 11:24 AM
41	3rd & Main (Lakeport)	8/29/2018 7:07 PM
42	3rd and Main Lakeport	8/26/2018 11:47 AM

Q6 Please rank 1 through 6 the following improvements based on what you believe would most effectively improve safety at these bus stops, with 1 being the most effective:



	1	2	3	4	5	6	TOTAL	SCORE
Bus pull out	43.40%	11.32%	13.21%	16.98%	7.55%	7.55%		
	23	6	7	9	4	4	53	4.43
Bus stop signs	23.53%	33.33%	15.69%	5.88%	15.69%	5.88%		
	12	17	8	3	8	3	51	4.25
Bus landing pad	0.00%	23.53%	27.45%	17.65%	15.69%	15.69%		
	0	12	14	9	8	8	51	3.27
An accessible path of travel	16.67%	9.26%	11.11%	33.33%	20.37%	9.26%		
	9	5	6	18	11	5	54	3.41
Improved lighting and visibility	10.91%	10.91%	23.64%	14.55%	30.91%	9.09%		
	6	6	13	8	17	5	55	3.29
Security cameras or security guards	10.71%	12.50%	8.93%	8.93%	8.93%	50.00%		
	6	7	5	5	5	28	56	2.57

Q7 In order of preference, how would you most like to be informed about the time the bus will arrive at your bus stop?



	1	2	3	TOTAL	SCORE
Bus schedule posted at bus stop	56.00% 42	20.00% 15	24.00% 18	75	2.32
Bus schedule posted on website	12.16% 9	40.54% 30	47.30% 35	74	1.65
Real-time bus schedule on phone app or computer	36.71% 29	36.71% 29	26.58% 21	79	2.10

Appendix B
Public Meeting Display Boards



To get started, please do the following:

- 1. Sign in
- 2. Visit the display stations at your leisure
- 3. Fill out our Bus Passenger Facility Plan public survey by filling out a paper copy, or going online to:

www.surveymonkey.com/r/LTABusSurvey

Thank you for coming!






For more information, please visit www.laketransit.org

What is the Bus Passenger Facility Plan?

Lake Transit Authority (LTA) is in the process of developing a Bus Passenger Facility Plan intended to provide an overall strategy for improving bus passenger facilities in the region.








What is the Bus Passenger Facility Plan?

Lake Transit Authority (LTA) is in the process of developing a Bus Passenger Facility Plan intended to provide an overall strategy for improving bus passenger facilities in the region.







Existing Conditions

Inventory conducted for the 306 bus stops located in Lake County

Amenity	Number of bus stops with amenity	Percent of total bus stops with amenity	Percent in poor condition, may require repair/ replacement
Bus Stop Location Signage	153	50%	6%
Sign Mounting Pole	147	48%	3%
Bench	65	21%	11%
Shelter	58	19%	12%
Light at Bus Stop	64	21%	N/A
Street Light	94	31%	N/A
Wheelchair Accessibility	144	47%	N/A



Appendix C
Bus Stop Facility Inventory and Existing Conditions

Table 1.10-11: Route 1 Bus Stops

	Route 1 WB		Route 1 EB
ID	Name	ID	Name
10.01	WALMART FOOD PLACE	11.01	SUTTER LAKESIDE
10.02	KEYS BLVD	11.02	LAKE COUNTY JAIL
10.03	HWY 20 & POST OFFICE	11.03	MAIN ST & HWY 20
10.04	EAST LAKE SCHOOL	11.04	UPPER LAKE HIGH SCHOOL
10.05	LAKE ST	11.05	RUNNING CREEK CASINO
10.06	RED & WHITE MARKET	11.06	ROBINSONS CASINO
10.07	MATTRESS STORE	11.07	SENTRY MARKET
10.08	LAKEVIEW DR	11.08	COLLIER
10.09	BLUE FISH COVE	11.09	BAT HOUSE ACROSS FROM HINMAN PARK
10.10	INDIAN BEACH RESORT	11.10	MARINA GRILL
10.11	GLENHAVEN DR	11.11	WORLD MARK-NICE POST OFFICE
10.12	BRUNER DR	11.12	THE HARBOR
10.13	DRIFTWOOD LOUNGE	11.13	1ST ST & HWY 20
10.14	LAUREL DELL AT RIVERA MOTEL	11.14	2ND & HWY 20 BTWN XWALK & ALPINE PARK
10.15	BELL RAY	11.15	5TH AND HWY 20 NEAR FIRE HYDRANT IN
10.16	LAKESHORE & HWY 20	11.16	FRONT OF THE WATER SERVICE COMPANY
10.17	LUCERNE ELEMENTARY SCHOOL	11.17	9TH & HWY 20 LUCERNE HARBOR PARK
10.18	HWY 20 & 14TH	11.18	13TH & COUNTRY CLUB MARYMONT COLLEGE
10.19	TOWER MART	11.19	13TH & HWY 20 COMMUNITY GARDEN PARK
10.20	AT MARYMOUNT COLLEGE AT 13TH	11.20	16TH & HWY 20 OLD MONUMENT SIGN
10.21	HWY 20 & 9TH	11.21	LAKESHORE & HWY 20
10.22	HWY 20 & 5TH	11.22	JUST BEFORE BELL RAY
10.23	HWY 20 & 1ST ST	11.23	RIVERA MOTEL-LAUREL DELL
10.24	THE HARBOR	11.24	DRIFTWOOD LOUNGE
10.25	NICE POST OFFICE	11.25	BRUNER DR-GRAVEL PULL OUT-KONA TAYHEE
10.26	NICE MARKET	11.26	GLENHAVEN
10.27	HINMAN PARK	11.27	INDIAN BEACH RESORT
10.28	LAKEVIEW AVE	11.28	BLUE FISH COVE
10.29	SENTRY MARKET	11.29	LAKEVIEW
10.30	ROBINSONS CASINO	11.30	TOWER MART
10.31	RUNNING CREEK CASINO	11.31	THE BARN
10.32	UPPER LAKE HIGH SCHOOL	11.32	LAKE ST
10.33	MAIN ST & HWY 20	11.33	EAST LAKE SCHOOL
10.34	TURNOUT ACROSS FROM CHEVRON	11.34	HWY 20 BURGERS
10.35	LAKE COUNTY JAIL	11.35	KEYS BLVD
10.36	SUTTER LAKESIDE	11.36	ORCHARD SHORES
		11.37	WOODLAND COLLEGE
		11.38	WALMART MARKET

Table 1.20-21:	Route	2	Bus	Stops	

	Route 2 SB		Route 2 NB	
ID	Name	ID	Name	
20.01	KITS CORNER	21.01	HWY 29 & YOUNG ST	
20.02	DIAMOND DUST	21.02	HWY 175 & MCKINLEY DR	
20.03	WILD CAT CANYON	21.03	MONTE VISTA COURT DR	
20.04	SALMINA	21.04	U-TURN TO BUS STOP AT ROCK	
20.05	ADMIRAL RD	21.05	JUST NORTH OF CASA GRANDE DR	
20.06	MARIAH MEADOWS	21.06	AUSTIN DR & SR 175	
20.07	LOCH LOMOND	21.07	WHISPERING PINES	
20.08	HARRINGTON FLATS	21.08	WATER CO SIGN	
20.09	HOBERGS RESORT	21.09	GIFFORD SPRINGS	
20.10	SUMMIT	21.10	GOLF RD	
20.11	HARDESTERS	21.11	TURNOUT ACROSS FROM FIRE DEPT	
20.12	TURNOUT ACROSS FROM GIFFORD SPRINGS	21.12	HARDESTERS MARKET COBB	
20.13	THE OLD TAVERN-MAPLE SHADOWS	21.13	SUMMIT	
20.14	TURNOUT PAST WHISPERING PINES	21.14	SR 175 & ENTRANCE RD	
20.15	ANDERSON SPRINGS RD	21.15	HOBERGS RESORT	
20.16	TURNOUT JUST PAST DRY CREEK	21.16	SR 175 & HARRINGTON FLATS	
20.17	TURNOUT BY SANTA CLARA RD	21.17	LOCH LOMOND	
20.18	MINI MALL-T&J AUTO PARTS	21.18	MARIAH MEADOWS	
20.19	FIVE STAR TOWING	21.19	ADMIRAL RD	
20.20	LAKESIDE APPLIANCE	21.20	SALMINA	
20.21	TWIN PINE CASINO	21.21	WILD CAT CANYON	
20.22	PERRYS DELI	21.22	DIAMOND DUST	
20.23	CHARTER SCHOOL	21.23	RED HILLS RD	
20.24	ARMSTRONG RD	21.24	KITS CORNER	
20.25	TRI COUNTIES BANK			

Route 3 SB			Route 3 NB	
ID	Name	ID	Name	
30.01	WALMART FOOD PLACE	31.01	ST HELENA HOSPITAL	
30.02	JOB ZONE	31.02	LINCOLN AVENUE BRIDGE	
30.03	ACROSS FROM LAKE TRANSIT	31.03	TWIN PINES CASINO	
30.04	TOWER MART- 53/29	31.04	PERRYS DELI	
30.05	TWIN LAKES	31.05	ARMSTRONG RD	
30.06	HIDDEN VALLEY WATER COMPANY	31.06	CHARTER SCHOOL	
30.07	MUG SHOTS- COYOTE VALLEY PHARM	31.07	HARDESTERS MARKET	
80.08	HWY 29 & YOUNG ST-TRI COUNTIES BANK	31.08	HIDDEN VALLY WATER COMPANY	
80.09	CHARTER SCHOOL	31.09	MUG SHOTS- COYOTE VALLEY PHARM	
30.10	FIVE STAR TOWING	31.10	TWIN LAKES	
80.11	LAKE COUNTY APPLIANCE	31.11	HWY 53 & HWY 29 (FOSTER FREEZE)	
30.12	TWIN PINES CASINO	31.12	LAKE TRANSIT YARD	
30.13	LINCOLN AVENUE BRIDGE	31.13	WALMART FOOD PLACE	
30.14	ST HELENA HOSPITAL			

Гab	le 1.40-41: Route 4 Bus S	Stops			
	Route 4 WB		Route 4 EB		
ID	Name	ID	Name		
40.01	WALMART FOOD PLACE	41.01	3RD & MAIN		
40.02	JOB ZONE	41.02	MAIN & MARTIN		
40.03	ACROSS FROM LAKE TRANSIT	41.03	MAIN & D ST		
40.04	TOWER MART	41.04	BOWLING ALLEY		
40.05	KITS CORNER	41.05	SOCIAL SECURITY		
40.06	KELSEYVILLE AUTO WRECKERS	41.06	TACO BELL BEFORE DRIVEWAY		
40.07	STORE 24	41.07	BRUNOS		
40.08	GAS HILL	41.08	GROCERY OUTLET		
40.09	4TH & MAIN	41.09	HOSPICE		
40.10	PHARMACY	41.10	KMART		
40.11	ACROSS FROM KELSEYVILLE LUMBER	41.11	ROTTEN ROBBIES		
40.12	MENDO COLLEGE	41.12	KELSEYVILLE LUMBER		
40.13	ACROSS FROM ROTTEN ROBBIES	41.13	ACROSS FROM PHARMACY		
40.14	STATE FARM (ACROSS FROM KMART)	41.14	4TH & MAIN (WEST AMERICA BANK)		
40.15	NURSERY & GROCERY OUTLET	41.15	BEFORE LIVE OAK		
40.16	BOWLING ALLEY	41.16	STORE 24		
40.17	SAFEWAY	41.17	ACROSS FROM KELSEYVILLE WRECKERS		
40.18	9TH & MAIN	41.18	KITS CORNER		
40.19	3RD & MAIN	41.19	HWY 29 & HWY 53- FOSTERS		
		41.20	LAKE TRANSIT YARD		
		41.21	WALMART FOOD PLACE		

Tab	Table 1.50-51: Route 4A Bus Stops					
	Route 4A WB		Route 4A EB			
ID	Name	ID	Name			
50.01	KITS CORNER	51.01	3RD & MAIN			
50.02	RIVIERA SHOPPING CENTER	51.02	MAIN & D ST			
50.03	BAYVIEW ESTATES	51.03	D STREET			
50.04	MONTEZUMA WAY	51.04	BOWLING ALLEY			
50.05	RIVIERA WEST	51.05	SOCIAL SECURITY			
50.06	BUCKINGHAM	51.06	BEFORE TACO BELL DRIVEWAY			
50.07	SODA BAY STORE	51.07	MENDO COLLEGE			
50.08	MAIN & 3RD	51.08	BRUNOS			
50.09	FINLEY POST OFFICE	51.09	GROCERY OUTLET			
50.10	KONOCTI VISTA CASINO	51.10	HOSPICE			
50.11	KMART	51.11	KMART			
50.12	MAIN ST NURSERY & GROCERY OUTLET	51.12	ROTTEN ROBBIES			
50.13	BOWLING ALLEY	51.13	KONOCTI VISTA CASINO			
50.14	SOCIAL SECURITY	51.14	FINLEY POST OFFICE			
50.15	BEFORE TACO BELL DRIVEWAY	51.15	SODA BAY STORE			
50.16	MENDO COLLEGE	51.16	RIVERA WEST			
50.17	SAFEWAY	51.17	MONTEZUMA WAY			
50.18	9TH & MAIN	51.18	RIVERA SHOPPING CENTER			
50.19	3RD & MAIN	51.19	KITS CORNER			

Гab	le 1.70-71: Route 7 Bus \$	Stops			
Route 7 WB Route 7 EB					
ID	Name	ID	Name		
70.01	3RD & MAIN	71.01	AIRPORT		
70.02	9TH & MAIN (NATURAL HIGH)	71.02	VETERANS CLINIC		
70.03	SENTRY MARKET	71.03	71.03 PEAR TREE		
70.04	ROBINSONS CASINO	71.04	MENDOCINO COLLEGE UKIAH		
70.05	1ST & MAIN UPPER LAKE	71.05	BLUE LAKES		
70.06	BLUE LAKES	71.06	71.06 1ST & MAIN UPPER LAKE		
70.07	MENDOCINO COLLEGE UKIAH	71.07	ROBINSONS CASINO		
70.08	PEAR TREE	71.08	71.08 SENTRY MARKET		
70.09	VETERANS CLINIC	71.09	SAFEWAY		
70.10	AIRPORT	71.10	9TH & MAIN (NATURAL HIGH)		
		71.11	3RD & MAIN		

	Route 8 NB		Route 8 SB
ID	Name	ID	Name
80.01	LAKE COUNTY JAIL	81.01	MENDO COLLEGE
80.02	SUTTER HOSPITAL	81.02	AAA
80.03	LAKESIDE HEALTH CLINIC	81.03	SENIOR CENTER
80.04	NORTHPORT MOBILE HOME PARK	81.04	MARTIN ST (BELLA VISTA)
80.05	EL DORADO MOTEL	81.05	
80.06	PEOPLE SERVICES-WALNUT DR	81.06	9TH & MAIN (NATURAL HIGH)
80.07	ELKS LODGE	81.07	SAFEWAY
80.08	RAINBOW MOBILE HOME PARK	81.08	VIA DEL LAGO
80.09	PARK WAY	81.09	LAKESHORE & LANGE
80.10	TOWER MART	81.10	BEACH LN-RAINBOW LODGE
80.11	CRYSTAL LAKE DR	81.11	THE CHEATEU
80.12	BEACH LN-RAINBOW LODGE	81.12	TOWER MART
80.13	LAKESHORE & LANGE	81.13	PARK WAY
80.14	HIGH ST	81.14	ACROSS FROM RAINBOW MOBILE HOME
80.15	LIBRARY	81.15	ROCKY POINT
80.16	N.FORBES ST	81.16	ACROSS FROM PEOPLE SERVICES
80.17	9TH & MAIN	81.17	ACROSS FROM PERKS MOBILE HOME
80.18	3RD & MAIN	81.18	NORTHPORT MOBILE HOME PARK
80.19	MARTIN & MAIN	81.19	LAKESIDE HEALTH CLINIC
80.20	STARR & MARTIN (BELLA VISTA)	81.20	SUTTER HOSPITAL
80.21	TRIBAL HEALTH	81.21	LAKE COUNTY JAIL
80.22	BEVINS ACROSS FROM WIC		
80.23	BRUNOS		
80.24	GROCERY OUTLET		
80.25	KMART		
80.26	ROTTEN ROBBIES		
80.27	MENDO COLLEGE		

Table C-1

Table 1.100-110-120: Route 10, 11, 12 Bus Stops

	Route 10 Northloop		Route 11 Avenues		Route 12 Southloop
ID	Name	ID	Name	ID	Name
100.01	WALMART FOOD PLACE	110.01	WALMART FOOD PLACE	120.01	WALMART FOOD PLACE
100.02	CLEARLAKE APTS	110.02	ST.HELENA CLEARLAKE	120.02	WOODLAND COLLEGE
100.03	J&L MARKET	110.03	IRVING & 18TH	120.03	SOCIAL SERVICES
100.04	CROSSROADS CHURCH	110.04	BOYLES & 18TH	120.04	JOB ZONE
100.05	CYPRESS	110.05	BOYLES & 25TH	120.05	LAKE TRANSIT (ACROSS STREET)
100.06	MENDO MILL	110.06	BOYLES BETWEEN 30TH & 31ST	120.06	HWY 53 & MAIN ST
100.07	OLD HWY 53 & LAKESHORE	110.07	33RD & PHILLIPS	120.07	BETWEEN LAKE ST & SECOND ST
100.08	OLD RED CROSS	110.08	36TH & PHILLIPS	120.08	LOWER LAKE HIGH SCHOOL
100.09	HILL AVE	110.09	PHILLIPS & 40TH (40TH STORE)	120.09	CEMETERY
100.10	RIDGE LAKE APTS-COMMONS	110.10	45TH -THE DUMP DAVIS ST	120.10	BRYANT ST (REBECCA LODGE)
100.11	BURNS VALLEY MALL	110.11	MOSS (FIRST DRIVE WAY)	120.11	CACHE CREEK APTS
100.12	CLEARLAKE POST OFFICE	110.12	WEST AMERICA BANK	120.12	WALMART FOOD PLACE
100.13	BABY STORE (ACROSS FROM LOCUST)	110.13	CLEARLAKE FAMILY CLINIC	120.13	CLEARLAKE APTS
100.14	CITY HALL	110.14	NAPA AUTO PARTS	120.14	J&L MARKET
100.15	OLD BOWLING ALLEY	110.15	NOTT'S LIQUOR	120.15	CROSSROADS CHURCH
100.16	POMO & WOODLAND	110.16	CATFISH COFFEE	120.16	CYPRESS
100.17	BOXWOOD & ARROWHEAD	110.17	BURGER TIME	120.17	MENDO MILL (ACROSS THE STREET)
100.18	TOYON	110.18	HOSPICE	120.18	OLD HWY 53 & LAKESHORE
100.19	MODOC	110.19	OLD FIREHOUSE	120.19	NAPA AUTO PARTS
100.20	2ND ST (HALFWAY DOWN BLOCK)	110.20	AUSTIN PARK	120.20	NOTT'S LIQOUR
100.21	2ND & BUSH	110.21	HAVERTY FIELD	120.21	CATFISH COFFEE SHOP
100.22	8TH & BUSH	110.22	CLEARLAKE POST OFFICE	120.22	BURGER TIME
100.23	11TH & BUSH	110.23	BURNS VALLEY MALL	120.23	HOSPICE
100.24	13TH & COUNTRY CLUB	110.24	SENIOR CENTER	120.24	OLD FIREHOUSE
100.25	COUNTRY CLUB & ARROWHEAD	110.25	SHELTER AT WALNUT GROVE APTS	120.25	AUSTIN PARK
100.26	CLEARLAKE PARK POST OFFICE	110.26	SAFEWAY	120.26	HAVERTY FIELD
100.27	AMERICAS BEST VALUE INN	110.27	OLD HWY 53 PAST RITE AID	120.27	CLEARLAKE POST OFFICE
100.28	LAKESHORE & POMO	110.28	HIGHLANDS WAY	120.28	BURNS VALLEY MALL
100.29	CITY HALL	110.29	HILLCREST	120.29	B&G TIRES
100.30	AUSTIN PARK	110.30	VETERANS CLINIC	120.30	SENIOR CENTER
100.31	BAYLIS & LAKEHORE	110.31	VALERO	120.31	SHELTER AT WALNUT GROVE
100.32	HIGHLANDS PARK (CASTLE DONUTS)	110.32	MOSS & DAVIS (BEFORE 35MPS SIGN)	120.32	SAFEWAY
100.33	CATFISH COFFEE	110.33	PHILLIPS & 44TH	120.33	OLD HWY 53 PAST RITE AID
100.34	VETERANS CLINIC	110.34	PHILLIPS & 39TH	120.34	HIGHLANDS WAY
100.35	VALERO	110.35	32ND & PHILLIPS	120.35	HILLCREST
100.36	SOCIAL SERVICES	110.36	BOYLES & 29TH	120.36	BALLPARK-OLD 53-LAKESHORE
100.37	JOB ZONE	110.37	BETWEEN 26TH & 25TH	120.37	MENDO MILL
100.38	LAKE TRANSIT (ACROSS STREET)	110.38	BOYLES AND 21ST	120.38	KING FISHER
100.39	HWY 53 & MAIN (DL'S PIZZA)	110.39	IRVING & 18TH	120.39	CEDAR VILLAGE APTS
100.40	BETWEEN LAKE & 2ND ST	110.40	ST.HELENA CLEARLAKE	120.40	HIGHLANDS APTS
100.41	LOWER LAKE HIGH SCHOOL	110.41	WOODLAND COLLEGE	120.41	CLEARLAKE APTS
100.42	CEMETERY	110.42	END ROUTE AT WALMART	120.42	WALMART
100.43	BRYANT RD				
100.44	CACHE CREEK APTS				
100 45	WALMART				

Table 2: Lake Transit Bus Stop List (1 of 3) Unique Stops, Shown For Lowest Numbered Route Only

ID#	Bus Stop	Stop Shared With	Relative Ri Over All R	
ייטו	bus stop	11.38, 30.01, 31.13, 40.01, 41.21,	Over All R	loutes
10.01	WALMART FOOD PLACE	100.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.42	High	276
10.02	KEYS BLVD	120.01, 120.12, 120.42	Med	6
10.03	HWY 20 & POST OFFICE		Low	
10.04	EAST LAKE SCHOOL		Low	
10.05	LAKE ST		Low	
10.06	RED & WHITE MARKET		Low	
10.07	MATTRESS STORE		Low	
10.08	LAKEVIEW DR		Low	
10.09	BLUE FISH COVE		Low	
10.10	INDIAN BEACH RESORT		Low	
10.11	GLENHAVEN DR		Low	
10.12	BRUNER DR		Low	
10.13	DRIFTWOOD LOUNGE	11.24	Low	
10.14	LAUREL DELL AT RIVERA MOTEL	11.23	Low	
10.15	BELL RAY		Low	
10.16	LAKESHORE & HWY 20		Low	
10.17	LUCERNE ELEMENTARY SCHOOL		Low	
10.18	HWY 20 & 14TH		Low	
10.19	TOWER MART		Low	
10.20	AT MARYMOUNT COLLEGE AT 13TH		Low	
10.21	HWY 20 & 9TH		Med	
10.22	HWY 20 & 5TH		Med	
10.23	HWY 20 & 1ST ST		Med	
10.24	THE HARBOR		Low	
10.25	NICE POST OFFICE		Med	
10.26	NICE MARKET		Med	
10.27	HINMAN PARK		Low	
10.28	LAKEVIEW AVE		Low	
10.29	SENTRY MARKET	11.07, 70.03, 71.08	Med	
10.30	ROBINSONS CASINO	71.02, 70.04, 11.06	Med	
10.31	RUNNING CREEK CASINO	11.05	Low	
10.32	UPPER LAKE HIGH SCHOOL		Low	
10.33	MAIN ST & HWY 20		Low	
10.34	TURNOUT ACROSS FROM CHEVRON		Low	
10.35	LAKE COUNTY JAIL	11.02, 80.01, 81.21	Low	
10.36	SUTTER LAKESIDE	11.01, 80.02, 81.20	High	52
11.03	MAIN ST & HWY 20		Med	
11.04	UPPER LAKE HIGH SCHOOL		Low	
11.08	COLLIER		Low	
11.09	BAT HOUSE ACROSS FROM HINMAN PARK		Low	
11.10	MARINA GRILL		Low	
11.11	WORLD MARK-NICE POST OFFICE		Med	
11.12	THE HARBOR		Low	
11.13	1ST ST & HWY 20		Med	
11.14	2ND & HWY 20 BETWEEN XWALK & ALPINE PARK	SIGN	Low	
11.15	5TH AND HWY 20 NEAR FIRE HYDRANT IN		Low	
11.16	FRONT OF THE WATER SERVICE COMPANY		Low	
11.17	9TH & HWY 20 LUCERNE HARBOR PARK		Low	
11.18	13TH & COUNTRY CLUB MARYMONT COLLEGE		Low	
11.19	13TH & HWY 20 COMMUNITY GARDEN PARK		Low	

ID#	Bus Stop	Stop Shared With	Relative Ridership Over All Routes ¹
11.20	16TH & HWY 20 OLD MONUMENT SIGN		Low
11.21	LAKESHORE & HWY 20		Low
11.22	JUST BEFORE BELL RAY BRUNER DR-GRAVEL PULL OUT-KONA TAYHEE		Low
11.25			Low
11.26 11.27	GLENHAVEN INDIAN BEACH RESORT		Low
11.27	BLUE FISH COVE		
			Low
11.29	LAKEVIEW		Low
11.30	TOWER MART		Low
11.31	THE BARN		Low
11.32	LAKE ST		Low
11.33	EAST LAKE SCHOOL		Low
11.34	HWY 20 BURGERS		Low
11.35	KEYS BLVD		Low
11.36	ORCHARD SHORES	446	Low
11.37	WOODLAND COLLEGE	110.41, 120.02	Med
20.01	KITS CORNER	1.24, 40.05, 41.18, 50.01, 51.1	Med
20.02	DIAMOND DUST		Low
20.03	WILD CAT CANYON		Low
20.04	SALMINA		Low
20.05	ADMIRAL RD		Low
20.06	MARIAH MEADOWS		Low
20.07	LOCH LOMOND		Low
20.08	HARRINGTON FLATS		Low
20.09	HOBERGS RESORT		Low
20.10	SUMMIT		Low
20.11	HARDESTERS	21.12	Low
20.12	TURNOUT ACROSS FROM GIFFORD SPRINGS		Low
20.13	THE OLD TAVERN-MAPLE SHADOWS		Low
20.14	TURNOUT PASSED THE LAST TURN OF WHISPERIN	IG PINES	Low
20.15	ANDERSON SPRINGS RD		Low
20.16	TURNOUT JUST PAST DRY CREEK		Low
20.17	TURNOUT BY SANTA CLARA RD		Low
20.18	MINI MALL-T&J AUTO PARTS		Low
20.19	FIVE STAR TOWING		Low
20.20	LAKESIDE APPLIANCE		Low
20.21	TWIN PINE CASINO		Low
20.22	PERRYS DELI		Low
20.23	CHARTER SCHOOL	30.09, 31.06	Low
20.24	ARMSTRONG RD		Low
20.25	TRI COUNTIES BANK		Low
21.01	HWY 29 & YOUNG ST		Low
21.02	HWY 175 & MCKINLEY DR		Low
21.03	MONTE VISTA COURT DR		Low
21.04	U-TURN TO BUS STOP AT ROCK		Low
21.05	JUST NORTH OF CASA GRANDE DR		Low
21.06	AUSTIN DR & SR 175		Low
21.07	WHISPERING PINES		Low
21.08	WATER CO SIGN		Low
21.09	GIFFORD SPRINGS		Low

Table 2: Lake Transit Bus Stop List (2 of 3) Unique Stops, Shown For Lowest Numbered Route Only

Stops I	Not Lo	cated i	in l	Lake	County	Shown	in	Italics
---------	--------	---------	------	------	--------	-------	----	---------

	Bus Stop	Stop Shared With	Relative Ridership Over All Routes ¹	ID#	Bus Stop	Stop Shared With	Relative Ridership Over All Routes ¹
21.10 21.11	GOLF RD TURNOUT ACROSS FROM FIRE DEPT		Low Low	41.08 41.09	GROCERY OUTLET HOSPICE	51.09, 80.24 51.10, 110.18, 120.23	Med Low
	SUMMIT		Low	41.10	KMART	31.10, 110.16, 120.23	Med
	SR 175 & ENTRANCE RD		Low	41.11	ROTTEN ROBBIES		Low
21.15	HOBERGS RESORT		Low	41.12	KELSEYVILLE LUMBER		Low
21.16	SR 175 & HARRINGTON FLATS		Low	41.13	ACROSS FROM PHARMACY		Med
21.17	LOCH LOMOND		Low	41.14	4TH & MAIN (WEST AMERICA BANK)		Low
21.18	MARIAH MEADOWS		Low	41.15	BEFORE LIVE OAK		Low
21.19	ADMIRAL RD		Low	41.17	ACROSS FROM KELSEYVILLE WRECKERS		Low
21.20	SALMINA		Low	41.19	HWY 29 & HWY 53- FOSTERS		Low
21.21	WILD CAT CANYON		Low	50.02	RIVIERA SHOPPING CENTER		Low
21.22	DIAMOND DUST		Low	50.03	BAYVIEW ESTATES		Low
21.23	RED HILLS RD		Low	50.04	MONTEZUMA WAY		Low
30.02	JOB ZONE	40.02, 100.37, 120.04	Low	50.05	RIVIERA WEST		Low
30.03	ACROSS FROM LAKE TRANSIT	40.03, 100.38, 120.05	Low	50.06	BUCKINGHAM		Low
30.04	TOWER MART- 53/29	, 200.00, 120.00	Low	50.07	SODA BAY STORE		Low
30.05	TWIN LAKES	31.1	Low	50.09	FINLEY POST OFFICE		Low
30.06	HIDDEN VALLEY WATER COMPANY	31.08	Low	50.10	KONOCTI VISTA CASINO	51.13	Low
30.07	MUG SHOTS- COYOTE VALLEY PHARM	31.09	Low	50.11	KMART	31.13	Low
30.08	HWY 29 & YOUNG ST-TRI COUNTIES BANK	31.03	Low	51.02	MAIN & D ST		Low
30.10	FIVE STAR TOWING		Low	51.03	D STREET		Low
30.11	LAKE COUNTY APPLIANCE		Low	51.03	KMART	80.25	Low
30.12	TWIN PINES CASINO		Low	51.12	ROTTEN ROBBIES	80.26	Low
30.13	LINCOLN AVENUE BRIDGE		Low	51.12	FINLEY POST OFFICE	80.20	Low
30.13	ST HELENA HOSPITAL	31.01	Low	51.14	SODA BAY STORE		Low
31.02	LINCOLN AVENUE BRIDGE	51.01	Med	51.15	RIVERA WEST		Low
							-
31.03	TWIN PINES CASINO		Low	51.17	MONTEZUMA WAY		Low
31.04 31.05	PERRYS DELI ARMSTRONG RD		Low	51.18 70.02	RIVERA SHOPPING CENTER	71 10 01 00	Low
31.05	HARDESTERS		 		9TH & MAIN (NATURAL HIGH) 1ST & MAIN UPPER LAKE	71.10, 81.06 71.06	Low
			Low	70.05		71.00	
31.11	HWY 53 & HWY 29 (FOSTER FREEZE) LAKE TRANSIT YARD	41.2	Low	70.06	BLUE LAKES MENDOCINO COLLEGE UKIAH	71.04	Low
31.12	TOWER MART	41.2	Low	70.07	PEAR TREE	71.04	Low
40.04	KELSEYVILLE AUTO WREKCERS		Low	70.08		71.03	Low
40.06		41.16	Low	70.09	VETERANS CLINIC	71.02	Low
40.07	STORE 24	41.16	Low	70.10	AIRPORT	71.01	Low
40.08	GAS HILL 4TH & MAIN		Low	71.05	BLUE LAKES	04.40	Low
			Low	80.03	LAKESIDE HEALTH CLINIC	81.19	Low
	PHARMACY		Low	80.04	NORTHPORT MOBILE HOME PARK	81.18	Low
	ACROSS FROM KELSEYVILLE LUMBER	F0.46 F4.07 00.07 04.01	Low	80.05	EL DORADO MOTEL		Low
40.12	MENDO COLLEGE	50.16, 51.07, 80.27, 81.01	Low	80.06	PEOPLE SERVICES-WALNUT DR		Low
40.13	ACROSS FROM ROTTEN ROBBIES		Low	80.07	PAINTON MODILE HOME DARK		Low
40.14	STATE FARM (ACROSS FROM KMART)	FO 42	Low	80.08	RAINBOW MOBILE HOME PARK		Low
40.15	NURSERY & GROCERY OUTLET	50.12	Low	80.09	PARK WAY		Low
40.16	BOWLING ALLEY	41.04, 50.13, 51.04	Low	80.10	TOWER MART		Low
40.17	SAFEWAY	50.17, 71.09, 81.07	Med	80.11	CRYSTAL LAKE DR		Low
	9TH & MAIN	50.18, 80.17	Low	80.12	BEACH LN-RAINBOW LODGE		Low
40.19	3RD & MAIN	50.08, 50.19, 80.18	Low	80.13	LAKESHORE & LANGE		Low
41.01	3RD & MAIN	51.01, 70.01, 71.06, 81.05	High 27	80.14	HIGH ST		Low
41.02	MAIN & MARTIN	80.19	Low	80.15	LIBRARY		Low
41.03	MAIN & D ST		Low	80.16	N.FORBES ST		Low
41.05	SOCIAL SECURITY	50.14, 51.05	Low	80.20	STARR & MARTIN (BELLA VISTA)		Low
41.06	TACO BELL BEFORE DRIVEWAY	50.15, 51.06	Low	80.21	TRIBAL HEALTH		Low

Table 2: Lake Transit Bus Stop List (3 of 3) Unique Stops, Shown For Lowest Numbered Route Only

ID#	Bus Stop	Stop Shared With	Relative Ridership Over All Routes	ID#	Bus Stop	Stop Shared With	Relative Ridership Over All Routes
81.02	AAA		Low	100.42	CEMETERY	120.09	Low
81.03	SENIOR CENTER	110.24, 120.30	Med	100.43	BRYANT RD	120.10	Low
81.04	MARTIN ST (BELLA VISTA)		Low	100.44	CACHE CREEK APTS	120.11	Low
81.08	VIA DEL LAGO		Low	110.02	ST.HELENA CLEARLAKE		Low
81.09	LAKESHORE & LANGE		Low	110.03	IRVING & 18TH		Low
81.10	BEACH LN-RAINBOW LODGE		Low	110.04	BOYLES & 18TH		Low
81.11	THE CHEATEU		Low	110.05	BOYLES & 25TH		Low
81.12	TOWER MART		Low	110.06	BOYLES BETWEEN 30TH & 31ST		Low
81.13	PARK WAY		Low	110.07	33RD & PHILLIPS		Low
81.14	ACROSS FROM RAINBOW MOBILE HOME		Low	110.08	36TH & PHILLIPS		Low
81.15	ROCKY POINT		Low	110.09	PHILLIPS & 40TH (40TH STORE)		Low
81.16	ACROSS FROM PEOPLE SERVICES		Low	110.10	45TH -THE DUMP DAVIS ST		Low
81.17	ACROSS FROM PERKS MOBILE HOME		Low	110.11	MOSS (FIRST DRIVE WAY)		Low
100.02	CLEARLAKE APTS	120.13	Med	110.12	WEST AMERICA BANK		Med
100.03	J&L MARKET	120.14	Low	110.13	CLEARLAKE FAMILY CLINIC		Med
100.04	CROSSROADS CHURCH	120.15	Low	110.14	NAPA AUTO PARTS	120.19	Low
100.05	CYPRESS	120.16	Low	110.14	NOTT'S LIQUOR	120.13	Low
		120.16				120.21	+
100.06	MENDO MILL		Low	110.16	CATFISH COFFEE	120.21	Med
100.07	OLD HWY 53 & LAKESHORE		Med	110.17	BURGER TIME	120.22	Low
100.08	OLD RED CROSS		Low	110.19	OLD FIREHOUSE	120.24	Low
100.09	HILL AVE		Low	110.20	AUSTIN PARK	120.25	Low
100.10	RIDGE LAKE APTS-COMMONS		Med	110.21	HAVERTY FIELD	120.26	Low
100.11	BURNS VALLEY MALL		Low	110.22	CLEARLAKE POST OFFICE	120.27	Low
100.12	CLEARLAKE POST OFFICE		Med	110.23	BURNS VALLEY MALL		Low
100.13	BABY STORE (ACROSS FROM LOCUST)		Low	110.25	SHELTER AT WALNUT GROVE APTS	120.31	Low
100.14	CITY HALL		Low	110.26	SAFEWAY	120.32	Low
100.15	OLD BOWLING ALLEY		Low	110.27	OLD HWY 53 PAST RITE AID	120.33	Low
100.16	POMO & WOODLAND		Low	110.28	HIGHLANDS WAY	120.34	Low
100.17	BOXWOOD & ARROWHEAD		Med	110.29	HILLCREST	120.35	Low
100.18	TOYON		Low	110.32	MOSS & DAVIS (BEFORE 35MPS SIGN)	120.55	Low
100.19	MODOC		Low	110.32	PHILLIPS & 44TH		Low
							+ + + + + + + + + + + + + + + + + + + +
100.20	2ND ST (HALFWAY DOWN BLOCK)		Low	110.34	PHILLIPS & 39TH		Low
100.21	2ND & BUSH		Med	110.35	32ND & PHILLIPS		Low
100.22	8TH & BUSH		Low	110.36	BOYLES & 29TH		Low
100.23	11TH & BUSH		Low	110.37	BETWEEN 26TH & 25TH		Low
100.24	13TH & COUNTRY CLUB		Low	110.38	BOYLES AND 21ST		Low
100.25	COUNTRY CLUB & ARROWHEAD		Low	110.39	IRVING & 18TH		Low
100.26	CLEARLAKE PARK POST OFFICE		Low	110.40	ST.HELENA CLEARLAKE		Low
100.27	AMERICAS BEST VALUE INN		Med	120.03	SOCIAL SERVICES		Low
100.28	LAKESHORE & POMO		Low	120.07	BETWEEN LAKE ST & SECOND ST		Low
100.29	CITY HALL		Low	120.17	MENDO MILL (ACROSS THE STREET)		Low
100.30	AUSTIN PARK		Low	120.18	OLD HWY 53 & LAKESHORE		Low
100.31	BAYLIS & LAKEHORE		Med	120.20	NOTT'S LIQOUR		Low
100.32	HIGHLANDS PARK (CASTLE DONUTS)		Low	120.28	BURNS VALLEY MALL		Low
100.32	CATFISH COFFEE		Med	120.29	B&G TIRES		Low
		110.20					
100.34	VALERO	110.30	Med	120.36	BALLPARK-OLD HWY 53-LAKESHORE		Low
100.35	VALERO	110.31	Low	120.37	MENDO MILL		Low
100.36	SOCIAL SERVICES		Low	120.38	KING FISHER		Low
100.39	HWY 53 & MAIN (DL'S PIZZA)	120.06	Low	120.39	CEDAR VILLAGE APTS		Low
100.40	BETWEEN LAKE & 2ND ST		Med	120.40	HIGHLANDS APTS		Low
100.41	LOWER LAKE HIGH SCHOOL	120.08	High	120.41	CLEARLAKE APTS	İ	Low

Table 3.10: Locations of Bus Stop for Route 1 Westbound

Bus Stop				6			
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
10.01	WALMART FOOD PLACE	11.38, 30.01, 31.13, 40.01, 41.21, 100.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.42	Clearlake	Dam Road Ext.	N/A	38.9299	-122.61576
10.02	KEYS BLVD		Clearlake Oaks	S.R. 20	Keys Blvd	39.02523	-122.65931
10.03	HWY 20 & POST OFFICE		Clearlake Oaks	S.R. 20	N/A	39.02634	-122.66170
10.04	EAST LAKE SCHOOL		Clearlake Oaks	S.R. 20	N/A	39.02777	-122.6666
10.05	LAKE ST		clearlake oaks	S.R. 20	Lake St	39.0261	-122.671
10.06	RED & WHITE MARKET		clearlake oaks	S.R. 20	N/A	39.02427	-122.6744
10.07	MATTRESS STORE		clearlake oaks	S.R. 20	Pine St	39.02275	-122.6752
10.08	LAKEVIEW DR		clearlake oaks	S.R. 20	Lakeview Dr	39.12487	-122.8603
10.09	BLUE FISH COVE		Clearlake Oaks	S.R. 20	Spring Rd	39.02181	-122.71273
10.10	INDIAN BEACH RESORT		Indian Beach	S.R. 20	Indian Beach Resort	39.02402	-122.7236
10.11	GLENHAVEN DR		Glenhaven	Glenhaven Dr	S.R 20	39.02594	-122.7305
10.12	BRUNER DR		Lucerne	Bruner Dr	S.R 20	39.04314	-122.7757
10.13	DRIFTWOOD LOUNGE	11.24	Lucerne	Lakeshore	N/A	39.06735	-122.7832
10.14	LAUREL DELL AT RIVERA MOTEL	11.23	Lucerne	S.R. 20	Frontage Rd	39.06893	-122.7826
10.15	BELL RAY		Lucerne	S.R. 20	Frontage Rd	39.07661	-122.7829
10.16	LAKESHORE & HWY 20		Lucerne	S.R. 20	Lakeshore	39.07889	-122.7860
10.17	LUCERNE ELEMENTARY SCHOOL		Lucerne	Country Club	17th	39.08339	-122.7907
10.18	HWY 20 & 14TH		Lucerne	S.R. 20	14th	39.08339	-122.7907
10.19	TOWER MART		Lucerne	S.R. 20	12th	39.02164	-122.6753
10.20	AT MARYMOUNT COLLEGE AT 13TH		Lucerne	13th	Country club	39.08929	-122.7905
10.21	HWY 20 & 9TH		Lucerne	S.R. 20	9th	39.09047	-122.7957
10.22	HWY 20 & 5TH		Lucerne	S.R. 20	5th	39.09229	-122.7983
10.23	HWY 20 & 1ST ST		Lucerne	S.R. 20	1st	39.09532	-122.8008
10.24	THE HARBOR		Lucerne	S.R. 20	Foothill Dr	39.09916	-122.8043
10.25	NICE POST OFFICE		Nice	S.R. 20	N/A	39.1203	-122.8366
10.26	NICE MARKET		Nice	S.R. 20	N/A	39.12701	-122.8403
10.27	HINMAN PARK		Nice	S.R. 20	Keeling Ave	39.12312	-122.8459
10.28	LAKEVIEW AVE		Nice	S.R. 20	Lakeview Dr	39.12423	-122.85029
10.29	SENTRY MARKET	11.07, 70.03, 71.08	Nice	S.R. 20	Lake	39.12901	-122.8711
10.30	ROBINSONS CASINO	71.07, 70.04, 11.06	Nice	S.R. 20	N/A	39.14162	-122.8816
10.31	RUNNING CREEK CASINO	11.05	Nice	S.R. 20		39.1609	-122.9040
10.32	UPPER LAKE HIGH SCHOOL		Upper Lake	Old Lucerne	1st	39.16464	-122.9026
10.33	MAIN ST & HWY 20		Upper Lake	S.R. 20	Main	39.16275	-122.91123
10.34	TURNOUT ACROSS FROM CHEVRON		Lakeport	Main	Konocti	39.16304	-122.9208
10.35	LAKE COUNTY JAIL	11.02, 80.01, 81.21	Lakeport	Hill Rd	-	39.10437	-122.9135
10.36	SUTTER LAKESIDE	11.01, 80.02, 81.20	North Lakeport	Parking Lot	N/A	39.10452	-122.9072

Table 3.11: Locations of Bus Stop for Route 1 Westbound

Bus Stop	Due Chan Name	Parada	A	Charact	Constant	LAT	LONG
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
11.01	SUTTER LAKESIDE	10.36, 80.02, 81.20	North Lakeport	Parking Lot	N/A	39.10452	-122.907216
11.02	LAKE COUNTY JAIL	10.35, 80.01, 81.21	Lakeport	Hill Rd	-	39.10437	-122.91355
11.03	MAIN ST & HWY 20		Upper Lake	S.R. 20	Main	39.16275	-122.911231
11.04	UPPER LAKE HIGH SCHOOL		Upper Lake	Old Lucerne	1st	39.16464	-122.90261
11.05	RUNNING CREEK CASINO	10.31	Nice	S.R. 20	-	39.1609	-122.90402
11.06	ROBINSONS CASINO	71.07, 70.04, 10.30	Nice	S.R. 20	N/A	39.14162	-122.88164
11.07	SENTRY MARKET	10.29, 70.03, 71.08	Nice	S.R. 20	Lake	39.12901	-122.87112
11.08	COLLIER		Nice	S.R. 20	Collier	39.12498	-122.86105
11.09	BAT HOUSE ACROSS FROM HINMAN PARK		Nice	S.R. 20	Keeling Ave	39.1229	-122.84595
11.10	MARINA GRILL		Nice	S.R. 20	N/A	39.12231	-122.84180
11.11	WORLD MARK-NICE POST OFFICE		Nice	S.R. 20	N/A	39.1203	-122.836676
11.12	THE HARBOR		Lucerne	S.R. 20	Foothill Dr	39.09916	-122.80437
11.13	1ST ST & HWY 20		Lucerne	S.R. 20	1st	39.09532	-122.8008
11.14	2ND & HWY 20 BTWN XWALK & ALPINE PARK SIG	N	Lucerne	S.R. 20	2nd	39.09348	-122.778074
11.15	5TH AND HWY 20 NEAR FIRE HYDRANT		Lucerne	S.R. 20	5th	39.09229	-122.79832
11.16	FRONT OF THE WATER SERVICE COMPANY		Lucerne	S.R. 20	7th	38.81239	-122.71112
11.17	9TH & HWY 20 LUCERNE HARBOR PARK		Lucerne	S.R. 20	9th	39.09001	-122.79578
11.18	13TH & COUNTRY CLUB MARYMONT COLLEGE		Lucerne	S.R. 20	13th	39.08929	-122.79056
11.19	13TH & HWY 20 COMMUNITY GARDEN PARK		Lucerne	S.R. 20	13th	39.08713	-122.79352
11.20	16TH & HWY 20 OLD MONUMENT SIGN		Lucerne	S.R. 20	16th	39.08559	-122.79182
11.21	LAKESHORE & HWY 20		Lucerne	S.R. 20	Lakeshore	39.07889	-122.78603
11.22	JUST BEFORE BELL RAY		Lucerne	S.R. 20	Bell Ray	39.07673	-122.78332
11.23	LAUREL DELL AT RIVERA MOTEL	10.14	Lucerne	S.R. 20	Frontage Rd	39.06893	-122.78261
11.24	DRIFTWOOD LOUNGE	10.13	Lucerne	Lakeshore	N/A	39.06735	-122.78321
11.25	BRUNER DR-GRAVEL PULL OUT-KONA TAYHEE		Lucerne	S.R. 20	BRUNER DR	39.04269	-122.77568
11.26	GLENHAVEN		Glenhaven	S.R. 20	N/A	39.02594	-122.73051
11.27	INDIAN BEACH RESORT		Indian Beach	S.R. 20	Indian Beach Resort	39.02402	-122.72368
11.28	BLUE FISH COVE		Clearlake Oaks	S.R. 20	N/A	39.02181	-122.712731
11.29	LAKEVIEW		Clearlake Oaks	S.R. 20	Lakeview Dr	39.12487	-122.86037
11.30	TOWER MART		Clearlake Oaks	S.R. 20	12th	39.02164	-122.67537
11.31	THE BARN		Clearlake Oaks	Short St.	S.R. 20	39.02305	-122.67497
11.32	LAKE ST		clearlake oaks	S.R. 20	Lake St	39.0261	-122.671
11.33	EAST LAKE SCHOOL		Clearlake Oaks	S.R. 20	N/A	39.02777	-122.66669
11.34	HWY 20 BURGERS		Clearlake Oaks	S.R. 20	N/A	39.02621	-122.66197
11.35	KEYS BLVD		Clearlake Oaks	S.R. 20	Keys Blvd	39.02523	-122.65931
11.36	ORCHARD SHORES		Clearlake	Orchard Shore	Apple	39.01905	-122.653012
11.37	WOODLAND COLLEGE	110.41, 120.02	Clearlake	-		38.93279	-122.61704
11.38	WALMART FOOD PLACE	10.01, 30.01, 31.13, 40.01, 41.21, 100.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.42	Clearlake	Dam Road Ext.	N/A	38.9299	-122.61576

Table 3.20: Locations of Bus Stop for Route 2 Southbound

Bus Stop							
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
20.01	KITS CORNER	21.24, 40.05, 41.18, 50.01, 51.19	Soda Bay	S.R. 29	S.R. 281	38.93	-122.743
20.02	DIAMOND DUST		Soda Bay	S.R. 175	Diamond dust	38.9049	-122.75526
20.03	WILD CAT CANYON		Soda Bay	S.R. 175	Wild cat Rd	38.89055	-122.73385
20.04	SALMINA		Soda Bay	S.R. 175	salmina Rd	38.88899	-122.73168
20.05	ADMIRAL RD		Soda Bay	S.R. 175	Admiral Wy	38.88805	-122.73042
20.06	MARIAH MEADOWS		Loch Lommand	S.R. 175	-	38.87605	-122.72836
20.07	LOCH LOMOND		Loch Lommand	S.R. 175	Loch Lommand	38.86337	-122.71848
20.08	HARRINGTON FLATS		Loch Lommand	S.R. 175	Harrington flat Rd	38.85379	-122.72303
20.09	HOBERGS RESORT		Cobb	S.R. 175	Grouse Rd	38.84959	-122.72758
20.10	SUMMIT		Cobb	S.R. 175	Summit Blvd	38.83746	-122.7321
20.11	HARDESTERS	21.12	Cobb	S.R. 175	N/A	38.82533	-122.7220
20.12	TURNOUT ACROSS FROM GIFFORD SPRINGS		Cobb	S.R. 175	Gifford springs	38.81487	-122.71254
20.13	THE OLD TAVERN-MAPLE SHADOWS		Cobb	S.R. 175	Shadows Dr	38.81355	-122.7118
20.14	TURNOUT PAST WHISPERING PINES		Cobb	S.R. 175	MaDrone Vista	38.8054	-122.70598
20.15	ANDERSON SPRINGS RD		Cobb	S.R. 175	Anderson Springs Road	38.77852	-122.6816
20.16	TURNOUT JUST PAST DRY CREEK		Middletown	S.R. 175	Dry Creek	38.75904	-122.6407
20.17	TURNOUT BY SANTA CLARA RD		Middletown	S.R. 175	Santa Clara Dr	38.75333	-122.6197
20.18	MINI MALL-T&J AUTO PARTS		Middletown	Olympic	Buckeye	38.75245	-122.6158
20.19	FIVE STAR TOWING		Middletown	Olympic	Buckeye	38.75158	-122.6160
20.20	LAKESIDE APPLIANCE		Middletown	Lakeshore Rd	Howard Ave	38.74934	-122.6166
20.21	TWIN PINE CASINO		Middletown	Twins Pine Casino	N/A	38.73237	-122.6239
20.22	PERRYS DELI		Middletown	S.R. 29	N/A	38.74133	-122.62951
20.23	CHARTER SCHOOL	30.09, 31.06	Middletown	Washington	Armstrong	38.75161	-122.61478
20.24	ARMSTRONG RD		Middletown	Calistoga Rd	Armstrong	38.75134	-122.6155
20.25	TRI COUNTIES BANK		Middletown	S.R. 29	Young St.	38.75345	-122.6146

Table 3.21: Locations of Bus Stop for Route 2 Northbound

Bus Stop							
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
21.01	HWY 29 & YOUNG ST		Middletown	S.R. 29	Young St.	38.75345	-122.61468
21.02	HWY 175 & MCKINLEY DR		Cobb	S.R. 175	Mckinley Dr	38.77293	-122.666289
21.03	MONTE VISTA COURT DR		Cobb	S.R. 175	Monte Vista Dr	38.77422	-122.66961
21.04	U-TURN TO BUS STOP AT ROCK		Cobb	S.R. 175	Rock	38.793	-122.672931
21.05	JUST NORTH OF CASA GRANDE DR		Cobb	S.R. 175	Casa Grande Dr	38.80238	-122.705284
21.06	AUSTIN DR & SR 175		Cobb	S.R. 175	Austin	38.80554	-122.705296
21.07	WHISPERING PINES		Cobb	S.R. 175	N/A	38.81008	-122.709906
21.08	WATER CO SIGN		Cobb	S.R. 175	N/A	38.81239	-122.71112
21.09	GIFFORD SPRINGS		Cobb	S.R. 175	Gifford springs	38.81451	-122.711983
21.10	GOLF RD		Cobb	Lakeshore	Golf	38.81664	-122.71908
21.11	TURNOUT ACROSS FROM FIRE DEPT		Cobb	S.R. 175	Shwartz Rd	38.8221	-122.714021
21.12	HARDESTERS	20.11	Cobb	S.R. 175	N/A	38.82533	-122.72202
21.13	SUMMIT		Cobb	S.R. 175	Summit Blvd	38.83746	-122.720233
21.14	SR 175 & ENTRANCE RD		Cobb	S.R. 175	Entrance Rd	38.841	-122.724050
21.15	HOBERGS RESORT		Cobb	S.R. 175	Grouse Rd	38.8478	-122.7278678
21.16	SR 175 & HARRINGTON FLATS		Loch Lommand	S.R. 175	Harrington flat Rd	38.85379	-122.723036
21.17	LOCH LOMOND		Loch Lommand	S.R. 175	Loch Lommand	38.86337	-122.718483
21.18	MARIAH MEADOWS		Loch Lommand	S.R. 175	-	38.87605	-122.728368
21.19	ADMIRAL RD		Soda Bay	S.R. 175	Admiral Wy	38.88899	-122.731681
21.20	SALMINA		Soda Bay	Dam Road Ext.	Yuba	38.88805	-122.730425
21.21	WILD CAT CANYON		Soda Bay	S.R. 175	Wild cat Rd	38.89055	-122.733857
21.22	DIAMOND DUST		Soda Bay	S.R. 175	Diamond dust	38.9049	-122.755268
21.23	RED HILLS RD		Soda Bay	S.R. 175	Red Hills Rd	38.91108	-122.764206
21.24	KITS CORNER	20.01, 40.05, 41.18, 50.01, 51.19	Soda Bay	S.R. 29	S.R. 281	38.94982	-122.615296

Table 3.30: Locations of Bus Stop for Route 3 Southbound

Bus Stop							
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
30.01	WALMART FOOD PLACE	11.38, 10.01, 31.13, 40.01, 41.21, 100.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.42	Clearlake	Dam Road Ext.	N/A	38.9299	-122.61576
30.02	JOB ZONE	40.02, 100.37, 120.04	Clearlake	S. R 53	Parking Lot	38.91701	-122.6124
30.03	ACROSS FROM LAKE TRANSIT	40.03, 100.38, 120.05	Clearlake Oaks	S.R. 53	N/A	38.9149	-122.61240
30.04	TOWER MART- 53/29		Clearlake Oaks	S.R. 53	S. R. 29	39.02164	-122.6753
30.05	TWIN LAKES	31.10	Clearlake Oaks	C Street	May Hollow Rd	38.88035	-122.61362
30.06	HIDDEN VALLEY WATER COMPANY	31.08	Clearlake Oaks	Hidden Valley Rd	Hatrmann Rd	38.79757	-122.554
30.07	COYOTE VALLEY PHARM	31.09	Middletown	S.R 29	Putah Ln	38.7952	-122.557
30.08	HWY 29 & YOUNG ST-TRI COUNTIES BANK		Middletown	S.R. 29	Young St.	38.75345	-122.6146
30.09	CHARTER SCHOOL	20.23, 31.06	Middletown	Washington	Armstrong	38.75161	-122.61478
30.10	FIVE STAR TOWING		Middletown	Olympic	Buckeye	38.75158	-122.6160
30.11	LAKE COUNTY APPLIANCE		Middletown	S.R 29	Armstrong Rd	38.74934	-122.61666
30.12	TWIN PINES CASINO		Middletown	Twins Pine Casino	N/A	38.7326	-122.624
30.13	LINCOLN AVENUE BRIDGE		Calistoga	Lincoln Ave	Cedar St	38.58167	-122.5768
30.14	ST HELENA HOSPITAL	31.01	Deer Park	Hospital Parking lot	Hospital Parking lot	38.54255	-122.4748

Table 3.31: Locations of Bus Stop for Route 3 Northbound

Bus Stop							
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
31.01	ST HELENA HOSPITAL	30.14	Deer Park	Hospital Parking lot	Hospital Parking lot	38.54255	-122.474827
31.02	LINCOLN AVENUE BRIDGE		Calistoga	Lincoln Ave	Cedar St	38.58167	-122.576879
31.03	TWIN PINES CASINO		Middletown	Twins Pine Casino	N/A	38.7326	-122.624
31.04	PERRYS DELI		Middletown	S.R. 29	N/A	38.692	-122.6171417
31.05	ARMSTRONG RD		Middletown	Calistoga Rd	Armstrong	38.75134	-122.615567
31.06	Charter School	20.23, 30.09	Middletown	Washington	Armstrong	38.75161	-122.6147898
31.07	HARDESTERS		Middletown	Washington	Young	38.82533	-122.72202
31.08	HIDDEN VALLEY WATER COMPANY	30.06	Middletown	Hidden Valley Rd	Hatrmann Rd	38.79757	-122.554
31.09	MUG SHOTS- COYOTE VALLEY PHARM	30.07	Middletown	S.R 29	Putah Ln	38.7952	-122.557
31.1	TWIN LAKES	30.05	Lower Lake	C Street	May Hollow Rd	38.88035	-122.613625
31.11	HWY 53 & HWY 29 (FOSTER FREEZE)		Lower Lake	S.R. 53	S.R. 29	38.91085	-122.612107
31.12	LAKE TRANSIT YARD	41.2	Clearlake Oaks	S.R. 20	N/A	38.91481	-122.611861
31.13	WALMART FOOD PLACE	11.38, 30.01, 40.01, 10.01, 41.21, 100.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.41	Clearlake	Dam Road Ext.	N/A	37.9299	-123.615764

Table 3.40: Locations of Bus Stop for Route 4 Westbound

Bus Stop							
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
40.01	WALMART FOOD PLACE	11.38, 30.01, 31.13, 10.01, 41.21, 100.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.42	Clearlake	Dam Road Ext.	N/A	38.9299	-122.61570
40.02	JOB ZONE	30.02, 100.37, 120.04	Clearlake	S. R 53	Parking Lot	38.91701	-122.6124
40.03	ACROSS FROM LAKE TRANSIT	30.03, 100.38, 120.05	Clearlake Oaks	S.R. 53	N/A	38.9149	-122.6124
40.04	TOWER MART		Clearlake Oaks	S.R. 53	S. R. 29	39.02164	-122.6753
40.05	KITS CORNER	21.24, 20.01, 41.18, 50.01, 51.19	Soda Bay	S.R. 29	S.R. 281	38.94982	-122.6152
40.06	Kelseyville Auto Wreckers		Kelseyville	S.R. 29	N/A	38.9418	-122.7783
40.07	STORE 24	41.16	Kelseyville	Forrest's Rd	Main	38.97476	-122.83210
40.08	GAS HILL		Kelseyville	Main	N/A	38.97626	-122.8330
40.09	4TH & MAIN		Kelseyville	Main	4th	38.97778	-122.8366
40.10	PHARMACY		Kelseyville	Main	1st	38.97833	-122.84
40.11	ACROSS FROM KELSEYVILLE LUMBER		Kelseyville	North Main	N/A	38.98126	-122.8454
40.12	MENDO COLLEGE	50.16, 51.07, 80.27, 81.01	Lakeport	Mendocino College	S.R. 29	39.18992	-123.2276
40.13	ACROSS FROM ROTTEN ROBBIES		Lakeport	S Main	N/A	39.0186	-122.912
40.14	STATE FARM (ACROSS FROM KMART)		Lakeport	S. Main	N/A	39.033	-122.915
40.15	NURSERY & GROCERY OUTLET	50.12	Lakeport	S. Main	Lakeport	39.03412	-122.915
40.16	BOWLING ALLEY	41.04, 50.13, 51.04	Lakeport	Lakeport Blvd	Larrecou Ln	39.03473	-122.921
40.17	SAFEWAY	50.17, 71.09, 81.07	Lakeport	Olympic	Burns Valley	39.04885	-122.925
40.18	9TH & MAIN	50.18, 80.17	Lakeport	Main	9th	39.04733	-122.915
40.19	3RD & MAIN	50.08, 50.20, 80.18	Lakeport	Main	3rd	39.04369	-122.9153

Table 3.41: Locations of Bus Stop for Route 4 Eastbound

Bus Stop							
ID .	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
41.01	3RD & MAIN	51.01, 70.01, 71.11, 81.05	Lakeport	Main	3rd	39.04369	-122.915302
41.02	MAIN & MARTIN	80.19	Lakeport	Main	Martin	39.04057	-122.915331
41.03	MAIN & D ST		Lakeport	Main	D St	39.03825	-122.91536
41.04	BOWLING ALLEY	40.16, 50.13, 51.04	Lakeport	Lakeport Blvd	Larrecou Ln	39.03473	-122.92149
41.05	SOCIAL SECURITY	50.14, 51.05	Lakeport	Parallel	Westside Park Rd	39.03475	-122.92573
41.06	TACO BELL BEFORE DRIVEWAY	50.15, 51.06	Lakeport	Parallel	Todd Rd	39.0323	-122.925
41.07	BRUNOS	51.08, 80.23	Lakeport	Lakeport	N/A	39.0323	-122.925
41.08	GROCERY OUTLET	51.09, 80.24	Lakeport	S Main St	Christopher Ln	39.03413	-122.915886
41.09	HOSPICE	51.10, 110.18, 120.23	Lakeport	Lakeshore	N/A	38.95441	-122.645269
41.1	KMART		Lakeport	S. Main	N/A	39.027	-122.918
41.11	ROTTEN ROBBIES		Lakeport	S Main	N/A	39.01862	-122.912794
41.12	KELSEYVILLE LUMBER		Kelseyville	S.R 175	Merrit Rd	38.98126	-122.845499
41.13	ACROSS FROM PHARMACY		Kelseyville	Main	1st	38.9782	-122.840993
41.14	4TH & MAIN (WEST AMERICA BANK)		Kelseyville	Main	4th	38.97769	-122.8373975
41.15	BEFORE LIVE OAK		Kelseyville	Main	Live Oak	38.97616	-122.833208
41.16	STORE 24	40.07	Kelseyville	Forrest's Rd	Main	38.97476	-122.8321686
41.17	ACROSS FROM KELSEYVILLE WRECKERS		Kelseyville	S.R. 29	N/A	38.9418	-122.778336
41.18	KITS CORNER	21.24, 40.05, 20.01, 50.01, 51.19	Soda Bay	S.R. 29	S.R. 281	38.94982	-122.615296
41.19	HWY 29 & HWY 53- FOSTERS		Lower Lake	S.R. 53	S.R. 29	38.88035	-122.613625
41.2	LAKE TRANSIT YARD	31.12	Clearlake Oaks	S.R. 20	N/A	38.91481	-122.611861
41.21	WALMART FOOD PLACE	11.38, 30.01, 31.13, 40.01, 10.01, 100.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.42	Clearlake	Dam Road Ext.	N/A	38.9299	-122.615764

Table 3.50: Locations of Bus Stop for Route 4A Westbound

Bus Stop							
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
50.01	KITS CORNER	21.24, 40.05, 20.01, 41.18, 51.19	Soda Bay	S.R. 29	S.R. 281	38.94982	-122.61529
50.02	RIVIERA SHOPPING CENTER		Soda Bay	Soda Bay Road	North of Riviera	38.9524	-122.72949
50.03	BAYVIEW ESTATES		Soda Bay	Soda Bay Rd	N/A	38.97534	-122.74293
50.04	MONTEZUMA WAY		Soda Bay	Montezuma	Soda Bay Rd	38.98051	-122.74254
50.05	RIVIERA WEST		Soda Bay	Soda Bay Road	Riviera West	38.99164	-122.74797
50.06	BUCKINGHAM		Soda Bay	Westlake Dr	N/A	39.00075	-122.75176
50.07	SODA BAY STORE		Soda Bay	Soda Bay Rd	Pine Ave	39.00111	-122.79194
50.08	3RD & MAIN	40.19, 50.20, 80.18	Clearlake	Main	3rd	39.04369	-122.91530
50.09	FINLEY POST OFFICE		Finley	Finley Rd	Stone Dr	38.97778	-122.8366
50.1	KONOCTI VISTA CASINO	51.13	Big Valley Rancheria	N/A - parking lot	N/A	39.02074	-122.88864
50.11	KMART		Lakeport	S. Main	N/A	39.027	-122.918
50.12	NURSERY & GROCERY OUTLET	40.15	Lakeport	S. Main	Lakeport	39.03412	-122.9156
50.13	BOWLING ALLEY	41.04, 40.16, 51.04	Lakeport	Lakeport Blvd	Larrecou Ln	39.03473	-122.9214
50.14	SOCIAL SECURITY	41.05, 51.05	Lakeport	Parallel	Westside Park Rd	39.03473	-122.9214
50.15	TACO BELL BEFORE DRIVEWAY	41.06, 51.06	Lakeport	Parallel	Todd Rd	39.03203	-122.9361
50.16	MENDO COLLEGE	40.12, 51.07, 80.27, 81.01	Lakeport	Mendocino College	S.R. 29	39.0323	-122.925
50.17	SAFEWAY	40.17, 50.18, 71.09, 81.07	Lakeport	Olympic	Burns Valley	39.04885	-122.9258
50.18	9TH & MAIN	40.18, 80.17	Lakeport	Main	9th	39.04733	-122.915
50.19	3RD & MAIN	50.08, 40.19, 80.18	Lakeport	Main	3rd	39.04369	-122.91530

Table 3.51: Locations of Bus Stop for Route 4A Eastbound

Bus Stop							
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
51.01	3RD & MAIN	41.01, 70.01, 71.11, 81.05	Lakeport	Main	3rd	39.04369	-122.91530
51.02	MAIN & D ST		Lakeport	Main	D St	39.03825	-122.91536
51.03	D STREET		Lakeport	D St	N/A	39.03825	-122.91536
51.04	BOWLING ALLEY	41.04, 40.16, 50.13	Lakeport	Lakeport Blvd	Larrecou Ln	39.03473	-122.92149
51.05	SOCIAL SECURITY	41.05, 50.14	Lakeport	Parallel	Westside Park Rd	39.03475	-122.92573
51.06	TACO BELL BEFORE DRIVEWAY	41.06, 50.15	Lakeport	Parallel	Todd Rd	39.0323	-122.925
51.07	MENDO COLLEGE	50.16, 40.12, 80.27, 81.01	Lakeport	Mendocino College	S.R. 29	39.18992	-123.22768
51.08	BRUNOS	41.07, 80.23	Lakeport	Lakeport	N/A	39.0323	-122.925
51.09	GROCERY OUTLET	41.08, 80.24	Lakeport	S Main St	Christopher Ln	39.03413	-122.91588
51.1	HOSPICE	41.09, 110.18, 120.23	Lakeport	Lakeshore	N/A	38.95441	-122.64526
51.11	KMART	80.25	Lakeport	S. Main	N/A	39.027	-122.918
51.12	ROTTEN ROBBIES	80.26	Lakeport	S Main	N/A	39.01862	-122.91279
51.13	KONOCTI VISTA CASINO	50.10	Big Valley Rancheria	N/A - parking lot	N/A	39.02074	-122.88864
51.14	FINLEY POST OFFICE		Finley	Finley Rd	Stone Dr	39.02074	-122.88864
51.15	SODA BAY STORE		Soda Bay	Soda Bay Rd	Pine Ave	39.00111	-122.79194
51.16	RIVERA WEST		Soda Bay	Soda Bay Road	Riviera West	38.99164	-122.74797
51.17	MONTEZUMA WAY		Soda Bay	Soda Bay Road	Montezuma Way	38.98051	-122.74254
51.18	RIVERA SHOPPING CENTER		Soda Bay	Soda Bay Road	North of Riviera	38.9524	-122.72949
51.19	KITS CORNER	21.24, 40.05, 20.01, 50.01, 41.18	Soda Bay	S.R. 29	S.R. 281	38.94982	-122.61529

Table 3.70: Locations of Bus Stop for Route 7 Westbound

Bus Stop							
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
70.01	3RD & MAIN	51.01, 41.01, 71.11, 81.05	Clearlake	Main	3rd	39.04369	-122.915302
70.02	9TH & MAIN (NATURAL HIGH)	71.10, 81.06	Clearlake	Main	9th	39.04684	-122.915013
70.03	SENTRY MARKET	11.07, 10.29, 71.08	Nice	S.R. 20	Lake	39.12901	-122.87112
70.04	ROBINSONS CASINO	71.07, 10.30, 11.06	Nice	S.R. 20	N/A	39.14162	-122.881645
70.05	1ST & MAIN UPPER LAKE	71.06	Nice	1st	Main	39.16527	-122.902794
70.06	BLUE LAKES		Ukiah	S.R. 20	Irving Ave	39.16962	-123.006632
70.07	MENDOCINO COLLEGE UKIAH	71.04	Ukiah	Mendocino College	S.R. 29	39.18992	-123.227684
70.08	PEAR TREE	71.03	Ukiah	N Orchard ave	-	39.1524	-123.200444
70.09	VETERANS CLINIC	71.02	Ukiah	Kings Ct	Hwy 101	39.14838	-123.197142
70.1	AIRPORT	71.01	Ukiah	S State St	-	39.12767	-123.201362

Table 3.71: Locations of Bus Stop for Route 7 Eastbound

Bus Stop							
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
71.01	AIRPORT	70.10	Ukiah	S State St	-		
71.02	VETERANS CLINIC	70.09	Ukiah	Kings Ct	Hwy 20		
71.03	PEAR TREE	70.08	Ukiah	N Orchard Ave	-		
71.04	MENDOCINO COLLEGE UKIAH	70.07	Ukiah	Mendocino College	S.R. 29	39.18992	-123.227684
71.05	BLUE LAKES		Ukiah	S.R. 20	Irving ave		
71.06	1ST & MAIN UPPER LAKE	70.05	Nice	1st	Main	39.16527	-122.902794
71.07	ROBINSONS CASINO	70.04, 10.30, 11.06	Nice	S.R. 20	N/A	39.14162	-122.881645
71.08	SENTRY MARKET	11.07, 10.29, 70.03	Nice	S.R. 20	Lake	39.12901	-122.87112
71.09	SAFEWAY	40.17, 50.17, 81.07	Clearlake	Olympic	Burns Valley	39.04885	-122.9258
71.10	9TH & MAIN (NATURAL HIGH)	70.02, 81.06	Clearlake	Main	9th	39.04684	-122.915013
71.11	3RD & MAIN	51.01, 70.01, 41.01, 81.05	Clearlake	Main	3rd	39.04369	-122.915302

Table 3.80: Locations of Bus Stop for Route 8 Northbound

Bus Stop							
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
80.01	LAKE COUNTY JAIL	11.02, 10.35, 81.21	Lakeport	Hill Rd	N/A	39.10437	-122.91355
80.02	SUTTER LAKESIDE	11.01, 10.36, 81.20	North Lakeport	Parking Lot	N/A	39.10452	-122.90721
80.03	LAKESIDE HEALTH CLINIC	81.19	North Lakeport	Parking Lot	N/A	39.10527	-122.90419
80.04	NORTHPORT MOBILE HOME PARK	81.18	North Lakeport	Lakeshore	Crystal Lake Way	39.10269	-122.90152
80.05	EL DORADO MOTEL		North Lakeport	Lakeshore	Rocky Point	39.08732	-122.90263
80.06	PEOPLE SERVICES-WALNUT DR		North Lakeport	Lakeshore	N. Walnut	39.09125	-122.90305
80.07	ELKS LODGE		North Lakeport	Lakeshore	N/A	39.086	-122.90347
80.08	RAINBOW MOBILE HOME PARK		North Lakeport	Lakeshore	Shady Ln	39.07977	-122.90689
80.09	PARK WAY		North Lakeport	Lakeshore	Park	39.07634	-122.91027
80.1	TOWER MART		North Lakeport	Lakeshore	Alterra Dr	39.02164	-122.6753
80.11	CRYSTAL LAKE DR		North Lakeport	Lakeshore	Crystal Lake Way	39.0687	-122.91300
80.12	BEACH LN-RAINBOW LODGE		North Lakeport	Beach Ln	Rainbow Rd	39.06216	-122.9133
80.13	LAKESHORE & LANGE		North Lakeport	Lakeshore	Lange St	39.05917	-122.91314
80.14	HIGH ST		Lakeport	High St	Via del lago	39.05453	-122.91704
80.15	LIBRARY		Lakeport	High St	15th	39.05221	-122.91706
80.16	N.FORBES ST		Lakeport	N forbes	Clearklake ave	39.04986	-122.91624
80.17	9TH & MAIN	50.18, 40.18	Lakeport	Main	9th	39.04733	-122.9152
80.18	3RD & MAIN	50.08, 50.19,40.19	Lakeport	Main	3rd	39.04369	-122.91530
80.19	MAIN & MARTIN	41.02	Lakeport	Main	Martin	39.04057	-122.91533
80.20	STARR & MARTIN (BELLA VISTA)		Lakeport	Martin	Starr	39.04041	-122.92269
80.21	TRIBAL HEALTH		Lakeport	Bevins ct	Bevins St	39.03684	-122.9227
80.22	BEVINS ACROSS FROM WIC		Lakeport	Bevins St	N/A	39.0325	-122.924
80.23	BRUNOS	41.07, 51.08	Lakeport	Lakeport	N/A	39.0323	-122.925
80.24	GROCERY OUTLET	41.08, 51.09	Lakeport	S Main St	Christopher Ln	39.03413	-122.91588
80.25	KMART	51.11	Lakeport	S. Main	N/A	39.027	-122.918
80.26	ROTTEN ROBBIES	51.12	Lakeport	S Main	N/A	39.01862	-122.91279
80.27	MENDO COLLEGE	50.16, 51.07, 40.12, 81.01	Lakeport	Mendocino College	S.R. 29	39.18992	-123.22768

Table 3.81: Locations of Bus Stop for Route 8 Southbound

Bus Stop							
ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
81.01	MENDO COLLEGE	40.12, 50.16, 51.07, 80.27	Lakeport	Mendocino College	S.R. 29	39.18992	-123.22768
81.02	AAA		Lakeport	Parallel Dr	N/A	39.005	-122.7
81.03	SENIOR CENTER	110.24, 120.30	Lakeport	Konocti ave	Larrecou Ln	38.966	-122.63113
81.04	MARTIN ST (BELLA VISTA)		Lakeport	Lakeport	Martin	39.04055	-122.92269
81.05	3RD & MAIN	51.01, 41.01, 71.11, 70.01	Lakeport	Main	3rd	39.04369	-122.91530
81.06	9TH & MAIN (NATURAL HIGH)	71.10, 70.02	Lakeport	Main	9th	39.04684	-122.91501
81.07	SAFEWAY	40.17, 50.17, 71.09	Lakeport	Olympic	Burns Valley	39.04885	-122.9258
81.08	VIA DEL LAGO		Lakeport	High St	Via del lago	39.05431	-122.91690
81.09	LAKESHORE & LANGE		North Lakeport	Lakeshore	Lange St	39.05917	-122.9131
81.1	BEACH LN-RAINBOW LODGE		North Lakeport	Beach Ln	Rainbow Rd	39.06216	-122.9133
81.11	THE CHEATEU		North Lakeport	Lakeshore	Crystal Lake Way	39.00048	-122.9135
81.12	TOWER MART		North Lakeport	Lakeshore	Alterra Dr	39.02164	-122.6753
81.13	PARK WAY		North Lakeport	Lakeshore	Alterra Dr	39.07634	-122.91027
81.14	ACROSS FROM RAINBOW MOBILE HOME		North Lakeport	Lakeshore	Shady Ln	39.07968	-122.90671
81.15	ROCKY POINT		North Lakeport	Lakeshore	Rockypoint	39.08679	-122.90243
81.16	ACROSS FROM PEOPLE SERVICES		North Lakeport	Lakeshore	N. Walnut	39.0919	-122.9027
81.17	ACROSS FROM PERKS MOBILE HOME		North Lakeport	Lakeshore	Crystal Lake Way	39.929	-122.61967
81.18	NORTHPORT MOBILE HOME PARK	80.04	North Lakeport	Lakeshore	Crystal Lake Way	39.10269	-122.90152
81.19	LAKESIDE HEALTH CLINIC	80.03	North Lakeport	Parking Lot	N/A	39.10527	-122.90419
81.2	SUTTER LAKESIDE	11.01, 10.36, 80.02	North Lakeport	Parking Lot	N/A	39.10452	-122.90721
81.21	LAKE COUNTY JAIL	11.02, 10.35, 80.01	Lakeport	Hill Rd	N/A	39.10437	-122.9135

Table 3.100: Locations of Bus Stop for Route 10 North Loop

Bus Stop ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
וט	Bus Stop Name	11.38, 30.01, 31.13, 40.01, 41.21, 10.01, 100.45,	Alea	Street		LAI	LONG
100.01	WALMART FOOD PLACE	110.01, 110.42, 120.01, 120.12, 120.42	Clearlake	Dam Road Ext.	N/A	38.9299	-122.61576
100.02	CLEARLAKE APTS	120.13	Clearlake	Old Hwy 53	N/A	38.93178	-122.62320
100.03	J&L MARKET	120.14	Clearlake	Old Hwy 53	Lakeview	38.9362	-122.62674
100.04	CROSSROADS CHURCH	120.15	Clearlake	Old Hwy 53	Crawford	38.93922	-122.6292
100.05	CYPRESS	120.16	Clearlake	Old Hwy 53	Cypress	38.94233	-122.6313
100.06	MENDO MILL	220.20	Clearlake	Old Hwy 53	Wayland	38.94518	-122.6311
100.07	OLD HWY 53 & LAKESHORE		Clearlake	Old Hwy 53	lakeshore	38.94852	-122.6314
100.08	OLD RED CROSS		Clearlake	Old Hwy 53	Hillcrest	38.95154	-122.6313
100.09	HILL AVE		Clearlake	Old Hwy 53	Hill ave	38.95359	-122.6313
100.10	RIDGE LAKE APTS-COMMONS		Clearlake	Old Hwy 53	Austin Dr	38.95565	-122.6314
100.11	BURNS VALLEY MALL		Clearlake	olympic	N/A	38.96184	-122.633
100.12	CLEARLAKE POST OFFICE		Clearlake	olympic	Buckeye St	38.96179	-122.6398
100.12	BABY STORE (ACROSS FROM LOCUST)		Clearlake	Olympic	Locust	38.96174	-122.646
100.13	CITY HALL		Clearlake	Olympic	Lakeshore	38.96108	-122.6481
100.14	OLD BOWLING ALLEY		Clearlake	Lakeshore	Villa	38.96222	-122.6493
100.15	POMO & WOODLAND		Clearlake	Pomo	Woodland	38.96541	-122.6499
100.17	BOXWOOD & ARROWHEAD		Clearlake	Arrowhead	Boxwood	38.96914	-122.6505
100.18	TOYON		Clearlake	Arrowhead	Toyon	38.96914	-122.6537
100.19	MODOC		Clearlake	Arrowhead	Modoc	38.971	-122.6569
100.2	2ND ST (HALFWAY DOWN BLOCK)		Clearlake	2nd	Bush/sonoma	38.97339	-122.6553
100.21	2ND & BUSH		Clearlake	2nd	Bush	38.9761	-122.6553
100.22	8TH & BUSH		Clearlake	8th	Bush	38.97627	-122.6601
100.23	11TH & BUSH		Clearlake	11th	Bush	38.97628	-122.6625
100.24	13TH & COUNTRY CLUB		Clearlake	13th	Country club	39.08929	-122.7905
100.25	COUNTRY CLUB & ARROWHEAD		Clearlake	Country club	Arrowhead	38.97157	-122.6614
100.26	CLEARLAKE PARK POST OFFICE		Clearlake	Clearlake	olympic	38.96696	-122.639
100.27	AMERICAS BEST VALUE INN		Clearlake	Lakeshore	N/A	38.96632	-122.6527
100.28	LAKESHORE & POMO		Clearlake	Lakeshore	Pomo	38.96568	-122.6503
100.29	CITY HALL		Clearlake	Olympic	Lakeshore	38.96108	-122.6481
100.3	AUSTIN PARK		Clearlake	Lakeshore	Austin Rd	38.95976	-122.6492
100.31	BAYLIS & LAKEHORE		Clearlake	Baylis	Lakeshore	38.95619	-122.647
100.32	HIGHLANDS PARK (CASTLE DONUTS)		Clearlake	Lakeshore	N/A	38.95375	-122.6437
100.33	CATFISH COFFEE		Clearlake	Lakeshore	N/A	38.95047	-122.6391
100.34	VETERANS CLINIC	110.30	Clearlake	Lakeshore	N/A	39.14821	-123.1973
	VALERO	110.31	Clearlake	Lakeshore	W 40th	38.95058	-122.624
100.36	SOCIAL SERVICES		Clearlake	Anderson Ranch	N/A	38.91919	-122.6171
100.37	JOB ZONE	40.02, 30.02, 120.04	Clearlake	S.R. 53	Parking Lot	38.91701	-122.612
100.38	ACROSS FROM LAKE TRANSIT	40.03, 30.03, 120.05	Clearlake Oaks	S.R. 53	N/A	38.9149	-122.6124
100.39	HWY 53 & MAIN (DL'S PIZZA)	120.06	Clearlake	Main	S.R. 53	38.91021	-122.6115
.00.40	BETWEEN LAKE & 2ND ST		Clearlake	Lakeshore	2nd	38.91089	-122.6091
L00.41	LOWER LAKE HIGH SCHOOL	120.08	Clearlake	Lake St	N/A Parking Lot	38.91548	-122.6087
100.42	CEMETERY	120.09	Clearlake	Lake	Cemetery cir Rd	38.91768	-122.6089
100.43	BRYANT RD	120.10	Clearlake	Lake	Bryant	38.92074	-122.611
100.44	CACHE CREEK APTS	120.11	Clearlake	Dam Rd	Lake	38.92617	-122.6120
		11.38, 30.01, 31.13, 40.01, 41.21, 100.01, 10.01,					
100.45	WALMART FOOD PLACE	110.01, 110.42, 120.01, 120.12, 120.42	Clearlake	Dam Road Ext.	N/A	38.9299	-122.6157

Table 3.110: Locations of Bus Stop for Route 11 Avenues

Bus Stop ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
110.01	WALMART FOOD PLACE	11.38, 30.01, 31.13, 40.01, 41.21, 100.01, 100.45,	Clearlake	Dam Road Ext.	N/A	38.9299	-122.61576
		10.01, 110.42, 120.01, 120.12, 120.42			•		
110.02	ST.HELENA CLEARLAKE		Clearlake	18th	S.R. 53	38.54288	-122.47556
110.03	IRVING & 18TH		Clearlake	18th	Irving	38.93605	-122.612
110.04	BOYLES & 18TH		Clearlake	Boyles	18th	38.93623	-122.6105
110.05	BOYLES & 25TH		Clearlake	Boyles	25th	38.94096	-122.6105
110.06	BOYLES BETWEEN 30TH & 31ST		Clearlake	Boyles	30th/31st	38.94428	-122.6104
110.07	33RD & PHILLIPS		Clearlake	Phillips	33rd	38.94592	-122.6152
110.08	36TH & PHILLIPS		Clearlake	Phillips	36th	38.94814	-122.6151
110.09	PHILLIPS & 40TH (40TH STORE)		Clearlake	Phillips	40th	38.95091	-122.6150
110.1	45TH -THE DUMP DAVIS ST		Clearlake	45th	davis St	38.95377	-122.6149
110.11	MOSS (FIRST DRIVE WAY)		Clearlake	Moss	davis St	38.95403	-122.6217
110.12	WEST AMERICA BANK		Clearlake	Lakeshore	Manzanita	38.94978	-122.6286
110.13	CLEARLAKE FAMILY CLINIC		Clearlake	Lakeshore	N/A	38.94996	-122.6285
110.14	NAPA AUTO PARTS	120.19	Clearlake	Lakeshore	Palmer	38.94998	-122.6330
110.15	NOTT'S LIQUOR		Clearlake	Lakeshore	Golf Rd	38.94989	-122.6358
110.16	CATFISH COFFEE	120.21	Clearlake	Lakeshore	N/A	38.95047	-122.6391
110.17	BURGER TIME	120.22	Clearlake	Lakeshore	Mullen	38.9516	-122.6417
110.18	HOSPICE	51.10, 41.09, 120.23	Clearlake	Lakeshore	N/A	38.95441	-122.6452
110.19	OLD FIREHOUSE	120.24	Clearlake	Lakeshore	Baylis	38.95634	-122.6477
110.2	AUSTIN PARK	120.25	Clearlake	Lakeshore	Austin Dr	38.95976	-122.6492
110.21	HAVERTY FIELD	120.26	Clearlake	Olympic	Pine	38.96093	-122.6459
110.22	CLEARLAKE POST OFFICE	120.27	Clearlake	Olympic	Buckeye	38.96179	-122.639
110.23	BURNS VALLEY MALL		Clearlake	Olympic	N/A	38.96184	-122.633
110.24	SENIOR CENTER	81.03, 120.30	Lakeport	Konocti ave	Larrecou Ln	38.966	-122.631
110.25	SHELTER AT WALNUT GROVE APTS	120.31	Clearlake	Rumsey Rd	Bartram Cir	38.96647	-122.6317
110.26	SAFEWAY	120.32	Clearlake	Olympic	Burns Valley	38.9628	-122.6313
110.27	OLD HWY 53 PAST RITE AID	120.33	Clearlake	Old Hwy 53	N/A	38.96062	-122.631
110.28	HIGHLANDS WAY	120.34	Clearlake	Highland way	Old Hwy 53	38.95582	-122.6314
110.29	HILLCREST	120.35	Clearlake	Old Hwy 53	Hillcrest	38.95275	-122.6311
110.3	VETERANS CLINIC	100.34	Clearlake	Lakeshore	N/A	39.14821	-123.1973
110.31	VALERO	100.35	Clearlake	Lakeshore	, W 40th	38.95058	-122.624
110.32	MOSS & DAVIS (BEFORE 35MPS SIGN)		Clearlake	Moss	davis St	38.95403	-122.6217
110.33	PHILLIPS & 44TH		Clearlake	Phillips	44th	38.9536	-122.6151
110.34	PHILLIPS & 40TH		Clearlake	Phillips	40th	38.94982	-122.6152
110.35	32ND & PHILLIPS		Clearlake	Phillips	32nd	38.94821	-122.6150
	BOYLES & 29TH		Clearlake	Phillips	29th	38.94528	-122.6151
110.37	BETWEEN 26TH & 25TH		Clearlake	Boyles	26th/25th	38.94348	-122.6106
110.38	BOYLES AND 21ST		Clearlake	Boyles	21st	38.94168	-122.6106
110.39	IRVING & 18TH		Clearlake	18th	Irving	38.93605	-122.612
110.33	ST.HELENA CLEARLAKE		Clearlake	18th	S.R. 53	38.54288	-122.4755
110.4	WOODLAND COLLEGE	11.37, 120.02	Clearlake	N/A	N/A	38.93279	-122.4733
110.71	THE COLLEGE	·	Cicuriane	14/ 🔿	N/A	30.33273	122.01/(
110.42	WALMART FOOD PLACE	10.01, 11.38, 30.01, 31.13, 40.01, 41.21, 100.01, 100.45, 110.01, 120.01, 120.12, 120.42	Clearlake	Dam Road Ext.	N/A	38.9299	-122.6157

Table 3.120: Locations of Bus Stop for Route 12 South Loop

Bus Stop ID	Bus Stop Name	Repeats	Area	Street	Cross Street	LAT	LONG
10	Bus Stop Name	10.01, 11.38, 30.01, 31.13, 40.01, 41.21, 100.01,	Aica	Street	CIO33 Street	LAI	LONG
120.01	WALMART FOOD PLACE	100.45, 110.01, 110.42, 120.12, 120.42	Clearlake	Dam Road Ext.	N/A	38.9299	-122.6157
120.02	WOODLAND COLLEGE	11.37, 110.41	Clearlake	N/A	N/A	38.93279	-122.6170
120.03	SOCIAL SERVICES		Clearlake	Anderson Ranch	N/A	38.91919	-122.6171
120.04	JOB ZONE	40.02, 100.37, 30.02	Clearlake	S. R 53	Parking Lot	38.91701	-122.612
120.05	ACROSS FROM LAKE TRANSIT	40.03, 100.38, 30.03	Clearlake Oaks	S.R. 53	N/A	38.9149	-122.6124
120.06	HWY 53 & MAIN (DL'S PIZZA)	100.39	Clearlake	Main	s.R. 53	38.91021	-122.611
120.07	BETWEEN LAKE ST & SECOND ST		Clearlake	Lakeshore	2nd	38.91089	-122.609
120.08	LOWER LAKE HIGH SCHOOL	100.41	Clearlake	Lake St	N/A Parking Lot	38.91548	-122.608
120.09	CEMETERY	100.42	Clearlake	Lake	Cemetery cir Rd	38.91768	-122.608
120.10	BRYANT RD	100.43	Clearlake	Lake	Bryant	38.92074	-122.611
120.11	CACHE CREEK APTS	100.44	Clearlake	Dam Rd	Lake	38.92617	-122.612
		11.38, 30.01, 31.13, 40.01, 41.21, 100.01, 100.45,					
120.12	WALMART FOOD PLACE	110.01, 110.42, 120.01, 10.01, 120.42	Clearlake	Dam Road Ext.	N/A	38.9299	-122.6157
120.13	CLEARLAKE APTS	100.02	Clearlake	Old Hwy 53	N/A	38.93178	-122.623
120.14	J&L MARKET	100.03	Clearlake	Old Hwy 53	Lakeview	38.9362	-122.626
120.15	CROSSROADS CHURCH	100.04	Clearlake	Old Hwy 53	Crawford	38.93922	-122.629
120.16	CYPRESS	100.05	Clearlake	Old Hwy 53	Cypress	38.94233	-122.631
120.17	MENDO MILL (ACROSS THE STREET)		Clearlake	Old Hwy 53	Wayland	38.94518	-122.631
120.18	OLD HWY 53 & LAKESHORE		Clearlake	Old Hwy 53	lakeshore	38.94852	-122.631
120.19	NAPA AUTO PARTS	110.14	Clearlake	Lakeshore	Palmer	38.94998	-122.633
120.2	NOTT'S LIQOUR		Clearlake	Lakeshore	Golf Rd	38.94989	-122.635
120.21	CATFISH COFFEE	110.16	Clearlake	Lakeshore	N/A	38.95047	-122.639
120.22	BURGER TIME	110.17	Clearlake	Lakeshore	Mullen	38.9516	-122.641
120.23	HOSPICE	110.18	Clearlake	Lakeshore	N/A	38.95441	-122.645
120.24	OLD FIREHOUSE	110.19	Clearlake	Lakeshore	Baylis	38.95634	-122.647
120.25	AUSTIN PARK	110.20	Clearlake	Lakeshore	Austin Dr	38.95976	-122.649
120.26	HAVERTY FIELD	110.21	Clearlake	Olympic	Pine	38.96093	-122.645
120.27	CLEARLAKE POST OFFICE	110.22	Clearlake	Olympic	Buckeye	38.96179	-122.639
120.28	BURNS VALLEY MALL		Clearlake	Olympic	N/A	38.96184	-122.633
120.29	B&G TIRES		Clearlake	Burns Valley	Turner Ave	38.96254	-122.63
120.3	SENIOR CENTER	81.03, 110.24	Lakeport	Konocti ave	Larrecou Ln	38.966	-122.631
120.31	SHELTER AT WALNUT GROVE APTS	110.25	Clearlake	Rumsey Rd	Bartram Cir	38.96647	-122.631
120.32	SAFEWAY	110.26	Clearlake	Olympic	Burns Valley	38.9628	-122.631
120.33	OLD HWY 53 PAST RITE AID	110.27	Clearlake	Old Hwy 53	N/A	38.96062	-122.631
120.34	HIGHLANDS WAY	110.28	Clearlake	Highland way	Old Hwy 53	38.95582	-122.631
120.35	HILLCREST	110.29	Clearlake	Old Hwy 53	Hillcrest	38.95275	-122.631
120.36	BALLPARK-OLD HWY 53-LAKESHORE-TRAVELODGE		Clearlake	Old Hwy 53	Ball Park Ave	38.94852	-122.631
120.37	MENDO MILL		Clearlake	Old Hwy 53	Wayland	38.94518	-122.631
120.38	KING FISHER		Clearlake	Old Hwy 53	Cypress	38.94107	-122.631
120.39	CEDAR VILLAGE APTS		Clearlake	Old Hwy 53	Crawford	38.93914	-122.630
120.40	HIGHLANDS APTS		Clearlake	Old Hwy 53	Lakeview	38.93576	-122.628
120.41	CLEARLAKE APTS		Clearlake	Old Hwy 53	N/A	38.93178	-122.623
120.42	WALMART FOOD PLACE	10.01, 11.38, 30.01, 31.13, 40.01, 41.21, 100.01, 100.45, 110.01, 110.42, 120.01, 120.12	Clearlake	Dam Road Ext.	N/A	38.9299	-122.615

Table C-4

Table 4.10- Roadway Characteristics for Bus Stops: Route 1 Westbound

			# of Travel	Speed	Can Bus pull out		Pull Out			Trip Generator Across	
us Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Limit	of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Dista
		11.38, 30.01, 31.13,			•		-			•	
10.01	WALMART FOOD PLACE	40.01,41.21, 100.01, 100.45	,		Parking Lot				Parking	z l ot	
10.01	WALIMANTTOOD FLACE	110.01, 110.42, 120.01, 120.1	2,		Tarking Lot				Tarking	5 LOT	
		120.42									
10.02	KEYS BLVD		3	55	Yes	Asphalt	No	No	Yes	Yes	Good
10.03	HWY 20 & POST OFFICE		3	55	Yes	Asphalt	No	Yes	No	Yes	Good
10.04	EAST LAKE SCHOOL		3	35	Yes	Asphalt	No	No	No	No	Good
10.05	LAKE ST				Under Construction				Under Cons	struction	
10.06	RED & WHITE MARKET		3	35	Yes	Asphalt	No	Yes	No	Yes	Good
10.07	MATTRESS STORE		3	35	Yes	Asphalt	No	Yes	No	No	Good
10.08	LAKEVIEW DR		2	45	No	Asphalt	Yes	No	No	No	Acceptab
10.09	BLUE FISH COVE		2	45	Yes	Asphalt	No	No	No	No	Good
10.10	INDIAN BEACH RESORT		2	35	Yes	Asphalt	No	No	No	No	Good
10.11	GLENHAVEN DR		2	35	Yes	Asphalt	No	No	No	No	Acceptab
10.12	BRUNER DR		2	35	No	Asphalt	Yes	No	No	No	Poor
10.13	DRIFTWOOD LOUNGE	11.24	Lot	25	No	Asphalt	Yes	No	No	No	Good
10.14	LAUREL DELL AT RIVERA MOTEL	11.23	Lot	25	No	Asphalt	Yes	No	No	No	Good
10.15	BELL RAY		Lot	25	No	Asphalt	Yes	No	No	No	Good
10.16	LAKESHORE & HWY 20		2	35	Yes	Asphalt	No	No	No	No	Acceptab
10.17	LUCERNE ELEMENTARY SCHOOL		3	35	Yes	Asphalt	No	No	Yes	No	Acceptab
10.18	HWY 20 & 14TH		3	35	Yes	Asphalt	No	No	Yes	No	Good
10.19	TOWER MART		3	30	Yes	Asphalt	No	Yes	Yes	No	Good
10.20	AT MARYMOUNT COLLEGE AT 13TH		2	30	No	Asphalt	Yes	No	Yes	No	Acceptab
10.21	HWY 20 & 9TH		3	35	Yes	Asphalt	No	Yes	Yes	No	Good
10.22	HWY 20 & 5TH		3	35	Yes	Asphalt	No	Yes	Yes	No	Good
10.23	HWY 20 & 1ST ST		3	35	Yes	Asphalt	No	Yes	Yes	No	Good
10.24	THE HARBOR		2	35	Yes	Asphalt	No	No	No	No	Good
10.25	NICE POST OFFICE		3	35	Yes	Asphalt	No	No	Yes	No	Good
10.26	NICE MARKET		3	35	Yes	Asphalt	No	Yes	No	No	Good
10.27	HINMAN PARK		3	35	Yes	Asphalt	No	Yes	Yes	No	Good
10.28	LAKEVIEW AVE		3	45	Yes	Dirt	No	No	No	No	Acceptab
10.29	SENTRY MARKET	11.07, 70.03, 71.08		-	Parking Lot	-	-	-	Parking		
10.30	ROBINSONS CASINO	71.07, 70.04, 11.06			Parking Lot				Parking		
10.31	RUNNING CREEK CASINO	11.05	Lot	10	Yes	Asphalt	No	No	Yes	Yes	Good
10.32	UPPER LAKE HIGH SCHOOL		2	25	Yes	Asphalt	No	Yes	Yes	No	Good
10.33	MAIN ST & HWY 20		2	25	Yes	Asphalt	No	Yes	Yes	Yes	Good
10.34	TURNOUT ACROSS FROM CHEVRON		2	55	Yes	Dirt	No	No	No	Yes	Acceptak
10.35	LAKE COUNTY JAIL	11.02, 80.01, 81.21		30	Parking Lot	•			Parking		
10.36	SUTTER LAKESIDE	11.01, 80.02, 81.20			Parking Lot				Parking		

Table 4.11- Roadway Characteristics for Bus Stops: Route 1 Eastbound

			# of Travel	Speed	Can Bus pull out		Pull Out			Trip Generator Across	
us Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Limit	of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Dista
11.01	SUTTER LAKESIDE	10.36, 80.02, 81.20			Parking Lot				Parking	g Lot	
11.02	LAKE COUNTY JAIL	10.35, 80.01, 81.21			Parking Lot				Parking	g Lot	
11.03	MAIN ST & HWY 20		2	25	Yes	Asphalt	No	Yes	Yes	Yes	Good
11.04	UPPER LAKE HIGH SCHOOL		2	25	Yes	Asphalt	No	Yes	Yes	No	Good
11.05	RUNNING CREEK CASINO	10.31			Parking Lot		No	No	Yes	Yes	Good
11.06	ROBINSONS CASINO	71.07, 70.04, 10.30			Parking Lot				Parking	g Lot	
11.07	SENTRY MARKET	10.29, 70.03, 71.08			Parking Lot				Parking	g Lot	
11.08	COLLIER		3	45	No	Asphalt	Yes	No	No	No	
11.09	BAT HOUSE ACROSS FROM HINMAN PARK		3	35	No	Dirt	Yes	Yes	No	Yes	Good
11.10	MARINA GRILL		3	45	Yes	Asphalt	No	No	No	Yes	Good
11.11	WORLD MARK-NICE POST OFFICE		3	45	Yes	Asphalt	No	No	No	No	Good
11.12	THE HARBOR		2	45	No	Dirt	Yes	No	No	No	Good
11.13	1ST ST & HWY 20		3	35	Yes	Asphalt	No	Yes	Yes	No	Good
11.14	2ND & HWY 20 BTWN XWALK & ALPINE PARK		3	35	No	Asphalt	Yes	Yes	Yes	No	Accepta
11.15	5TH AND HWY 20 NEAR FIRE HYDRANT IN		3	35	Yes	Asphalt	No	Yes	Yes	No	Good
11.16	FRONT OF THE WATER SERVICE COMPANY		3	35	Yes	Asphalt	No	Yes	No	Yes	Good
11.17	9TH & HWY 20 LUCERNE HARBOR PARK		3	35	Yes	Asphalt	No	Yes	Yes	No	Good
11.18	13TH & COUNTRY CLUB MARYMONT COLLEGE		2	25	No	Dirt	Yes	No	No	No	Good
11.19	13TH & HWY 20 COMMUNITY GARDEN PARK		3	35	Yes	Gravel	No	No	No	Yes	Good
11.20	16TH & HWY 20 OLD MONUMENT SIGN		3	35	Yes	Asphalt	No	No	No	Yes	Good
11.21	LAKESHORE & HWY 20		2	35	Yes	Asphalt	No	No	Yes	No	Accepta
11.22	JUST BEFORE BELL RAY		2	35	Yes	Asphalt	No	No	No	No	Good
11.23	LAUREL DELL AT RIVERA MOTEL	10.14			Parking Lot		Yes	No	No	No	Good
11.24	DRIFTWOOD LOUNGE	10.13	Lot	25	No	Asphalt	Yes	No	No	No	Good
11.25	BRUNER DR-GRAVEL PULL OUT-KONA TAYHEE		2	45	Yes	Asphalt	No	No	No	No	Poor
11.26	GLENHAVEN		2	45	Yes	Asphalt	No	No	No	No	Accepta
11.27	INDIAN BEACH RESORT		2	35	Yes	Asphalt	No	No	No	No	Good
11.28	BLUE FISH COVE		2	45	Yes	Asphalt	No	No	No	No	Good
11.29	LAKEVIEW		2	45	No	Asphalt	Yes	No	No	No	Accepta
11.30	TOWER MART		3	35	Yes	Asphalt	No	No	Yes	No	Good
11.31	THE BARN		3	35	Yes	Asphalt	No	Yes	No	Yes	Good
11.32	LAKE ST				Under Construction				Under Cons	struction	
11.33	EAST LAKE SCHOOL		3	35	Yes	Asphalt	No	No	No	No	Good
11.34	HWY 20 BURGERS		3	35	Yes	Asphalt	No	Yes	No	No	Good
11.35	KEYS BLVD		3	55	Yes	Asphalt	No	No	No	Yes	Good
11.36	ORCHARD SHORES				Parking Lot		No	No	Yes	No	Good
11.37	WOODLAND COLLEGE	110.41, 120.02			Parking Lot				Parking	g Lot	
11.38	WALMART FOOD PLACE	10.01, 30.01, 31.13, 40.01, 41.21, 100.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.42			Parking Lot				Parking	g Lot	

Table 4.20- Roadway Characteristics for Bus Stops: Route 2 Southbound

	,	•								Т	
			# of Travel	Speed	Can Bus pull out		Pull Out			Trip Generator Across	
Bus Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Limit	of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Distance
	·	21.24, 40.05, 41.18, 50.01,	1		•					<u>'</u>	
20.01	KITS CORNER	51.19			Parking Lot		No	No	No	No	Good
20.02	DIAMOND DUST		2	55	Yes	Dirt	No	No	No	Yes	Good
20.03	WILD CAT CANYON		2	55	Yes	Dirt	No	No	No	Yes	Poor
20.04	SALMINA		2	55	Yes	Asphalt	No	No	No	Yes	Acceptable
20.05	ADMIRAL RD		2	55	Yes	Dirt	No	No	No	Yes	Good
20.06	MARIAH MEADOWS		2	55	Yes	Asphalt	No	No	No	No	Good
20.07	LOCH LOMOND		2	55	No	Asphalt	Yes	No	No	No	Acceptable
20.08	HARRINGTON FLATS		2	55	Yes	Gravel	No	No	No	No	Good
20.09	HOBERGS RESORT		2	55	Yes	Asphalt	No	No	No	No	Poor
20.10	SUMMIT		2	55	Yes	Asphalt	No	No	No	No	Good
20.11	HARDESTERS	21.12			Parking Lot		No	Parking Lot	No	No	Good
20.12	TURNOUT ACROSS FROM GIFFORD SPRINGS		2	55	No	Dirt	Yes	No	No	No	Good
20.13	THE OLD TAVERN-MAPLE SHADOWS		2	55	Yes	Asphalt	Yes	No	No	Yes	Poor
20.14	TURNOUT PAST WHISPERING PINES		2	55	Yes	Asphalt	No	No	No	No	Poor
20.15	ANDERSON SPRINGS RD		2	55	Yes	Asphalt	Yes	No	No	No	Acceptable
20.16	TURNOUT JUST PAST DRY CREEK		2	55	Yes	Dirt	No	No	No	No	Good
20.17	TURNOUT BY SANTA CLARA RD		2	35	Yes	Dirt	Yes	No	No	No	Good
20.18	MINI MALL-T&J AUTO PARTS		2	25	Yes	Asphalt	No	No	No	No	Good
20.19	FIVE STAR TOWING		2	30	Yes	Asphalt	No	Yes	Yes	Yes	Acceptable
20.20	LAKESIDE APPLIANCE		2	30	Yes	Dirt	No	No	No	Yes	Good
20.21	TWIN PINE CASINO				Parking Lot		No	No	No	No	Good
20.22	PERRYS DELI		2	45	Yes	Dirt	Yes	No	No	No	Poor
20.23	CHARTER SCHOOL	30.09, 31.06	1	25	No	Dirt	Yes	No	No	No	Acceptable
20.24	ARMSTRONG RD		2	30	Yes	Asphalt	No	Yes	Yes	Yes	Good
20.25	TRI COUNTIES BANK		2	35	Yes	Asphalt	No	Yes	Yes	Yes	Good

Table C-4

Table 4.21- Roadway Characteristics for Bus Stops: Route 2 Northbound

			# of Travel	Speed	Can Bus pull out		Pull Out			Trip Generator Across	
Bus Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Limit	of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Distance
21.01	HWY 29 & YOUNG ST		2	35	Yes	Asphalt	No	Yes	Yes	Yes	Acceptable
21.02	HWY 175 & MCKINLEY DR		2	55	Yes	Asphalt	No	No	No	No	Good
21.03	MONTE VISTA COURT DR		2	55	Yes	Asphalt	No	No	No	No	Good
21.04	U-TURN TO BUS STOP AT ROCK		2	55	Yes	Asphalt	Yes	No	No	No	Acceptable
21.05	JUST NORTH OF CASA GRANDE DR		2	55	Yes	Gravel	No	No	No	No	Good
21.06	AUSTIN DR & SR 175		2	55	Yes	Gravel	No	No	No	No	Poor
21.07	WHISPERING PINES		2	55	Yes	Asphalt	No	No	No	Yes	Good
21.08	WATER CO SIGN		2	55	Yes	Asphalt	No	No	No	Yes	Good
21.09	GIFFORD SPRINGS		2	55	Yes	Asphalt	No	No	No	No	Acceptable
21.10	GOLF RD		2	55	Yes	Gravel	No	No	No	Yes	Acceptable
21.11	TURNOUT ACROSS FROM FIRE DEPT		2	55	Yes	Gravel	No	No	No	Yes	Good
21.12	HARDESTERS	20.11			Parking Lot		No	Parking Lot	No	No	Good
21.13	SUMMIT		2	55	Yes	Gravel	No	No	No	No	Poor
21.14	SR 175 & ENTRANCE RD		2	55	Yes	Asphalt	Yes	No	No	No	No
21.15	HOBERGS RESORT		2	55	Yes	Asphalt	Yes	No	No	No	No
21.16	SR 175 & HARRINGTON FLATS		2	55	Yes	Gravel	No	No	No	No	Poor
21.17	LOCH LOMOND		2	55	Yes	Dirt	No	No	No	Yes	Good
21.18	MARIAH MEADOWS		2	55	No	Dirt	Yes	No	No	Yes	Good
21.19	ADMIRAL RD		2	55	Yes	Dirt	No	No	No	No	Good
21.20	SALMINA		2	55	No	Dirt	Yes	No	No	Yes	Good
21.21	WILD CAT CANYON		2	55	No	Dirt	Yes	No	No	Yes	Acceptable
21.22	DIAMOND DUST		2	55	Yes	Dirt	No	No	No	Yes	Good
21.23	RED HILLS RD		2	55	No	Dirt	Yes	No	No	Yes	Good
		20.01, 40.05, 41.18, 50.01,									
21.24	KITS CORNER	51.19			Parking Lot		No	No	No	No	Good

Table 4.30- Roadway	v Characteristics for	Rus Stons	Route 3 Southbo	und
Table 7.30- Noauwa	y Characteristics for	Dus Stops.	Noute 3 Journal	ullu

Bus Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Speed Limit	Can Bus pull out of travel lane?	Pullout Material	Pull out needed?	Crosswalk	Sidewalk	Trip Generator Across the Street	Sight Distance
30.01	WALMART FOOD PLACE	11.38, 10.01, 31.13, 40.01, 41.21, 100.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.42		+	Parking Lot				Parking	g Lot	
30.02	JOB ZONE	40.02, 100.37, 120.04	5	55	No	Asphalt	Yes	No	No	No	Poor
30.03	ACROSS FROM LAKE TRANSIT	40.03, 100.38, 120.05	5	55	Yes	Gravel	No	No	No	No	Good
30.04	TOWER MART- 53/29		5	55?	Yes	Asphalt	No	Yes	Yes	Yes	Good
30.05	TWIN LAKES	31.10	2	55	No	Asphalt	Yes	No	No	No	Good
30.06	HIDDEN VALLEY WATER COMPANY	31.08			Parking Lot		No	No	No	Yes	Good
30.07	MUG SHOTS- COYOTE VALLEY PHARM	31.09			Parking Lot		No	No	No	No	Acceptable
30.08	HWY 29 & YOUNG ST-TRI COUNTIES BANK		2	35	Yes	Asphalt	No	Yes	Yes	Yes	Good
30.09	CHARTER SCHOOL	20.23, 31.06	1	25	No	Dirt	Yes	No	No	No	Acceptable
30.10	FIVE STAR TOWING		2	30	Yes	Asphalt	No	Yes	Yes	Yes	Acceptable
30.11	LAKE COUNTY APPLIANCE		2	30	Yes	Dirt	No	No	No	Yes	Good
30.12	TWIN PINES CASINO				Parking Lot		No	No	No	No	Good
30.13	LINCOLN AVENUE BRIDGE		2	25	Yes	Asphalt	No	No	Yes	No	Good
30.14	ST HELENA HOSPITAL	31.01	1	10	Parking Lot	Asphalt	No	No	Yes	Yes	Acceptable

Table 4.31- Roadway Characteristics for Bus Stops: Route 3 Northbound

Duc Stan ID	Due Chan Maria		# of Travel	Speed Limit	Can Bus pull out	Dullout Motorial	Pull Out	Crosswalls	Cidoualle	Trip Generator Across	
Bus Stop ID	Bus Stop Name	Shares Stops with:	Lanes		of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Distanc
31.01	ST HELENA HOSPITAL	30.14	1	10	Parking Lot	Asphalt	No	No	Yes	Yes	Acceptable
31.02	LINCOLN AVENUE BRIDGE		2	25	Yes	Asphalt	No	No	Yes	No	Good
31.03	TWIN PINES CASINO				Parking Lot		No	No	No	No	Good
31.04	PERRYS DELI		2	45	Yes	Dirt	Yes	No	No	No	Poor
31.05	ARMSTRONG RD		2	30	Yes	Asphalt	No	Yes	Yes	Yes	Good
31.06	CHARTER SCHOOL	20.23, 30.09	1	25	No	Dirt	Yes	No	No	No	Acceptable
31.07	HARDESTERS		2	35	Yes	Asphalt	No	Yes	Yes	Yes	Acceptable
31.08	HIDDEN VALLEY WATER COMPANY	30.06			Parking Lot		No	No	No	Yes	Good
31.09	MUG SHOTS- COYOTE VALLEY PHARM	30.07			Parking Lot		No	No	No	No	Acceptable
31.1	TWIN LAKES	30.05	2	55	No	Asphalt	Yes	No	No	No	Good
31.11	HWY 53 & HWY 29 (FOSTER FREEZE)		5	55	Yes	Asphalt	No	Yes	Yes	Yes	Good
31.12	LAKE TRANSIT YARD	41.2			Parking Lot		No	No	No	No	Good
		11.38, 30.01, 40.01, 10.01,									
	WALMART FOOD PLACE	41.21, 100.01, 100.45, 110.01,			Parking Lot				Parkin	g Lot	
31.13		110.42, 120.01, 120.12, 120.41									

Table 4.40- Roadway Characteristics for Bus Stops: Route 4 Westbound

	<u> </u>	1									
			# of Travel	Speed	Can Bus pull out		Pull Out			Trip Generator Across	
Bus Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Limit	of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Distance
		11.38, 30.01, 31.13, 10.01,			•				•	•	
40.01	WALMART FOOD PLACE	41.21, 100.01, 100.45, 110.01,			Parking Lot				Parking	Lot	
10.01	W LEW WITH OOD FERGE	110.42, 120.01, 120.12, 120.42							8		
40.02	JOB ZONE	30.02, 100.37, 120.04	5	55	No	Asphalt	Yes	No	No	No	Poor
40.03	ACROSS FROM LAKE TRANSIT	30.03, 100.38, 120.05	5	55	Yes	Gravel	No	No	No	No	Good
40.04	TOWER MART		6	55?	Yes	Asphalt	No	Yes	Yes	Yes	Good
		21.24, 20.01, 41.18, 50.01,									
40.05	KITS CORNER	51.19			Parking Lot		No	No	No	No	Good
40.06	KELSEYVILLE AUTO WREKCERS		2	45	Yes	Gravel	No	No	No	No	Acceptable
40.07	STORE 24	41.16			Parking Lot		Yes	No	No	No	Good
40.08	GAS HILL		2	25	No	Asphalt	Yes	No	Yes	No	Good
40.09	4TH & MAIN		2	25	Yes	Dirt	No	Yes	Yes	Yes	Good
40.10	PHARMACY		2	25	Yes	Asphalt	No	No	Yes	Yes	Good
40.11	ACROSS FROM KELSEYVILLE LUMBER		2	25	Yes	Asphalt	No	No	No	No	Good
40.12	MENDO COLLEGE	50.16, 51.07, 80.27, 81.01			Parking Lot	•	No	No	No	No	Good
	ACROSS FROM ROTTEN ROBBIES		3	35	No	Dirt	Yes	No	No	Yes	Poor
	STATE FARM (ACROSS FROM KMART)		3	35	Yes	Asphalt	Yes	No	Yes	Yes	Good
	NURSERY & GROCERY OUTLET	50.12	3	35	No	Asphalt	Yes	No	Yes	Yes	Good
	BOWLING ALLEY	41.04, 50.13, 51.04			Parking Lot		No	No	No	No	N/A
	SAFEWAY	50.17, 71.09, 81.07			Parking Lot		No	No	Yes	No	Good
	9TH & MAIN	50.18, 80.17	3	35	Yes	Asphalt	No	No	Yes	Yes	Good
	3RD & MAIN	50.08, 50.19, 80.18	3	35	Yes	Asphalt	No	Yes	Yes	Yes	Good
40.19	SND & IVIAIIV	30.06, 30.19, 80.18] 3	33	162	Ashugir	INO	162	162	165	G000

Table 4.41- Roadway Characteristics for Bus Stops: Route 4 Eastbound

			# of Travel	Speed	Can Bus pull out		Pull Out			Trip Generator Across	
Bus Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Limit	of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Distance
41.01	3RD & MAIN	51.01, 70.01, 71.11, 81.05,	3	35	Yes	Asphalt	No	Yes	Yes	Yes	Good
41.02	MAIN & MARTIN	80.19	3	35	No	Asphalt	Yes	Yes	Yes	Yes	Good
41.03	MAIN & D ST		3	35	Yes	Asphalt	Yes	No	Yes	Yes	Good
41.04	BOWLING ALLEY	40.16, 50.13, 51.04			Parking Lot		No	No	No	No	N/A
41.05	SOCIAL SECURITY	50.14, 51.05	2	35	Yes	Asphalt	Yes	No	No	No	Good
41.06	TACO BELL BEFORE DRIVEWAY	50.15, 51.06	3	30	No	Asphalt	Yes	No	Yes	Yes	Good
41.07	BRUNOS	51.08, 80.23	3	35	Yes	Asphalt	Yes	No	Yes	No	Acceptable
41.08	GROCERY OUTLET	51.09, 80.24	3	35	No	Asphalt	Yes	No	Yes	Yes	Good
41.09	HOSPICE	51.10, 110.18, 120.23	3	35	Yes	Asphalt	No	No	Yes	No	Good
41.1	KMART		2	35	Yes	Asphalt	No	No	Yes	No	Good
41.11	ROTTEN ROBBIES		3	35	No	Asphalt	Yes	No	Yes	Yes	Good
41.12	KELSEYVILLE LUMBER		2	25	Yes	Asphalt	No	No	No	No	Good
41.13	ACROSS FROM PHARMACY		2	25	Yes	Asphalt	No	No	Yes	Yes	Good
41.14	4TH & MAIN (WEST AMERICA BANK)		2	25	Yes	Asphalt	No	Yes	Yes	Yes	Good
41.15	BEFORE LIVE OAK		2	25	Yes	Asphalt	No	No	No	No	Good
41.16	STORE 24	40.07			Parking Lot		Yes	No	No	No	Good
41.17	ACROSS FROM KELSEYVILLE WRECKERS		2	45	Yes	Gravel	No	No	No	No	Acceptable
		21.24, 40.05, 20.01, 50.01,									
41.18	KITS CORNER	51.19			Parking Lot		No	No	No	No	Good
41.19	HWY 29 & HWY 53- FOSTERS		5	55	Yes	Asphalt	No	Yes	No	Yes	Good
41.2	LAKE TRANSIT YARD	31.12			Parking Lot		No	No	No	No	Good
		11.38, 30.01, 31.13, 40.01,									
41.21	WALMART FOOD PLACE	10.01, 100.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.42			Parking Lot				Parking	g Lot	

Table 4.50- Roadway Characteristics for Bus Stops: Route 4A Westbound

			# of Travel	Speed	Can Bus pull out		Pull Out			Trip Generator Across	
Bus Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Limit	of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Distance
		21.24, 40.05, 20.01, 41.18,									
50.01	KITS CORNER	51.19			Parking Lot		No	No	No	No	Good
50.02	RIVIERA SHOPPING CENTER		2	55	No	Asphalt	Yes	No	No	Yes	Good
50.03	BAYVIEW ESTATES		2	55	Yes	Asphalt	No	No	No	Yes	Acceptable
50.04	MONTEZUMA WAY		2	55	Yes	Gravel	No	No	No	Yes	Good
50.05	RIVIERA WEST		2	40	Yes	Gravel	No	No	No	Yes	Acceptable
50.06	BUCKINGHAM				Parking Lot		No	No	No	Yes	Good
50.07	SODA BAY STORE		2	40	No	Asphalt	Yes	Yes	No	Yes	Acceptable
50.08	3RD & MAIN	40.19, 50.19, 80.18	3	35	Yes	Asphalt	No	Yes	Yes	Yes	Good
50.09	FINLEY POST OFFICE		2	35	Yes	Dirt	Yes	No	No	Yes	Acceptable
50.10	KONOCTI VISTA CASINO	51.13			Parking Lot		No	No	No	No	Good
50.11	KMART		2	35	Yes	Asphalt	No	No	Yes	No	Good
50.12	NURSERY & GROCERY OUTLET	40.15	3	35	No	Asphalt	Yes	No	Yes	Yes	Good
50.13	BOWLING ALLEY	41.04, 40.16, 51.04			Parking Lot		No	No	No	No	N/A
50.14	SOCIAL SECURITY	41.05, 51.05	2	35	Yes	Asphalt	No	No	Yes	No	Good
50.15	TACO BELL BEFORE DRIVEWAY	41.06, 51.06	3	30	No	Asphalt	Yes	No	Yes	Yes	Good
50.16	MENDO COLLEGE	40.12, 51.07, 80.27, 81.01			Parking Lot		No	No	No	No	Good
50.17	SAFEWAY	40.17, 71.09, 81.07			Parking Lot		No	No	Yes	No	Good
50.18	9TH & MAIN	40.18, 80.17	3	35	Yes	Asphalt	No	No	Yes	Yes	Good
50.19	3RD & MAIN	50.08, 40.19, 80.18	3	35	Yes	Asphalt	No	Yes	Yes	Yes	Good

Table 4.51- Roadway Characteristics for Bus Stops: Route 4A Eastbound

			# of Travel	Speed	Can Bus pull out		Pull Out			Trip Generator Across	
Bus Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Limit	of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Distance
51.01	3RD & MAIN	41.01, 70.01, 71.11, 81.05	3	35	Yes	Asphalt	No	Yes	Yes	Yes	Good
51.02	MAIN & D ST		3	35	Yes	Asphalt	No	No	Yes	Yes	Good
51.03	D STREET		3	35	Yes	Asphalt	No	No	Yes	Yes	Good
51.04	BOWLING ALLEY	41.04, 40.16, 50.13			Parking Lot		No	No	No	No	N/A
51.05	SOCIAL SECURITY	41.05, 50.14	2	35	Yes	Asphalt	No	No	Yes	No	Good
51.06	TACO BELL BEFORE DRIVEWAY	41.06, 50.15	3	30	No	Asphalt	Yes	No	Yes	Yes	Good
51.07	MENDO COLLEGE	50.16, 40.12, 80.27, 81.01			Parking Lot		No	No	No	No	Good
51.08	BRUNOS	41.07, 80.23	3	35	Yes	Asphalt	Yes	No	Yes	No	Acceptable
51.09	GROCERY OUTLET	41.08, 80.24	3	35	No	Asphalt	Yes	No	Yes	Yes	Good
51.10	HOSPICE	41.09, 110.18, 120.23	3	35	Yes	Asphalt	No	No	Yes	No	Good
51.11	KMART	80.25	2	35	Yes	Asphalt	No	No	Yes	No	Good
51.12	ROTTEN ROBBIES	80.26	3	35	No	Asphalt	Yes	No	No	Yes	Good
51.13	KONOCTI VISTA CASINO	50.10			Parking Lot		No	No	No	No	Good
51.14	FINLEY POST OFFICE		2	35	Yes	Dirt	No	No	No	Yes?	Good
51.15	SODA BAY STORE		2	40	No	Dirt	Yes	Yes	No	Yes	Good
51.16	RIVERA WEST		2	40	No	Asphalt	Yes	No	No	Yes	Acceptable
51.17	MONTEZUMA WAY		2	40	No	Dirt	Yes	No	No	Yes	Acceptable
51.18	RIVERA SHOPPING CENTER		2	55	No	Asphalt	Yes	No	No	Yes	Good
		21.24, 40.05, 20.01, 50.01,									
51.19	KITS CORNER	41.18			Parking Lot		No	No	No	No	Good

Table 4.70- Roadway Characteristics for Bus Stops: Route 7 Westbound

			# of Travel	Speed	Can Bus pull out		Pull Out		Т	rip Generator Across	
Bus Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Limit	of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Distance
70.01	3RD & MAIN	51.01, 41.01, 71.11, 81.05,	3	35	Yes	Asphalt	No	Yes	Yes	Yes	Good
70.02	9TH & MAIN (NATURAL HIGH)	71.10, 81.06	2	35	Yes	Asphalt	No	No	Yes	Yes	Good
70.03	SENTRY MARKET	11.07, 10.29, 71.08			Parking Lot				Parking L	ot	
70.04	ROBINSONS CASINO	71.07, 10.30, 11.06			Parking Lot				Parking L	ot	
70.05	1ST & MAIN UPPER LAKE	71.06	2	25	No	Asphalt	Yes	Yes	Yes	Yes	Acceptable
70.06	BLUE LAKES		2	35	Yes	Gravel	Yes	No	No	Yes	Good
70.07	MENDOCINO COLLEGE UKIAH	71.04			Parking Lot		No	No	No	No	Good
70.08	PEAR TREE	71.03	3	25	Yes	Asphalt	No	No	Yes	Yes	Good
70.09	VETERANS CLINIC	71.02	2	15	Yes	Asphalt	No	No	Yes	Yes	Good
70.1	AIRPORT	71.01	3	30	Yes	Asphalt	No	No	Yes	Yes	Good

Table 4.71- Roadway Characteristics for Bus Stops: Route 7 Eastbound

			# of Travel	Speed	Can Bus pull out		Pull Out			Trip Generator Across	
Bus Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Limit	of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Distance
71.01	AIRPORT	70.10	3	30	Yes	Asphalt	No	No	Yes	Yes	Good
71.02	VETERANS CLINIC	70.09	2	15	Yes	Asphalt	No	No	Yes	Yes	Good
71.03	PEAR TREE	70.08	3	25	Yes	Asphalt	No	No	Yes	Yes	Good
71.04	MENDOCINO COLLEGE	70.07			Parking Lot		No	No	No	No	Good
71.05	BLUE LAKES		2	35	No	Gravel	Yes	No	No	Yes	Good
71.06	1ST & MAIN UPPER LAKE	70.05	2	25	No	Asphalt	Yes	Yes	Yes	Yes	Acceptable
71.07	ROBINSONS CASINO	70.04, 10.30, 11.06			Parking Lot				Parking	Lot	
71.08	SENTRY MARKET	11.07, 10.29, 70.03			Parking Lot				Parking	Lot	
71.09	SAFEWAY	40.17, 50.17, 81.07			Parking Lot		No	No	Yes	No	Good
71.10	9TH & MAIN (NATURAL HIGH)	70.02, 81.06	2	35	Yes	Asphalt	No	No	Yes	Yes	Good
71.11	3RD & MAIN	51.01, 70.01, 41.01, 81.05	3	35	Yes	Asphalt	No	Yes	Yes	Yes	Good

Table 4.80- Roadwa	y Characteristics f	for Bus Stops: Route 8 Northbound
--------------------	---------------------	-----------------------------------

			# of Travel	Speed	Can Bus pull out		Pull Out		a	Trip Generator Across	
Bus Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Limit	of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Distanc
80.01	LAKE COUNTY JAIL	11.02, 10.35, 81.21			Parking Lot				Parking		
80.02	SUTTER LAKESIDE	11.01, 10.36, 81.20	_		Parking Lot				Parking		
80.03	LAKESIDE HEALTH CLINIC	81.19	2	35	Yes	Asphalt	No	No	No	No	Good
80.04	NORTHPORT MOBILE HOME PARK	81.18	2	35	Yes	Dirt	Yes	No	No	No	Acceptable
80.05	EL DORADO MOTEL		2	35	Yes	Dirt	No	No	No	Yes	Acceptable
80.06	PEOPLE SERVICES-WALNUT DR		2	35	Yes	Dirt	No	Yes	No	Yes	Poor
80.07	ELKS LODGE		2	35	Yes	Dirt	No	No	No	No	Good
80.08	RAINBOW MOBILE HOME PARK		2	35	Yes	Asphalt	No	No	No	No	Good
80.09	PARK WAY		2	35	No	Dirt	Yes	No	No	No	Acceptable
80.10	TOWER MART		2	35	No	Asphalt	Yes	No	No	Yes	Acceptable
80.11	CRYSTAL LAKE DR		2	35	Yes	Asphalt	No	No	No	No	Good
80.12	BEACH LN-RAINBOW LODGE		2	35	No	Dirt	Yes	No	No	No	Poor
80.13	LAKESHORE & LANGE		2	35	No	Asphalt	Yes	No	No	No	Good
80.14	HIGH ST		2	35	No	Asphalt	Yes	Yes	Yes	Yes	Good
80.15	LIBRARY		2	35	No	Asphalt	Yes	No	Yes	No	Good
80.16	N.FORBES ST		2	35	Yes	Asphalt	No	No	Yes	Yes	Good
80.17	9TH & MAIN	50.18, 40.18	3	35	Yes	Asphalt	No	No	Yes	Yes	Good
80.18	3RD & MAIN	50.08, 50.19, 40.19	3	35	Yes	Asphalt	No	Yes	Yes	Yes	Good
80.19	MAIN & MARTIN	41.02	3	35	No	Asphalt	Yes	Yes	Yes	Yes	Good
80.20	STARR & MARTIN (BELLA VISTA)		2	25	Yes	Asphalt	No	Yes	Yes	Yes	Good
80.21	TRIBAL HEALTH				Parking Lot		No	No	Yes	No	Good
80.22	BEVINS ACROSS FROM WIC		2	35	No	Asphalt	Yes	No	Yes	No	Good
80.23	BRUNOS	41.07, 51.08	3	35	Yes	Asphalt	Yes	No	Yes	No	Acceptable
80.24	GROCERY OUTLET	41.08, 51.09	3	35	No	Asphalt	Yes	No	Yes	Yes	Good
80.25	KMART	51.11	2	35	Yes	Asphalt	No	No	Yes	No	Good
80.26	ROTTEN ROBBIES	51.12	3	35	No	Asphalt	Yes	No	No	Yes	Good
80.27	MENDO COLLEGE	50.16, 51.07, 40.12, 81.01			Parking Lot		No	No	No	No	Good

Table 4.81- Roadway Characteristics for Bus Stops: Route 8 Southbound

			# of Travel	Speed	Can Bus pull out		Pull Out			Trip Generator Across	
Bus Stop ID	Bus Stop Name	Shares Stops with:	Lanes	Limit	of travel lane?	Pullout Material	needed?	Crosswalk	Sidewalk	the Street?	Sight Distance
81.01	MENDO COLLEGE	40.12, 50.16, 51.07, 80.27			Parking Lot		No	No	No	No	Good
81.02	AAA		3	35	Yes	Asphalt	No	Yes	Yes	Yes	Acceptable
81.03	SENIOR CENTER	110.24, 120.30	1	slow	No	Asphalt	Yes	No	Yes	Yes	Good
81.04	MARTIN ST (BELLA VISTA)		2	25	Yes	Asphalt	No	Yes	Yes	Yes	Good
81.05	3RD & MAIN	51.01, 41.01, 71.11, 70.01	3	35	Yes	Asphalt	No	Yes	Yes	Yes	Good
81.06	9TH & MAIN (NATURAL HIGH)	71.10, 70.02	2	35	Yes	Asphalt	No	No	Yes	Yes	Good
81.07	SAFEWAY	40.17, 50.17,71.09			Parking Lot		No	No	Yes	No	Good
81.08	VIA DEL LAGO		3	25	No	Asphalt	Yes	No	Yes	Yes	Good
81.09	LAKESHORE & LANGE		2	35	No	Asphalt	Yes	No	No	No	Good
81.1	BEACH LN-RAINBOW LODGE		2	35	Yes	Asphalt	No	No	No	No	Good
81.11	THE CHEATEU		2	35	No	Asphalt	Yes	No	No	Yes	Acceptable
81.12	TOWER MART		2	35	Yes	Asphalt	No	No	No	No	Acceptable
81.13	PARK WAY		2	35	No	Asphalt	Yes	No	No	No	Good
81.14	ACROSS FROM RAINBOW MOBILE HOME		2	35	Yes	Asphalt	No	No	No	No	Poor
81.15	ROCKY POINT		2	35	Yes	Dirt	No	No	No	Yes	Good
81.16	ACROSS FROM PEOPLE SERVICES		2	35	Yes	Asphalt	No	No	No	No	Good
81.17	ACROSS FROM PERKS MOBILE HOME		2	25	No	Asphalt	Yes	No	No	Yes	Good
81.18	NORTHPORT MOBILE HOME PARK	80.04	2	35	Yes	Dirt	Yes	No	No	No	Acceptable
81.19	LAKESIDE HEALTH CLINIC	80.03	2	35	Yes	Asphalt	No	No	No	No	Good
81.2	SUTTER LAKESIDE	11.01, 10.36, 80.02			Parking Lot				Parking	g Lot	
81.21	LAKE COUNTY JAIL	11.02, 10.35, 80.01			Parking Lot				Parking	g Lot	

us Stop ID	Bus Stop Name	Shares Stops with:	# of Travel Lanes	Speed Limit	Can Bus pull out of travel lane?	Pullout Material	Pull Out needed?	Crosswalk	Sidewalk	Trip Generator Across the Street?	Sight Distan
		11.38, 30.01, 31.13, 40.01,									
100.01	WALMART FOOD PLACE	41.21, 10.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.42			Parking Lot				Parkin	g Lot	
100.02	CLEARLAKE APTS	120.13	2	35	No	Asphalt	Yes	No	Yes	Yes	Good
100.03	J&L MARKET	120.14	2	35	No	Dirt	Yes	No	No	Yes	Poor
100.04	CROSSROADS CHURCH	120.15	2	35	No	Dirt	Yes	No	No	No	Acceptab
100.05	CYPRESS	120.16	2	45	No	Asphalt	Yes	No	No	Yes	Good
100.06	MENDO MILL		2	35	Yes	Dirt	No	No	No	Yes	Good
100.07	OLD HWY 53 & LAKESHORE		2	25	No	Asphalt	Yes	No	No	No	Good
100.08	OLD RED CROSS		2	35	Yes	Dirt	No	No	No	No	Good
100.09	HILL AVE		2	35	Yes	Dirt	No	No	No	No	Good
100.10	RIDGE LAKE APTS-COMMONS		2	35	Yes	Asphalt	No	No	Yes	No	Good
100.11	BURNS VALLEY MALL		3	35	No	Asphalt	Yes	No	Yes	No	Good
100.12	CLEARLAKE POST OFFICE		2	25	Yes	Dirt	No	No	No	No	Good
100.13	BABY STORE (ACROSS FROM LOCUST)		2	35	No	Asphalt	Yes	No	Yes	No	Acceptal
100.14	CITY HALL		3	35	No	Asphalt	Yes	No	No	Yes	Good
100.15	OLD BOWLING ALLEY		2	25	Yes	Asphalt	No	No	No	No	Poor
100.16	POMO & WOODLAND		2	25	No	Asphalt	Yes	No	No	No	Poor
100.17	BOXWOOD & ARROWHEAD		2	25	No	Dirt	Yes	Yes	No	Yes	Good
100.17	TOYON		2								
				25	No	Dirt	Yes	Yes	No	Yes	Good
100.19	MODOC		2	25	Yes	Dirt	No	No	No	No	Acceptal
100.2	2ND ST (HALFWAY DOWN BLOCK)		2	25	Yes	Dirt	No	No	No	No	Good
100.21	2ND & BUSH		2	25	Yes	Dirt	No	No	No	No	Good
100.22	8TH & BUSH		2	25	No	Dirt	Yes	No	No	No	Good
100.23	11TH & BUSH		2	25	No	Asphalt	Yes	No	No	No	Good
100.24	13TH & COUNTRY CLUB		2	25	No	Dirt	Yes	No	No	No	Good
100.25	COUNTRY CLUB & ARROWHEAD		2	25	No	Dirt	Yes	No	No	No	Poor
100.26	CLEARLAKE PARK POST OFFICE		2	25	Yes	Dirt	No	No	No	No	Good
100.27	AMERICAS BEST VALUE INN		2	35	Yes	Asphalt	No	No	Yes	No	Good
100.28	LAKESHORE & POMO		2	35	No	Dirt	Yes	No	No	No	Acceptal
100.29	CITY HALL		3	35	No	Asphalt	Yes	No	No	Yes	Good
	AUSTIN PARK		2	35	Yes	Asphalt	No	Yes	Yes	Yes	Good
100.31	BAYLIS & LAKEHORE		2	35	Yes	Dirt	No	Yes	No	Yes	Good
100.32	HIGHLANDS PARK (CASTLE DONUTS)		2	35	Yes	Asphalt	No	Yes	No	Yes	Good
100.33	CATFISH COFFEE		2	35	No	Asphalt	Yes	No	Yes	No	Good
100.34	VETERANS CLINIC	110.30	2	35	Yes	Dirt	No	Yes	Yes'	Yes	Good
100.35	VALERO	110.31	2	35	Yes	Asphalt	No	No	No	No	Good
100.36	SOCIAL SERVICES	110.51		33	Parking Lot	ποριιαίτ	No	No	No	No	Good
100.37	JOB ZONE	40.02, 30.02, 120.04	5	55	No	Asphalt	Yes	No	No	No	Poor
100.37	ACROSS FROM LAKE TRANSIT	40.02, 30.02, 120.04	5								
100.38		120.06		55 25	Yes	Gravel	No No	No No	No No	No	Good
	HWY 53 & MAIN (DL'S PIZZA)	120.06	2	25 25	Yes	Asphalt	No	No	No	Yes	Good
100.40	BETWEEN LAKE AUGUS ST	430.00	2	25	Yes	Asphalt	No	No	Yes	No	Good
100.41	LOWER LAKE HIGH SCHOOL	120.08	2	35	No	Asphalt	Yes	No	Yes	No	Good
100.42	CEMETERY	120.09	2	35	Yes	Dirt	No	No	No	No	Poor
100.43	BRYANT RD	120.10	2	25	Yes	Gravel	No	No	No	No	Poor
100.44	CACHE CREEK APTS	120.11	2	25	Yes	Asphalt	No	No	Yes	No	Good
		11.38, 30.01, 31.13, 40.01,									
100.45	WALMART FOOD PLACE	41.21, 100.01, 10.01, 110.01,			Parking Lot				Parkin	g Lot	
		110.42, 120.01, 120.12, 120.42									

Bus Stop ID	Bus Stop Name	Shares Stops with:	# of Travel Lanes	Speed Limit	Can Bus pull out of travel lane?	Pullout Material	Pull Out needed?	Crosswalk	Sidewalk	Trip Generator Across the Street?	Sight Distan
110.01	WALMART FOOD PLACE	11.38, 30.01, 31.13, 40.01, 41.21, 100.01, 100.45, 10.01, 110.42, 120.01, 120.12, 120.42			Parking Lot				Parking	Lot	
110.02	ST.HELENA CLEARLAKE		2	35	No	Asphalt	Yes	No	No	Yes	Poor
110.03	IRVING & 18TH		2	25	Yes	Dirt	No	No	No	No	Poor
110.04	BOYLES & 18TH		2	25	No	Dirt	Yes	No	No	No	Good
110.05	BOYLES & 25TH		2	25	Yes	Dirt	No	No	No	No	Good
110.06	BOYLES BETWEEN 30TH & 31ST		2	25	No	Dirt	Yes	No	No	No	Good
110.07	33RD & PHILLIPS		2	30	No	Dirt	Yes	No	No	No	Acceptab
110.08	36TH & PHILLIPS		2	30	Yes	Dirt	No	No	No	No	Good
110.09	PHILLIPS & 40TH (40TH STORE)		2	30	No	Asphalt	No	No	No	No	Acceptab
110.1	45TH -THE DUMP DAVIS ST		2	30	Yes	Dirt	No	No	No	No	Poor
110.11	MOSS (FIRST DRIVE WAY)		2	30	Yes	Asphalt	No	No	No	No	Acceptab
110.12	WEST AMERICA BANK		2	25	Yes	Asphalt	No	Yes	Yes	Yes	Good
110.13	CLEARLAKE FAMILY CLINIC		2	35	No	Dirt	Yes	No	No	Yes	Good
110.14	NAPA AUTO PARTS	120.19	2	35	Yes	Asphalt	No	No	No	Yes	Good
110.15	NOTT'S LIQUOR		2	25	Yes	Asphalt	No	No	Yes	Yes	Good
110.16	CATFISH COFFEE	120.21	2	35	No	Asphalt	Yes	No	Yes	Yes	Good
110.17	BURGER TIME	120.22	2	35	Yes	Asphalt	No	No	No	No	Good
110.18	HOSPICE	51.10, 41.09, 120.23	3	35	Yes	Asphalt	No	No	Yes	No	Good
110.19	OLD FIREHOUSE	120.24	2	35	Yes	Dirt	No	Yes	No	Yes	Good
110.2	AUSTIN PARK	120.25	2	35	Yes	Dirt	No	No	No	Yes	Good
110.21	HAVERTY FIELD	120.26	2	35	No	Asphalt	Yes	No	Yes	Yes	Good
110.22	CLEARLAKE POST OFFICE	120.27	2	35	No	Asphalt	Yes	Yes	Yes	Yes	Good
110.23	BURNS VALLEY MALL		2	35	No	Asphalt	Yes	No	Yes	Yes	Good
110.24	SENIOR CENTER	81.03, 120.30	1	25	No	Asphalt	Yes	No	Yes	Yes	Good
110.25	SHELTER AT WALNUT GROVE APTS	120.31			Parking Lot		No	No	Yes	No	Good
110.26	SAFEWAY	120.32	2	35	No	Asphalt	Yes	No	Yes	No	Acceptab
110.27	OLD HWY 53 PAST RITE AID	120.33	2	35	Yes	Asphalt	No	No	No	No	Good
110.28	HIGHLANDS WAY	120.34	2	35	Yes	Asphalt	No	No	No	No	Acceptab
110.29	HILLCREST	120.35	2	35	Yes	Dirt	No	No	No	No	Poor
110.3	VETERANS CLINIC	100.34	2	35	Yes	Dirt	No	Yes	Yes'	Yes	Good
110.31	VALERO	100.35	2	35	Yes	Asphalt	No	No	No	No	Good
110.32	MOSS & DAVIS (BEFORE 35MPS SIGN)		2	30	Yes	Asphalt	No	No	No	No	Acceptab
110.33	PHILLIPS & 44TH		2	30	Yes	Dirt	No	No	No	No	Acceptab
110.34	PHILLIPS & 40TH		2	30	Yes	Dirt	No	No	No	No	Good
110.35	32ND & PHILLIPS		2	30	Yes	Dirt	No	No	No	No	Acceptab
110.36	BOYLES & 29TH		2	25	Yes	Dirt	No	No	No	No	Good
110.37	BETWEEN 26TH & 25TH		2	25	Yes	Dirt	No	No	No	No	Good
110.38	BOYLES AND 21ST		2	25	No	Dirt	Yes	No	No	No	Acceptab
110.39	IRVING & 18TH		2	30	No	Asphalt	Yes	No	No	No	Good
110.4	ST.HELENA CLEARLAKE		2	35	Yes	Dirt	No	No	No	No	Poor
110.41	WOODLAND COLLEGE	11.37, 120.02			Parking Lot				Parking	Lot	
110.42	WALMART FOOD PLACE	10.01, 11.38, 30.01, 31.13, 40.01, 41.21, 100.01, 100.45, 110.01, 120.01, 120.12, 120.42			Parking Lot				Parking	Lot	

Bus Stop ID	Bus Stop Name	Shares Stops with:	# of Travel Lanes	Speed Limit	Can Bus pull out of travel lane?	Pullout Material	Pull Out needed?	Crosswalk	Sidewalk	Trip Generator Across the Street?	Sight Distan
120.01	WALMART FOOD PLACE	10.01, 11.38, 30.01, 31.13, 40.01, 41.21, 100.01, 100.45, 110.01, 110.42, 120.12, 120.42			Parking Lot				Parkinį	g Lot	
120.02	WOODLAND COLLEGE	11.37, 110.41			Parking Lot				Parkin	g Lot	
120.03	SOCIAL SERVICES				Parking Lot		No	No	No	No	Good
120.04	JOB ZONE	40.02, 100.37, 30.02	5	55	No	Asphalt	Yes	No	No	No	Poor
120.05	ACROSS FROM LAKE TRANSIT	40.03, 100.38, 30.03	5	55	Yes	Gravel	No	No	No	No	Good
120.06	HWY 53 & MAIN (DL'S PIZZA)	100.39	2	25	Yes	Asphalt	No	No	No	Yes	Good
120.07	BETWEEN LAKE ST & SECOND ST		2	25	Yes	Asphalt	No	No	Yes	No	Good
120.08	LOWER LAKE HIGH SCHOOL	100.41	2	35	No	Asphalt	Yes	No	Yes	No	Good
120.09	CEMETERY	100.42	2	35	Yes	Dirt	No	No	No	No	Poor
120.10	BRYANT RD	100.43	2	25	Yes	Gravel	No	No	No	No	Poor
120.11	CACHE CREEK APTS	100.44	2	25	Yes	Asphalt	No	No	Yes	No	Good
120.12	WALMART FOOD PLACE	11.38, 30.01, 31.13, 40.01, 41.21, 100.01, 100.45, 110.01,	_	23	Parking Lot	Aspirate			Parkinį		3000
120 12	CLEADLAKE ADTS	110.42, 120.01, 10.01, 120.42		25	No	A l l +	V	NI-	V	V	Canal
120.13	CLEARLAKE APTS	100.02	2	35	No	Asphalt	Yes	No	Yes	Yes	Good
120.14	J&L MARKET	100.03	2	35	No	Dirt	Yes	No	No	Yes	Poor
120.15	CROSSROADS CHURCH	100.04	2	35	No	Dirt	Yes	No	No	No	Acceptak
120.16	CYPRESS	100.05	2	45	No	Asphalt	Yes	No	No	Yes	Good
120.17	MENDO MILL (ACROSS THE STREET)		2	35	Yes	Asphalt	No	No	Yes	No	Good
120.18	OLD HWY 53 & LAKESHORE		2	25	No	Asphalt	Yes	No	No	No	Good
120.19	NAPA AUTO PARTS	110.14	2	35	Yes	Asphalt	No	No	No	Yes	Good
120.2	NOTT'S LIQOUR		2	35	Yes	Asphalt	No	No	No	Yes	Good
120.21	CATFISH COFFEE	110.16	2	35	No	Asphalt	Yes	No	Yes	Yes	Good
120.22	BURGER TIME	110.17	2	35	Yes	Asphalt	No	No	No	No	Good
120.23	HOSPICE	41.09, 51.10, 110.18	3	35	Yes	Asphalt	No	No	Yes	No	Good
120.24	OLD FIREHOUSE	110.19	2	35	Yes	Dirt	No	Yes	No	Yes	Good
120.25	AUSTIN PARK	110.20	2	35	Yes	Dirt	No	No	No	Yes	Good
120.26	HAVERTY FIELD	110.21	2	35	No	Asphalt	Yes	No	Yes	Yes	Good
120.27	CLEARLAKE POST OFFICE	110.22	2	35	No	Asphalt	Yes	Yes	Yes	Yes	Good
120.28	BURNS VALLEY MALL		2	35	No	Asphalt	Yes	No	Yes	Yes	Good
120.29	B&G TIRES		2	30	No	Asphalt	Yes	No	Yes	Yes	Good
120.3	SENIOR CENTER	81.03, 110.24	1	25	No	Asphalt	Yes	No	Yes	Yes	Good
120.31	SHELTER AT WALNUT GROVE APTS	110.25			Parking Lot		No	No	Yes	No	Good
120.32	SAFEWAY	110.26	2	35	No	Asphalt	Yes	No	Yes	No	Acceptab
120.33	OLD HWY 53 PAST RITE AID	110.27	2	35	Yes	Asphalt	No	No	No	No	Good
120.34	HIGHLANDS WAY	110.28	2	35	Yes	Asphalt	No	No	No	No	Acceptab
120.35	HILLCREST	110.29	2	35	Yes	Dirt	No	No	No	No	Poor
120.36	BALLPARK-OLD HWY 53/LAKESHORE		2	35	Yes	Asphalt	No	No	Yes	No	Poor
120.37	MENDO MILL		2	35	Yes	Asphalt	No	No	Yes	No	Good
120.38	KING FISHER		2	45	Yes	Asphalt	No	No	No	No	Good
120.39	CEDAR VILLAGE APTS		2	45	No	Asphalt	Yes	No	Yes	No	Good
120.40	HIGHLANDS APTS		2	35	Yes	Asphalt	No	No	Yes	No	Good
120.41	CLEARLAKE APTS		2	35	Yes	Asphalt	No	No	Yes	No	Good
120.42	WALMART FOOD PLACE	10.01, 11.38, 30.01, 31.13, 40.01, 41.21, 100.01, 100.45,			Parking Lot				Parkinį	g Lot	

Table C-5

Table 5.10 - Bus Stop Passenger Amenities -- Route 1 Westbound

					Sign	า		Pole		Bench	9	Shelter				ı
						Dia also di hec								Light of		ADA Assess
Due Char ID	Due Chara Name	Domanto	Daaudinaa	V/NI	Condition	Blocked by	\//NI	Canaditian	V/NI	Com dition	V/NI	Condition	Chada	Light at	Church Limbs	ADA Access- ible?
Bus Stop ID	Bus Stop Name	Repeats 11.38, 30.01, 31.13, 40.01, 41.21,	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ibler
10.01	WALMART FOOD PLACE	100.01, 100.45, 110.01, 110.42,	High 27	Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
10.01	WALWART TOOD FLACE	120.01, 120.12, 120.42	Tilgii 27	163	A	NO	163	A	INO	IN/A	NO	N/A	D	NO	NO	163
10.02	KEYS BLVD	120.01, 120.12, 120.42	Med 6	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	No	No	Yes
10.03	HWY 20 & POST OFFICE		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	C	No	No	Yes
10.04	EAST LAKE SCHOOL		Low	Yes	, F	No	No	N/A	No	N/A	No	N/A	Α	No	No	Yes
10.05	LAKE ST		Low					•		Under Constru		•				
10.06	RED & WHITE MARKET		Low	No	N/A	No	No	N/A	Yes	В	No	N/A	F	No	No	Yes
10.07	MATTRESS STORE		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	Yes
10.08	LAKEVIEW DR		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	No	No
10.09	BLUE FISH COVE		Low	Yes	C	No	Yes	В	No	N/A	No	N/A	В	No	No	Yes
10.10	INDIAN BEACH RESORT		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	В	No	No	Yes
10.11	GLENHAVEN DR		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	D	No	No	No
10.12	BRUNER DR		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
10.13	DRIFTWOOD LOUNGE	11.24	Low	Yes	Α	Yes	Yes	Α	No	N/A	No	N/A	С	No	No	No
10.14	LAUREL DELL AT RIVERA MOTEL	11.23	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	С	No	No	No
10.15	BELL RAY		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	No
10.16	LAKESHORE & HWY 20		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	No	No
10.17	LUCERNE ELEMENTARY SCHOOL		Low	Yes	Α	No	Yes	Α	Yes	В	No	N/A	Α	No	No	Yes
10.18	HWY 20 & 14TH		Low	Yes	С	No	Yes	С	No	N/A	No	N/A	В	No	No	No
10.19	TOWER MART		Low	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	В	Yes	No	Yes
10.20	AT MARYMOUNT COLLEGE AT 13TH		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	No	No
10.21	HWY 20 & 9TH		Med	No	N/A	No	No	N/A	Yes	В	No	N/A	D	No	No	Yes
10.22	HWY 20 & 5TH		Med	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
10.23	HWY 20 & 1ST ST		Med	Yes	D	No	No	N/A	Yes	В	Yes	В	С	Yes	Yes	Yes
10.24	THE HARBOR		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	No	Yes
10.25	NICE POST OFFICE		Med	No	N/A	No	No	N/A	Yes	В	No	N/A	D	No	No	Yes
10.26	NICE MARKET		Med	No	N/A	No	No	N/A	No	N/A	No	N/A	D	No	No	Yes
10.27	HINMAN PARK		Low	Yes	С	No	Yes	В	Yes	D	Yes	С	С	Yes	Yes	Yes
10.28	LAKEVIEW AVE		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	No	No
10.29	SENTRY MARKET	11.07, 70.03, 71.08	Med	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	Α	No	No	Yes
10.30	ROBINSONS CASINO	71.07, 70.04, 11.06	Med	Yes	Α	No	No	N/A	Yes	В	Yes	Α	В	Yes	Yes	Yes
10.31	RUNNING CREEK CASINO	11.05	Low	No	N/A	No	No	N/A	Yes	Α	Yes	В	В	Yes	No	Yes
10.32	UPPER LAKE HIGH SCHOOL		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	Yes	No
10.33	MAIN ST & HWY 20		Low	Yes	Α	Yes	Yes	Α	Yes	Α	Yes	Α	В	Yes	Yes	Yes
10.34	TURNOUT ACROSS FROM CHEVRON		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	Yes
10.35	LAKE COUNTY JAIL	11.02, 80.01, 81.21	Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	F	No	Yes	Yes
10.36	SUTTER LAKESIDE	11.01, 80.02, 81.20	Low	No	N/A	No	No	N/A	Yes	В	Yes	Α	Α	Yes	Yes	Yes

Table 5.11- Bus Stop Passenger Amenities -- Route 1 Eastbound

					Sign			Pole	В	Bench	S	helter				
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
11.01	SUTTER LAKESIDE	10.36, 80.02, 81.20	High 22	No	N/A	No	No	N/A	Yes	В	Yes	Α	Α	Yes	Yes	Yes
11.02	LAKE COUNTY JAIL	10.35, 80.01, 81.21	Low 1	Yes	В	No	Yes	Α	No	N/A	No	N/A	F	No	Yes	Yes
11.03	MAIN ST & HWY 20		Low 5	Yes	Α	Yes	Yes	Α	Yes	Α	No	N/A	В	No	Yes	Yes
11.04	UPPER LAKE HIGH SCHOOL		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	Yes	Yes
11.05	RUNNING CREEK CASINO	10.31	Med	No	N/A	No	No	N/A	Yes	Α	Yes	В	В	Yes	No	Yes
11.06	ROBINSONS CASINO	71.07, 70.04, 10.30	Med	Yes	Α	No	No	N/A	Yes	В	Yes	Α	В	Yes	Yes	Yes
11.07	SENTRY MARKET	10.29, 70.03, 71.08	Med	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	Α	No	No	Yes
11.08	COLLIER		Low	Yes	Α	N/A	Yes	Α	No	N/A	No	N/A	F	No	No	No
11.09	BAT HOUSE ACROSS FROM HINMAN PARK		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	F	No	No	No
11.10	MARINA GRILL		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	Yes	Yes	Yes
11.11	WORLD MARK-NICE POST OFFICE		Med	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	No	No	No
11.12	THE HARBOR		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	Yes	No	No
11.13	1ST ST & HWY 20		Med	No	N/A	N/A	No	N/A	No	N/A	No	N/A	С	No	No	No
11.14	2ND & HWY 20 BTWN XWALK & ALPINE PARK SIGN		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	Yes	Yes
11.15	5TH AND HWY 20 NEAR FIRE HYDRANT IN		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	D	No	No	Yes
11.16	FRONT OF THE WATER SERVICE COMPANY		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	Yes	Yes
11.17	9TH & HWY 20 LUCERNE HARBOR PARK		Low	Yes	В	No	Yes	F	Yes	В	No	N/A	D	No	No	Yes
11.18	13TH & COUNTRY CLUBMARYMONT COLLEGE		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	No	Yes
11.19	13TH & HWY 20 COMMUNITY GARDEN PARK		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	D	No	No	No
11.20	16TH & HWY 20 OLD MONUMENT SIGN		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	No	No	No
11.21	LAKESHORE & HWY 20		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	В	No	No	Yes
11.22	JUST BEFORE BELL RAY		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	В	No	No	Yes
11.23	LAUREL DELL AT RIVERA MOTEL	10.14	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	С	No	No	No
11.24	DRIFTWOOD LOUNGE	10.13	Low	Yes	Α	Yes	Yes	Α	No	N/A	No	N/A	С	No	No	No
11.25	BRUNER DR-GRAVEL PULL OUT-KONA TAYHEE		Low	No	N/A	N/a	No	N/A	No	N/A	No	N/A	Α	No	No	No
11.26	GLENHAVEN		Low	Yes	В	No	No	N/A	No	N/A	No	N/A	D	No	No	Yes
11.27	INDIAN BEACH RESORT		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	Yes
11.28	BLUE FISH COVE		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	В	No	No	Yes
11.29	LAKEVIEW		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	С	No	No	No
11.30	TOWER MART		Low	Yes	Α	No	Yes	Α	Yes	Α	No	N/A	В	No	No	Yes
11.31	THE BARN		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	No	Yes	Yes
11.32	LAKE ST		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	No	No
11.33	EAST LAKE SCHOOL		Low	Yes	В	No	No	N/A	No	N/A	No	N/A	В	No	No	Yes
11.34	HWY 20 BURGERS		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	С	No	No	Yes
11.35	KEYS BLVD		Low	Yes	В	No	No	N/A	Yes	D	No	N/A	D	No	No	Yes
11.36	ORCHARD SHORES		Low	Yes	Α	No	Yes	В	No	N/A	No	N/A	Α	Yes	Yes	Yes
11.37	WOODLAND COLLEGE	110.41, 120.02	Low	Yes	В	Yes	Yes	Α	Yes	В	Yes	A	В	Yes	Yes	Yes
		10.01, 30.01, 31.13, 40.01, 41.21,														
11.38	WALMART FOOD PLACE	100.01, 100.45, 110.01, 110.42,	High	Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
		120.01, 120.12, 120.42													1	

Table 5.20- Bus Stop Passenger Amenities -- Route 2 Southbound

					Sign			Pole	E	Bench	S	helter				
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
20.01	KITS CORNER	21.24, 40.05, 41.18, 50.01, 51.19	Low	No	N/A	No	No	N/A	Yes	D	Yes	F	Α	No	No	Yes
20.02	DIAMOND DUST		Low	No	N/A	No	No	N/A	No	N/A	Yes	D	Α	No	No	Yes
20.03	WILD CAT CANYON		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	No	No
20.04	SALMINA		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	No	No
20.05	ADMIRAL RD		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	No	No
20.06	MARIAH MEADOWS		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	No	No
20.07	LOCH LOMOND		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	No
20.08	HARRINGTON FLATS		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
20.09	HOBERGS RESORT		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	D	No	No	No
20.10	SUMMIT		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
20.11	HARDESTERS	21.12	Low	Yes	С	No	Yes	В	Yes	В	Yes	В	Α	Yes	Yes	Yes
20.12	TURNOUT ACROSS FROM GIFFORD SPRINGS		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	No
20.13	THE OLD TAVERN-MAPLE SHADOWS		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	No
20.14	TURNOUT AFTER WHISPERING PINES		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	No	Yes
20.15	ANDERSON SPRINGS RD		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	No	No
20.16	TURNOUT JUST PAST DRY CREEK		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
20.17	TURNOUT BY SANTA CLARA RD		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
20.18	MINI MALL-T&J AUTO PARTS		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	Yes
20.19	FIVE STAR TOWING		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	No	Yes
20.20	LAKESIDE APPLIANCE		Low	Yes	С	Yes	Yes	Α	No	N/A	No	N/A	D	Yes	Yes	No
20.21	TWIN PINE CASINO		Low	No	N/A	No	No	N/A	Yes	В	No	N/A	В	Yes	No	Yes
20.22	PERRYS DELI		Low	Yes	С	No	Yes	Α	No	N/A	No	N/A	С	No	Yes	No
20.23	CHARTER SCHOOL	30.09, 31.06	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	No
20.24	ARMSTRONG RD		Low	Yes	Α	No	Yes	Α	Yes	В	Yes	Α	F	Yes	Yes	Yes
20.25	TRI COUNTIES BANK		Low	Yes	Α	No	Yes	Α	Yes	В	Yes	Α	Α	Yes	Yes	Yes

Table 5.21- Bus Stop Passenger Amenities -- Route 2 Northbound

					Sign Blocked by			Pole	В	ench	S	helter				
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
21.01	HWY 29 & YOUNG ST		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	Yes	No
21.02	HWY 175 & MCKINLEY DR		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
21.03	MONTE VISTA COURT DR		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
21.04	U-TURN TO BUS STOP AT ROCK		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
21.05	JUST NORTH OF CASA GRANDE DR		Low	Yes	С	No	Yes	В	No	N/A	No	N/A	F	No	No	No
21.06	AUSTIN DR & SR 175		Low	Yes	D	No	Yes	С	No	N/A	No	N/A	F	No	No	Yes
21.07	WHISPERING PINES		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	No	Yes
21.08	WATER CO SIGN		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	No	Yes
21.09	GIFFORD SPRINGS		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	Yes
21.10	GOLF RD		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	No
21.11	TURNOUT ACROSS FROM FIRE DEPT		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	Yes
21.12	HARDESTERS	20.11	Low	Yes	С	No	Yes	В	Yes	В	Yes	В	Α	Yes	Yes	Yes
21.13	SUMMIT		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
21.14	SR 175 & ENTRANCE RD		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
21.15	HOBERGS RESORT		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
21.16	SR 175 & HARRINGTON FLATS		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
21.17	LOCH LOMOND		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	No	Yes
21.18	MARIAH MEADOWS		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	No	No
21.19	ADMIRAL RD		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	No	No
21.20	SALMINA		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	No	No
21.21	WILD CAT CANYON		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	No	No
21.22	DIAMOND DUST		Low	No	N/A	No	No	N/A	No	N/A	Yes	D	Α	No	No	No
21.23	RED HILLS RD		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	No	No
21.24	KITS CORNER	20.01, 40.05, 41.18, 50.01, 51.19	Low	No	N/A	No	No	N/A	Yes	D	Yes	F	Α	No	No	Yes

Table 5.30- Bus Stop Passenger Amenities -- Route 3 Southbound

					Sigr	1		Pole	E	Bench	S	helter				l
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
		11.38, 10.01, 31.13, 40.01, 41.21,														i
30.01	WALMART FOOD PLACE	100.01, 100.45, 110.01, 110.42,	High 15	Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
		120.01, 120.12, 120.42														i
30.02	JOBZONE	40.02, 100.37, 120.04	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	D	No	No	No
30.03	ACROSS FROM LAKE TRANSIT	40.03, 100.38, 120.05	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	No	No	No
30.04	TOWER MART- 53/29		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	Yes	Yes	Yes
30.05	TWIN LAKES	31.1	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	D	No	No	No
30.06	HIDDEN VALLEY WATER COMPANY	31.08	Low	No	N/A	No	No	N/A	Yes	В	Yes	В	В	Yes	Yes	Yes
30.07	MUG SHOTS- COYOTE VALLEY PHARM	31.09	Low	No	N/A	No	No	N/A	No	N/A	Yes	В	В	Yes	Yes	No
30.08	HWY 29 & YOUNG ST-TRI COUNTIES BANK		Low	Yes	Α	No	Yes	Α	Yes	В	Yes	Α	Α	Yes	Yes	Yes
30.09	CHARTER SCHOOL	20.23, 31.06	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	No
30.10	FIVE STAR TOWING		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	No	Yes
30.11	LAKE COUNTY APPLIANCE		Low	Yes	С	Yes	Yes	Α	No	N/A	No	N/A	D	Yes	Yes	No
30.12	TWIN PINES CASINO		Low	No	N/A	No	No	N/A	Yes	В	No	N/A	В	Yes	No	Yes
30.13	LINCOLN AVENUE BRIDGE (CALISTOGA)		Low	yes	Α	No	No	N/A	Yes	Α	Yes	Α	В	No	Yes	Yes
30.14	ST HELENA HOSPITAL	31.01		No	N/A	No	No	N/A	Yes	В	No	N/A	С	No	Yes	Yes

Table 5.31- Bus Stop Passenger Amenities -- Route 3 Northbound

					Sign	า		Pole	E	Bench	S	helter				
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
31.01	ST HELENA HOSPITAL	30.14	Low	No	N/A	No	No	N/A	Yes	В	No	N/A	С	No	Yes	Yes
31.02	LINCOLN AVENUE BRIDGE (CALISTOGA)		Med	yes	Α	No	No	N/A	Yes	Α	Yes	Α	В	No	Yes	Yes
31.03	TWIN PINES CASINO		Low	No	N/A	No	No	N/A	Yes	В	No	N/A	В	Yes	No	Yes
31.04	PERRYS DELI		Low	Yes	С	No	Yes	Α	No	N/A	No	N/A	С	No	Yes	No
31.05	ARMSTRONG RD		Low	Yes	Α	No	Yes	Α	Yes	В	Yes	Α	Α	Yes	Yes	Yes
31.06	CHARTER SCHOOL	20.23, 30.09	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	No
31.07	HARDESTERS		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	Yes	Yes	No
31.08	HIDDEN VALLEY WATER COMPANY	30.06	Low	No	N/A	No	No	N/A	Yes	В	Yes	В	В	Yes	Yes	Yes
31.09	MUG SHOTS- COYOTE VALLEY PHARM	30.07	Low	No	N/A	No	No	N/A	No	N/A	Yes	В	В	Yes	Yes	No
31.10	TWIN LAKES	30.05	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	D	No	No	No
31.11	HWY 53 & HWY 29 (FOSTER FREEZE)		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	Yes	No
31.12	LAKE TRANSIT YARD	41.2	Low	Yes	Α	No	Yes	В	Yes	Α	Yes	Α	F	Yes	Yes	Yes
		11.38, 30.01, 40.01, 10.01, 41.21,														
31.13	WALMART FOOD PLACE	100.01, 100.45, 110.01, 110.42,		Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
		120.01, 120.12, 120.41														

Table 5.40- Bus Stop Passenger Amenities -- Route 4 Westbound

					Sign	1		Pole	E	Bench	s	helter				
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
		11.38, 30.01, 31.13, 10.01, 41.21,						_								
40.01	WALMART FOOD PLACE	100.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.42	High 28	Yes	А	No	Yes	А	No	N/A	No	N/A	D	No	No	Yes
40.02	JOBZONE	30.02, 100.37, 120.04	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	D	No	No	No
40.03	ACROSS FROM LAKE TRANSIT	30.03, 100.38, 120.05	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	No	No	No
40.04	TOWER MART		Low	No	N/A	N/A	No	N/A	No	N/A	N/A	N/A	В	Yes	Yes	Yes
40.05	KITS CORNER	21.24, 20.01, 41.18, 50.01, 51.19	Med	No	N/A	No	No	N/A	Yes	D	Yes	F	Α	No	No	Yes
40.06	KELSEYVILLE AUTO WRECKERS		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	Α	No	No	No
40.07	STORE 24	41.16	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	No	No	No
40.08	GAS HILL		Low	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	Α	No	No	No
40.09	4TH & MAIN		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	No	No	No
40.10	PHARMACY		Low	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
40.11	ACROSS FROM KELSEYVILLE LUMBER		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	No	Yes
40.12	MENDO COLLEGE	50.16, 51.07, 80.27, 81.01	Low	No	N/A	No	No	N/A	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
40.13	ACROSS FROM ROTTEN ROBBIES		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	No	No
40.14	STATE FARM (ACROSS FROM KMART)		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	D	No	No	No
40.15	NURSERY & GROCERY OUTLET	50.12	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	Yes	No
40.16	BOWLING ALLEY	41.04, 50.13, 51.04	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	Yes	No
40.17	SAFEWAY	50.17, 71.09, 81.07	Low	Yes	В	No	Yes	Α	Yes	В	Yes	Α	F	Yes	Yes	Yes
40.18	9TH & MAIN	50.18, 80.17	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
40.19	3RD & MAIN	50.08, 50.19, 80.18		Yes	Α	No	Yes	Α	Yes	В	Yes	С	Α	Yes	Yes	Yes

Table 5.41- Bus Stop Passenger Amenities -- Route 4 Eastbound

					Sigr	1		Pole	В	ench	S	helter				
						Blocked by								Light at		ADA Access
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
41.01	3RD & MAIN	51.01, 70.01, 71.11, 81.05,	High 18	Yes	Α	No	Yes	Α	Yes	В	Yes	С	Α	Yes	Yes	Yes
41.02	MAIN & MARTIN	80.19	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	В	No	Yes	Yes
41.03	MAIN & D ST		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	F	No	Yes	Yes
41.04	BOWLING ALLEY	40.16, 50.13, 51.04	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	Yes	No
41.05	SOCIAL SECURITY	50.14, 51.05	Low	No	N/A	No	No	N/A	Yes	D	Yes	С	Α	No	Yes	Yes
41.06	TACO BELL BEFORE DRIVEWAY	50.15, 51.06	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	No	No	No
41.07	BRUNOS	51.08, 80.23	Med	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	Yes	No
41.08	GROCERY OUTLET	51.09, 80.24	Med	Yes	С	No	Yes	Α	Yes	D	Yes	С	С	No	Yes	Yes
41.09	HOSPICE	51.10, 110.18, 120.23	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	F	No	No	Yes
41.10	KMART		Med	Yes	Α	No	Yes	Α	No	N/A	Yes	D	Α	No	No	Yes
41.11	ROTTEN ROBBIES		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	D	No	Yes	No
41.12	KELSEYVILLE LUMBER		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	No	Yes
41.13	ACROSS FROM PHARMACY		Med	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
41.14	4TH & MAIN (WEST AMERICA BANK)		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	F	No	Yes	No
41.15	BEFORE LIVE OAK		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	В	No	No	No
41.16	STORE 24	40.07	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	No	No	No
41.17	ACROSS FROM KELSEYVILLE WRECKERS		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	Α	No	No	No
41.18	KITS CORNER	21.24, 40.05, 20.01, 50.01, 51.19	Low	No	N/A	No	No	N/A	Yes	D	Yes	F	Α	No	No	Yes
41.19	HWY 29 & HWY 53- FOSTERS		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	D	No	Yes	Yes
41.20	LAKE TRANSIT YARD	31.12	Low	Yes	Α	No	Yes	В	Yes	Α	Yes	Α	F	Yes	Yes	Yes
41.21	WALMART FOOD PLACE	11.38, 30.01, 31.13, 40.01, 10.01, 100.01, 100.01, 100.45, 110.01, 110.42, 120.01, 120.12, 120.42		Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes

Table 5.50- Bus Stop Passenger Amenities -- Route 4A Westbound

					Sign			Pole	В	ench	S	helter				
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
50.01	KITS CORNER	21.24, 40.05, 20.01, 41.18, 51.19	Low	No	N/A	No	No	N/A	Yes	D	Yes	F	Α	No	No	Yes
50.02	RIVIERA SHOPPING CENTER		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	No	No
50.03	BAYVIEW ESTATES		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	F	No	No	No
50.04	MONTEZUMA WAY		Low	Yes	С	No	Yes	В	No	N/A	No	N/A	Α	No	No	No
50.05	RIVIERA WEST		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	Α	No	No	No
50.06	BUCKINGHAM		Low	Yes	С	No	Yes	Α	No	N/A	No	N/A	F	No	No	Yes
50.07	SODA BAY STORE		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	D	No	No	No
50.08	3RD & MAIN	40.19, 50.19, 80.18	Low	Yes	Α	No	Yes	Α	Yes	В	Yes	С	Α	Yes	Yes	Yes
50.09	FINLEY POST OFFICE		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	No	No
50.10	KONOCTI VISTA CASINO	51.13	Low	Yes	В	No	Yes	В	No	N/A	Yes	Α	Α	Yes	No	Yes
50.11	KMART		Low	Yes	В	No	Yes	Α	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
50.12	NURSERY & GROCERY OUTLET	40.15	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	С	No	Yes	No
50.13	BOWLING ALLEY	41.04, 40.16, 51.04	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	Yes	No
50.14	SOCIAL SECURITY	41.05, 51.05	Low	No	N/A	N/A	No	N/A	Yes	D	Yes	В	В	No	Yes	Yes
50.15	TACO BELL BEFORE DRIVEWAY	41.06, 51.06	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	No	No	No
50.16	MENDO COLLEGE	40.12, 51.07, 80.27, 81.01	Low	No	N/A	No	No	N/A	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
50.17	SAFEWAY	40.17, 71.09, 81.07	Low	Yes	В	No	Yes	Α	Yes	В	Yes	Α	F	Yes	Yes	Yes
50.18	9TH & MAIN	40.18, 80.17	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
50.19	3RD & MAIN	50.08, 40.19, 80.18		Yes	Α	No	Yes	Α	Yes	В	Yes	С	Α	Yes	Yes	Yes

Table 5.51- Bus Stop Passenger Amenities -- Route 4A Eastbound

					Sign	1		Pole	Е	Bench	S	helter				
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
51.01	3RD & MAIN	41.01, 70.01, 71.11, 81.05	Low	Yes	Α	No	Yes	Α	Yes	В	Yes	С	Α	Yes	Yes	Yes
51.02	MAIN & D ST		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	F	No	Yes	Yes
51.03	D STREET		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	F	No	Yes	Yes
51.04	BOWLING ALLEY	41.04, 40.16, 50.13	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	F	No	Yes	No
51.05	SOCIAL SECURITY	41.05, 50.14	Low	No	N/A	N/A	No	N/A	Yes	D	Yes	В	В	No	Yes	Yes
51.06	TACO BELL BEFORE DRIVEWAY	41.06, 50.15	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	No	No	No
51.07	MENDO COLLEGE	50.16, 40.12, 80.27, 81.01	Low	No	N/A	No	No	N/A	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
51.08	BRUNOS	41.07, 80.23	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	Yes	No
51.09	GROCERY OUTLET	41.08, 80.24	Low	Yes	С	No	Yes	Α	Yes	D	Yes	С	С	No	Yes	Yes
51.10	HOSPICE	41.09, 110.18, 120.23	Low	Yes	Α	No	Yes	Α	No	N/A	Yes	D	Α	No	No	Yes
51.11	KMART	80.25	Low	Yes	В	No	Yes	Α	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
51.12	ROTTEN ROBBIES	80.26	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	Yes	No
51.13	KONOCTI VISTA CASINO	50.10	Low	Yes	В	No	Yes	В	No	N/A	Yes	Α	Α	Yes	No	Yes
51.14	FINLEY POST OFFICE		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	No	No
51.15	SODA BAY STORE		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	D	Yes	No	No
51.16	RIVERA WEST		Low	Yes	С	No	Yes	В	Yes	В	Yes	D	С	No	No	No
51.17	MONTEZUMA WAY		Low	Yes	В	No	No	N/A	No	N/A	No	N/A	F	No	No	No
51.18	RIVERA SHOPPING CENTER		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	F	No	No	No
51.19	KITS CORNER	21.24, 40.05, 20.01, 50.01, 41.18		No	N/A	No	No	N/A	Yes	D	Yes	F	Α	No	No	Yes

Table 5.70- Bus Stop Passenger Amenities -- Route 7 Westbound

					Sign			Pole	Е	Bench	S	helter				i
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
70.01	3RD & MAIN	51.01, 41.01, 71.11, 81.05	Med	Yes	Α	No	Yes	Α	Yes	В	Yes	С	Α	Yes	Yes	Yes
70.02	9TH & MAIN (NATURAL HIGH)	71.10, 81.06	Low	Yes	В	No	Yes	В	No	N/A	No	N/A	Α	No	Yes	Yes
70.03	SENTRY MARKET	11.07, 10.29, 71.08	Low	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	Α	No	No	Yes
70.04	ROBINSONS CASINO	71.07, 10.30, 11.06	Low	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	В	Yes	Yes	Yes
70.05	1ST & MAIN UPPER LAKE	71.06	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	Α	Yes	Yes	Yes
70.06	BLUE LAKES		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	Yes	Yes
70.07	MENDOCINO COLLEGE UKIAH	71.04	Low	No	N/A	No	No	N/A	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
70.08	PEAR TREE	71.03	Low	Yes	Α	No	No	N/A	Yes	Α	No	N/A	Α	No	Yes	Yes
70.09	VETERANS CLINIC	71.02	Low	No	N/A	No	No	N/A	Yes	Α	Yes	В	С	no	Yes	Yes
70.1	AIRPORT	71.01		Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	В	no	Yes	Yes

Table 5.71- Bus Stop Passenger Amenities -- Route 7 Eastbound

					Sigr	1		Pole	E	Bench	S	helter				
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
71.01	AIRPORT	70.1	Low	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	В	no	Yes	Yes
71.02	VETERANS CLINIC-UKIAH	70.09	Low	No	N/A	No	No	N/A	Yes	Α	Yes	В	С	no	Yes	Yes
71.03	PEAR TREE	70.08	Low	Yes	Α	No	No	N/A	Yes	Α	No	N/A	Α	No	Yes	Yes
71.04	MENDOCINO COLLEGE UKIAH	70.07	Low	No	N/A	No	No	N/A	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
71.05	BLUE LAKES		Low	No	N/A	No	No	N/A	Yes	Α	Yes	В	С	no	yes	No
71.06	1ST & MAIN UPPER LAKE	70.05	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	Α	Yes	Yes	Yes
71.07	ROBINSONS CASINO	70.04, 10.30, 11.06	Low	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	В	Yes	Yes	Yes
71.08	SENTRY MARKET	11.07, 10.29, 70.03	Low	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	Α	No	No	Yes
71.09	SAFEWAY	40.17, 50.17, 81.07	Low	Yes	В	No	Yes	Α	Yes	В	Yes	Α	F	Yes	Yes	Yes
71.10	9TH & MAIN (NATURAL HIGH)	70.02, 81.06	Low	Yes	В	No	Yes	В	No	N/A	No	N/A	Α	No	Yes	Yes
71.11	3RD & MAIN	51.01, 70.01, 41.01, 81.05		Yes	Α	No	Yes	Α	Yes	В	Yes	С	Α	Yes	Yes	Yes
	•	•	•	•			•		•					-		

Table 5.80- Bus Stop Passenger Amenities -- Route 8 Southbound

					Sign			Pole	Е	Bench	S	helter				
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
80.01	LAKE COUNTY JAIL	11.02, 10.35, 81.21	Low 2	Yes	Α	No	Yes	Α	No	N/A	No	N/A	F	No	Yes	Yes
80.02	SUTTER LAKESIDE	11.01, 10.36, 81.20	High 30	No	N/A	No	No	N/A	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
80.03	LAKESIDE HEALTH CLINIC	81.19	Low 1	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	Yes	No
80.04	NORTHPORT MOBILE HOME PARK	81.18	Low	Yes	С	No	Yes	В	No	N/A	No	N/A	F	No	Yes	No
80.05	EL DORADO MOTEL		Low	Yes	D	No	Yes	Α	No	N/A	No	N/A	F	Yes	No	No
80.06	PEOPLE SERVICES-WALNUT DR		Low	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	Α	No	No	Yes
80.07	ELKS LODGE		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	F	No	No	No
80.08	RAINBOW MOBILE HOME PARK		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	F	No	No	No
80.09	PARK WAY		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	No
80.10	TOWER MART		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	No
80.11	CRYSTAL LAKE DR		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	F	No	No	No
80.12	BEACH LN-RAINBOW LODGE		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	F	No	No	No
80.13	LAKESHORE & LANGE		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	В	No	No	No
80.14	HIGH ST		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	В	No	Yes	Yes
80.15	LIBRARY		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	С	No	Yes	Yes
80.16	N.FORBES ST		Low	Yes	С	No	Yes	F	No	N/A	No	N/A	D	No	Yes	Yes
80.17	9TH & MAIN	50.18, 40.18	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
80.18	3RD & MAIN	50.08, 50.19, 40.19	Low	Yes	Α	No	Yes	Α	Yes	В	Yes	С	Α	Yes	Yes	Yes
80.19	MAIN & MARTIN	41.02	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	В	No	Yes	Yes
80.2	STARR & MARTIN (BELLA VISTA)		Low	Yes	С	No	Yes	Α	No	N/A	No	N/A	Α	Yes	No	Yes
80.21	TRIBAL HEALTH		Low	No	N/A	N/A	No	N/A	Yes	Α	Yes	Α	Α	No	Yes	Yes
80.22	BEVINS ACROSS FROM WIC		Low	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
80.23	BRUNOS	41.07, 51.08	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	Α	No	Yes	No
80.24	GROCERY OUTLET	41.08, 51.09	Low	Yes	С	No	Yes	Α	Yes	D	Yes	С	С	No	Yes	Yes
80.25	KMART	51.11	Low	Yes	В	No	Yes	Α	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
80.26	ROTTEN ROBBIES	51.12	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	Yes	No
80.27	MENDO COLLEGE	50.16, 51.07, 40.12, 81.01		No	N/A	No	No	N/A	Yes	Α	Yes	Α	Α	Yes	Yes	Yes

Table 5.81- Bus Stop Passenger Amenities -- Route 8 Northbound

					Sigr	1		Pole	E	Bench	S	helter				
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
81.01	MENDO COLLEGE	40.12, 50.16, 51.07, 80.27	Med 9	No	N/A	No	No	N/A	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
81.02	AAA		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	С	No	Yes	Yes
81.03	SENIOR CENTER	110.24, 120.30	Med	No	N/A	N/A	No	N/A	No	N/A	Yes	С	В	No	No	Yes
81.04	MARTIN ST (BELLA VISTA)		Low 4	No	N/A	No	No	N/A	Yes	Α	Yes	Α	Α	No	No	Yes
81.05	3RD & MAIN	51.01, 41.01, 71.11, 70.01	High 31	Yes	Α	No	Yes	Α	Yes	В	Yes	С	Α	Yes	Yes	Yes
81.06	9TH & MAIN (NATURAL HIGH)	71.10, 70.02	Low	Yes	В	No	Yes	В	No	N/A	No	N/A	Α	No	Yes	Yes
81.07	SAFEWAY	40.17, 50.17, 71.09	Med	Yes	В	No	Yes	Α	Yes	В	Yes	Α	F	Yes	Yes	Yes
81.08	VIA DEL LAGO		Low	Yes	Α	No	Yes	В	No	N/A	No	N/A	В	No	Yes	No
81.09	LAKESHORE & LANGE		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	В	No	No	No
81.10	BEACH LN-RAINBOW LODGE		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	No	No	No
81.11	THE CHEATEU		Low	Yes	В	Yes	Yes	В	No	N/A	No	N/A	Α	No	Yes	No
81.12	TOWER MART		Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	No	Yes
81.13	PARK WAY		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	D	No	No	No
81.14	ACROSS FROM RAINBOW MOBILE HOME		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	Α	No	No	No
81.15	ROCKY POINT		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	В	No	No	No
81.16	ACROSS FROM PEOPLE SERVICES		Low	Yes	Α	No	Yes	Α	Yes	Α	Yes	Α	В	No	No	Yes
81.17	ACROSS FROM PERKS MOBILE HOME		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	D	No	No	No
81.18	NORTHPORT MOBILE HOME PARK	80.04	Low	Yes	С	No	Yes	В	No	N/A	No	N/A	F	No	Yes	No
81.19	LAKESIDE HEALTH CLINIC	80.03	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	В	No	Yes	No
81.20	SUTTER LAKESIDE	11.01, 10.36, 80.02	Low	No	N/A	No	No	N/A	Yes	Α	Yes	Α	Α	Yes	Yes	Yes
81.21	LAKE COUNTY JAIL	11.02, 10.35, 80.01	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	F	No	Yes	Yes

Table C-5

Table 5.100- Bus Stop Passenger Amenities -- Route 10

					Sign	1		Pole	E	ench	S	helter				
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
		11.38, 30.01, 31.13, 40.01, 41.21,														
100.01	WALMART FOOD PLACE	10.01, 100.45, 110.01, 110.42,	High 76	Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
		120.01, 120.12, 120.42														
100.02	CLEARLAKE APTS	120.13	Med	Yes	В	No	Yes	Α	No	N/A	Yes	A	D	No	No	Yes
100.03	J&L MARKET	120.14	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	F	No	No	No
100.04	CROSSROADS CHURCH	120.15	Low	No	N/A	N/A	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
100.05	CYPRESS	120.16	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	No	No	No
100.06	MENDO MILL		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	No	No	No
100.07	OLD HWY 53 & LAKESHORE		Med	Yes	Α	No	Yes	Α	No	N/A	No	N/A	Α	No	No	No
100.08	OLD RED CROSS (OPPOSITE HILLCREST)		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	Α	No	No	No
100.09	HILL AVE		Low	Yes	В	No	Yes	С	No	N/A	No	N/A	Α	No	No	No
100.10	RIDGE LAKE APTS-COMMONS		Med	Yes	Α	No	Yes	В	Yes	В	Yes	С	В	No	Yes	Yes
100.11	BURNS VALLEY MALL		High	Yes	В	No	Yes	F	No	N/A	No	N/A	Α	No	No	No
100.12	CLEARLAKE POST OFFICE		Med	Yes	D	No	Yes	В	No	N/A	No	N/A	F	Yes	Yes	Yes
100.13	BABY STORE (ACROSS FROM LOCUST)		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	No	No
100.14	CITY HALL		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	F	No	Yes	Yes
100.15	OLD BOWLING ALLEY		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	F	Yes	No	Yes
100.16	POMO & WOODLAND		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	С	No	No	No
100.17	BOXWOOD & ARROWHEAD		Med	Yes	Α	No	Yes	Α	No	N/A	No	N/A	В	No	No	No
100.18	TOYON		Low	Yes	D	No	Yes	Α	No	N/A	No	N/A	D	No	No	No
100.19	MODOC		Low	Yes	Α	No	Yes	С	No	N/A	No	N/A	D	Yes	No	Yes
100.20	2ND ST (HALFWAY DOWN BLOCK)		Low	Yes	Α	Yes	Yes	В	No	N/A	No	N/A	В	No	No	No
100.21	2ND & BUSH		Med	Yes	В	No	Yes	В	Yes	В	No	N/A	В	No	No	No
100.22	8TH & BUSH		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	F	No	No	No
100.23	11TH & BUSH		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	No	No	No
100.24	13TH & COUNTRY CLUB		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	No	No
100.25	COUNTRY CLUB& ARROWHEAD		Low	Yes	В	, No	Yes	A	Yes	Ċ	No	N/A	С	No	No	No
100.26	CLEARLAKE PARK POST OFFICE		Low	Yes	В	Yes	Yes	A	No	N/A	No	N/A	В	Yes	Yes	Yes
100.27	AMERICAS BEST VALUE INN		Med	No	N/A	N/A	No	N/A	No	N/A	No	N/A	C	No	Yes	No
100.28	LAKESHORE & POMO		Low	Yes	C	No	Yes	В	No	N/A	No	N/A	D	Yes	Yes	No
100.29	CITY HALL		Low	Yes	B	No	Yes	В	No	N/A	No	N/A	F	No	Yes	Yes
100.30	AUSTIN PARK		Low	Yes	C	No	Yes	A	Yes	В	No	N/A	D.	Yes	Yes	Yes
100.31	BAYLIS & LAKESHORE		Med	Yes	A	No	Yes	A	No	N/A	No	N/A	F	No	No	No
100.31	HIGHLANDS PARK (CASTLE DONUTS)		Low	Yes	B	No	Yes	Ä	No	N/A	No	N/A	, F	No	No	Yes
100.32	CATFISH COFFEE		Med	No	N/A	No	No	N/A	No	N/A	No	N/A	D.	No	Yes	No
100.34	VETERANS CLINIC	110.30	Med	No	N/A	N/A	No	N/A	Yes	A	Yes	A	B	Yes	Yes	Yes
100.34	VALERO	110.30	Low	No	N/A	N/A N/A	No	N/A N/A	No	N/A	No	N/A	D D	No	No	No
100.35	SOCIAL SERVICES	110.31	Low	No	N/A	N/A N/A	No	N/A N/A	No	N/A N/A	Yes	B IN/A	ר	No	Yes	No No
100.36	JOBZONE	40.02.20.02.120.04				· ·		N/A N/A		-			D			
		40.02, 30.02, 120.04	Low	No No	N/A	No N/A	No	· ·	No No	N/A	No No	N/A N/A	В В	No No	No No	No No
100.38	ACROSS FROM LAKE TRANSIT	40.03, 30.03, 120.05	Low	No	N/A	N/A	No	N/A	No No	N/A	No No	N/A	D F	No	No	No No
100.39	HWY 53 & MAIN (DL'S PIZZA)	120.06	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	L L	Yes	Yes	No Yos
100.40	BETWEEN LAKE & 2ND ST LOWER LAKE HIGH SCHOOL	420.00	Med	Yes	, r	No	Yes	В	Yes	A	Yes	A	D	Yes	No	Yes
100.41		120.08	High	Yes	В	No	Yes	Α	Yes	В	Yes	В	D	Yes	No	Yes
100.42	CEMETERY	120.09	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	С	No	No	Yes
100.43	BRYANT RD	120.10	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	No	No	Yes
100.44	CACHE CREEK APTS	120.11	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	В	Yes	Yes	Yes
		11.38, 30.01, 31.13, 40.01, 41.21,														
100.45	WALMART FOOD PLACE	100.01, 10.01, 110.01, 110.42,		Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
		120.01, 120.12, 120.42														

Table 5.110- Bus Stop Passenger Amenities -- Route 11

					Sign	1		Pole	В	ench	S	helter				
						Blocked by								Light at		ADA Access-
Bus Stop ID	Bus Stop Name	Repeats	Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
		11.38, 30.01, 31.13, 40.01, 41.21,														
110.01	WALMART FOOD PLACE	100.01, 100.45, 10.01, 110.42, 120.01, 120.12, 120.42	High 76	Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
110.02	ST.HELENA CLEARLAKE		Low 2	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	Yes	No	Yes
110.03	IRVING & 18TH		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	Α	No	No	No
110.04	BOYLES & 18TH		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	В	No	No	No
110.05	BOYLES & 25TH		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	С	No	No	No
110.06	BOYLES BETWEEN 30TH & 31ST		Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	В	No	No	No
110.07	33RD & PHILLIPS		Low	Yes	С	No	Yes	В	No	N/A	No	N/A	В	No	No	No
110.08	36TH & PHILLIPS		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	С	No	No	No
110.09	PHILLIPS & 40TH (40TH STORE)		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	F	No	No	No
110.10	45TH -THE DUMP DAVIS ST		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	F	No	No	No
110.11	MOSS (FIRST DRIVE WAY)		Low	Yes	С	No	Yes	В	No	N/A	No	N/A	В	No	No	No
110.12	WEST AMERICA BANK		Med	Yes	В	No	Yes	В	No	N/A	No	N/A	F	No	Yes	No
110.13	CLEARLAKE FAMILY CLINIC		Med	No	N/A	N/A	No	N/A	No	N/A	Yes	Α	В	No	No	No
110.14	NAPA AUTO PARTS	120.19	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	В	No	No	Yes
110.15	NOTT'S LIQUOR		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	No	No	Yes
110.16	CATFISH COFFEE	120.21	Med	Yes	В	No	Yes	Α	No	N/A	No	N/A	С	No	Yes	No
110.17	BURGER TIME	120.22	Low	Yes	В	No	Yes	Α	No	N/A	No	N/A	В	No	No	No
110.18	HOSPICE	51.10, 41.09, 120.23	Med	Yes	Α	No	Yes	Α	No	N/A	Yes	D	Α	No	No	Yes
110.19	OLD FIREHOUSE	120.24	Low	Yes	Α	No	Yes	Α	No	N/A	No	N/A	F	No	No	No
110.20	AUSTIN PARK	120.25	Low	Yes	В	No	Yes	Α	Yes	В	No	N/A	С	Yes	Yes	No
110.21	HAVERTY FIELD	120.26	Low	Yes	D	No	Yes	Α	No	N/A	No	N/A	F	No	No	No
110.22	CLEARLAKE POST OFFICE	120.27	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	Yes	Yes	No
110.23	BURNS VALLEY MALL		Low	Yes	В	No	Yes	F	No	N/A	No	N/A	Α	No	No	No
110.24	SENIOR CENTER	81.03, 120.30	Med 8	No	N/A	N/A	No	N/A	No	N/A	Yes	С	В	No	No	Yes
110.25	WALNUT GROVE APTS	120.31	Low	No	N/A	N/A	No	N/A	Yes	В	Yes	В	В	Yes	Yes	Yes
110.26	SAFEWAY	120.32	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	No	Yes	Yes
110.27	OLD HWY 53 PAST RITE AID	120.33	Low	Yes	Α	Yes	Yes	Α	No	N/A	No	N/A	D	No	No	No
110.28	HIGHLANDS WAY	120.34	Low	Yes	В	No	Yes	В	No	N/A	No	N/A	С	No	No	No
110.29	HILLCREST	120.35	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	D	No	No	No
110.30	VETERANS CLINIC	100.34	Low	No	N/A	N/A	No	N/A	Yes	Α	Yes	Α	В	Yes	Yes	Yes
110.31	VALERO	100.35	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	No	No	No
110.32	MOSS & DAVIS (BEFORE 35 MPH SIGN)		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	No	No
110.33	PHILLIPS & 44TH		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	В	No	No	Yes
110.34	PHILLIPS & 39TH		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	No	Yes
110.35	32ND & PHILLIPS		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	В	No	No	No
110.36	BOYLES & 29TH		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	Α	No	No	Yes
110.37	BETWEEN 26TH & 25TH		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	No	No	Yes
110.38	BOYLES AND 21ST		Low	Yes	D	Yes	Yes	В	No	N/A	No	N/A	В	No	No	No
110.39	IRVING & 18TH		Low	Yes	В	Yes	Yes	В	No	N/A	No	N/A	Α	No	No	No
110.40	ST.HELENA CLEARLAKE		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	No	No	Yes
110.41	WOODLAND COLLEGE	11.37, 120.02	Med 8	Yes	B	Yes	Yes	A	Yes	В	Yes	A	В	Yes	Yes	Yes
110.11		10.01, 11.38, 30.01, 31.13, 40.01,	.,,,,,,			163		, ,	103		103	[1.03	103	
110.42	WALMART FOOD PLACE	41.21, 100.01, 100.45, 110.01,		Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
		120.01, 120.12, 120.42			'`			, ,		,,,		'','	_		.,,	
L	I .				1	I.	1	I.	1	1	1			1	1	

Table 5.120- Bus Stop Passenger Amenities -- Route 12

120.01 W 120.02 W 120.03 SG	Bus Stop Name WALMART FOOD PLACE	Repeats				Dia also al lass										
120.01 W 120.02 W 120.03 SG	·	Repeats				Blocked by								Light at		ADA Access-
120.02 W 120.03 SC	WALMART FOOD PLACE		Boardings	Y/N	Condition	Vegetation?	Y/N	Condition	Y/N	Condition	Y/N	Condition	Shade	Stop	Street Light	ible?
120.02 W 120.03 SC	WALMART FOOD PLACE	11.38, 30.01, 31.13, 40.01, 41.21,	54	.,			.,						_			.,
120.03 SC		100.01, 100.45, 110.01, 110.42,	High 54	Yes	A	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
120.03 SC	WOOD! AND COLLEGE	10.01, 120.12, 120.42	Low 2	Voc	В	Voc	Voc	_	Voc	В	Voc	^	В	Voc	Vos	Vos
	WOODLAND COLLEGE SOCIAL SERVICES	11.37, 110.41	Low 3 Low 4	Yes No	N/A	Yes N/A	Yes No	A N/A	Yes No	N/A	Yes	A B	C	Yes	Yes Yes	Yes
10004 110	JOBZONE	40.02.100.27.20.02	LOW 4		N/A	-	No	N/A		N/A N/A	Yes		D	No No		No No
	ACROSS FROM LAKE TRANSIT	40.02, 100.37, 30.02 40.03, 100.38, 30.03	Low	No No	N/A N/A	No N/A	No	N/A N/A	No No	N/A N/A	No No	N/A N/A	В	No No	No No	No No
	HWY 53 & MAIN (DL'S PIZZA)	100.39	Low	No	N/A	N/A N/A	No	N/A		N/A N/A	No	1.	F	Yes	Yes	
	BETWEEN LAKE ST & SECOND ST	100.59	Low	Yes	IN/A	No	Yes	B	No Yes	A	Yes	N/A A	D	Yes	No	No Yes
	LOWER LAKE HIGH SCHOOL	100.41	Med	Yes	B B	No	Yes	A	Yes	b	Yes	В	D	Yes	No	Yes
												_	U	162		
	CEMETERY	100.42	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	С	No	No	Yes
	BRYANT RD	100.43	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	No	No	Yes
120.11 CA	CACHE CREEK APTS	100.44	Low	Yes	A	No	Yes	A	No	N/A	No	N/A	В	Yes	Yes	Yes
		11.38, 30.01, 31.13, 40.01, 41.21,											_			
120.12 W	WALMART FOOD PLACE	100.01, 100.45, 110.01, 110.42,	1	Yes	A	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
120.12	CLEARLANE ARTS	120.01, 10.01, 120.42	Low	V		Na	Vaa		NI-	N1 / A	V		-	N	N.	Vaa
	CLEARLAKE APTS	100.02	Low	Yes	В	No	Yes	A	No	N/A	Yes	A N/A	D	No	No	Yes
	J&L MARKET	100.03	Low	Yes	A N/A	No N/A	Yes	A	No	N/A	No	N/A	r	No	No	No
	CROSSROADS CHURCH	100.04	Low	No	N/A	N/A	Yes	A N/A	No	N/A	No	N/A	D	No	No	Yes
	CYPRESS MANUSCO MALL (ACROSS THE STREET)	100.05	Low	No	N/A B	N/A	No	N/A	No	N/A B	No	N/A	В	No	No	No
	MENDO MILL (ACROSS THE STREET)		Low	Yes		Yes	Yes	В	Yes		Yes	D N/A	۸	Yes	No	Yes
	OLD HWY 53 & LAKESHORE NAPA AUTO PARTS	110.14	Low	Yes	A	No No	Yes	A	No	N/A	No	N/A	A B	No No	No	No
	NOTT'S LIQUOR	110.14	Low	Yes	A	No No	Yes	A	No	N/A	No	N/A	В	No	No No	Yes
	CATFISH COFFEE	110.16	Low Med	Yes	A	No No	Yes	A	No	N/A	No	N/A	6	No No	No	Yes
	BURGER TIME	110.16		Yes	D D	No No	Yes	A	No	N/A	No	N/A	В	No	Yes	No
	HOSPICE	41.09, 51.10, 110.18	Low Med	Yes Yes	A A	No No	Yes Yes	A A	No No	N/A N/A	No Yes	N/A D	A	No No	No No	No Yes
	OLD FIREHOUSE	110.19	Low	Yes	A	No	Yes	A	No	N/A N/A	No	N/A	F	No	No	No
	AUSTIN PARK	110.19	Low	Yes	A D	No	Yes	A	Yes	B N/A	No	N/A N/A	r	Yes	Yes	No
	HAVERTY FIELD	110.20	Low	Yes	D	No	Yes	A	No	N/A	No	N/A		No	No	No
	CLEARLAKE POST OFFICE	110.21	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	, E	Yes	Yes	No
	BURNS VALLEY MALL	110.22	Low	Yes	B	No	Yes	F	No	N/A	No	N/A	A	No	No	No
	B&G TIRES		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	F	No	Yes	No
	SENIOR CENTER	81.03, 110.24	Low	No	N/A	N/A	No	N/A	No	N/A	Yes	C	В	No	No	Yes
	SHELTER AT WALNUT GROVE APTS	110.25	Low	No	N/A	N/A	No	N/A	Yes	В	Yes	В	В	Yes	Yes	Yes
	SAFEWAY	110.26	Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	D	No	Yes	Yes
	OLD HWY 53 PAST RITE AID	110.27	Low	Yes	A	Yes	Yes	Α	No	N/A	No	N/A	D	No	No	No
	HIGHLANDS WAY	110.27	Low	Yes	B	No	Yes	В	No	N/A	No	N/A	C	No	No	No
	HILLCREST	110.29	Low	No	N/A	No	No	N/A	No	N/A	No	N/A	D	No	No	No
	BALLPARK-OLD HWY 53-LAKESHORE-TRAVELODGE	110.23	Low	Yes	A	No	Yes	В	No	N/A	No	N/A	C	No	No	No
	MENDO MILL		Low	Yes	В	Yes	Yes	В	Yes	В	Yes	D	Č	Yes	No	Yes
	KING FISHER		Low	No	N/A	N/A	No	N/A	No	N/A	No	N/A	В	Yes	No	No
	CEDAR VILLAGE APTS		Low	Yes	В	No	Yes	В	No	N/A	No	N/A	A	No	No	Yes
	HIGHLANDS APTS		Low	Yes	A	No	Yes	A	Yes	B	No	N/A N/A	В	No	No	Yes
	CLEARLAKE APTS		Low	Yes	B	No	Yes	Ä	Yes	В	No	N/A	A	No	No	Yes
120.71	OLLY WILL MILL FILL IS	10.01, 11.38, 30.01, 31.13, 40.01,	LOW	163		140	163		163		140	11/7	^	140	110	103
120.42 W	WALMART FOOD PLACE	41.21, 100.01, 100.45, 110.01,		Yes	Α	No	Yes	Α	No	N/A	No	N/A	D	No	No	Yes
		110.42, 120.01, 120.12			'`			'`		,,		'','	_	.,,		. 53

Table 6: Summary of Lake Transit Bus Stop Facility AmenitiesStops Within Lake County Only

	Bus Stop Signage										
	Present	t			Con	dition				Sign Blocked by	
Yes	No	Total	Α	В	С	D	F	Total		Vegetation	
153	153	306	46	77	21	7	1	152		14	
50%	50%	% of Total	30%	51%	14%	5%	1%	100%		9%	

Sign Mounting Pole									
Present Condition									
Yes	No	Total		Α	В	С	D	F	Total
147	159	306		79	59	4	0	5	147
48%	52%	% of Total		54%	40%	3%	0%	3%	100%

Bench									
Present Condition									
Yes	No	Total	Α	В	С	D	F	Total	
65	241	306	25	32	1	7	0	65	
21%	79%	% of Total	38%	49%	2%	11%	0%	100%	

	Shelter									
Present Condition										
Yes	No	Total	Α	В	С	D	F	Total		
58	248	306	32	12	7	6	1	58		
19%	81%	% of Total	55%	21%	12%	10%	2%	100%		

Shade								
			Con	dition				
	Α	В	С	D	F	Total		
	66	80	44	46	70	306		
	22%	26%	14%	15%	23%	100%		

Light at Bus Stop							
	Present	t					
Yes	No	Total					
64	242	306					
21%	79%	% of Total					

Street Lights							
	Present	:					
Yes	No	Total					
94	212	306					
31%	69%	% of Total					

	Wheelchair Accessible								
Yes	No	Total							
144	162	306							
47%	53%	% of Total							


Appendix D City of Clearlake Design and Construction Standards

DESIGN AND CONSTRUCTION STANDARDS




September, 1994 Revised June, 2012

City of Clearlake 14050 Olympic Drive Clearlake, CA 95422



4 4.11 0



NOTES:

- SEE SECTION A-A, SHEET 3.
 BUS BENCHES AND SHELTER SHALL BE LOCATED BEHIND THE SIDEWALK OR IN SUCH A MANNER THAT
 A MINIMUM 5' CLEAR SIDEWALK IS PROVIDED.
 DESIGN SHALL CONFORM TO THESE REQUIREMENTS, EXCEPT AS OTHERWISE APPROVED BY THE
 CITY ENGINEER.

SHEET 1 of 3



BUS STOP INTERSECTION AT

STD. NO.

223

SCALE: NONE


DRAWN: DRH

CHK: PWW


APPVD: JLW

DATE: JUN. 2012

Plot Date: Jun 18, 2012 at 11:53 am



100011111



SECTION A-A

NOTES:

- 1. EXPANSION JOINTS & SCORE MARKS TO MATCH EXISTING CURB, GUTTER, & SIDEWALK.
- 2. USE CLASS "A" P.C.C.
- 3. CONSTRUCT SUBDRAINS WHEN REQUIRED BY CITY ENGINEER.
- 4. REINFORCING STEEL REQUIRED IN CONC. #4 @ 12" O.C. EACH WAY, OR #5 @ 16" O.C. EACH WAY.
- 5. DESIGN SHALL CONFORM TO THESE REQUIREMENTS EXCEPT AS OTHERWISE APPROVED BY THE CITY ENGINEER.

SHEET 3 of 3

of PASSAGLAND CONTRACTOR



CONCRETE BUS PAD DETAIL

STD. NO.

223

SCALE: NONE DRAWN: DRH CHK: PWW APPVD: JLW DATE: JUN. 2012

Appendix E
Lake County Bus Stop Design Standards

SECTION A-A

NOTES:

- EXPANSION JOINTS SHALL MATCH EXISTING CURB, GUTTER, & SIDEWALK. SCORE MARKS SHALL BE AT 8' INTERVALS OR LESS.
- 2. USE CLASS "1" P.C.C. (6-SACK MIX) FOR BUS STOP SLAB.
- 3. CONSTRUCT SUB DRAINS WHEN REQUIRED BY D.P.W. DIRECTOR.
- 4. REINFORCING STEEL REQUIRED IN CONC. #4 @ 12" O.C. EACH WAY, OR #5 @ 16" O.C. EACH WAY.
- 5. DESIGN SHALL CONFORM TO THESE REQUIREMENTS EXCEPT AS OTHERWISE APPROVED BY THE D.P.W. DIRECTOR.

SHEET 1 OF 3





BUS STOP - SLAB DETAIL

STD. NO. **216-A**

SCALE: NONE | DRAWN: CLG | CHK: JLW, TEM | APPVD: GRS

DATE: JUNE 2004





D.P.W. DIRECTOR.

SHEET 2 OF 3



DRAWING FILE NAME:

BUS STOP - INTERSECTION LOCATIONS

STD. NO. 216-B

SCALE: NONE

DRAWN: CLG

CHK: JLW, TEM APPVD: GRS

DATE: JUNE 2004

Appendix F
Systemwide Recommended Improvements at Individual Bus Stops

100 March																	Reco	mmer	nded I	mprove	ments			
Decomposition Property Prop													Si	gn		Pole		Beno	ch	Shelter				
WALMART FOOD PLACE														e		e			Se	9	Trin	1		4
WALMART FOOD PLACE												•	>	plac	*	plac		≥	plac	× place	Vege		Bus	Imp
MAINT FLOOP FLACE	ID#	Bus Stop	1	2 3	4	4A	7 8	3 10	0 11	. 12	Stop Shared With	All Routes	Ne	Re	Š	Re	ι×	Š	Re	Re Ne	tatio	n Lighting	Pullout	t m
10.00 10.0											11.38, 30.01, 31.13, 40.01, 41.21,													
MORE	10.01	WALMART FOOD PLACE	Х	Х	X	Х		Х	(X	Х	100.01, 100.45, 110.01, 110.42,	High					Rep	lace	With	New 7	ransi	Center		
10.03 MAY 20 & POST OFFICE											120.01, 120.12, 120.42													
10.00 START SCHOOL	10.02	KEYS BLVD	Х									Med	Х		Χ			Х				Х		
1.005 MARS EST	10.03	HWY 20 & POST OFFICE	Х									Low	Х		Х									
10.00 10.0	L0.04	EAST LAKE SCHOOL	Х									Low		Х	Χ									
10.00 MATTERS STORE	10.05	LAKE ST	Х									Low												
10.08 LAKPIEW DR	10.06	RED & WHITE MARKET	Х									Low	Х		Χ									
10.09 BLUE FISH COVE	L0.07	MATTRESS STORE	Х									Low	Х		Χ									
10.10 INJAN BEACH RESORT	10.08		Х					Ι	\mathbf{I}			Low	Х		Х								Х	
10.11 GLEMAYEN DR	10.09											Low					Х							
MUNIFOR NAME NAME	10.10											Low					Х							
10.13 ALJANE DILA TAYLERA MOTEL																	Х							
10.14 LAJBEL DELLA FREVERA MOTEL X			_										Х		Х								Х	
SELERAY																							<u> </u>	
10.16 MASSHORE & HWY 20 X X X X X X X X X											11.23	Low											ļ	
UCERNE ELEMENTARY SCHOOL						Щ																	Х	
10.18 MWY 20 8.14TH													Х		Χ				ļ_			<u> </u>	<u> </u>	
10.19 TOWER MART					_																			4
10.20 AT MARYMOUNT COLLEGE AT 13TH																	Χ							
10.21 MWY 20 8 9TH																								
10.22 14WY 20 & 21TH																								
10.23 HWY 20 & 15T ST							_						Х		Χ							Х		
10.24 THE HABBOR							_		_									_						
10.25 NICE POST OFFICE							_							Х						Х				4
10.26 NICE MARKET							_		_									_						_
ILINIAN PARK					-		_		-															4
10.28 LAKEVIEW AVE					-		_		-				X		Х			Х				X		4
10.29 SENTRY MARKET						-	_		-	+			L.,			-	Х		Х	Х				_
10.30 ROBINSONS CASINO				_	-				-	-	11 07 70 02 71 00		X		Х									
10.31 RUNNING CREEK CASINO				_	-				-	-			-									Х		+-
10.32 UPPER LAKE HIGH SCHOOL				_	-	-+	^		-	+			F.,				_					-		+-
10.33 MAIN ST & HWY 20				_	-		_		-	-	11.05													+-
10.34 TURNOUT ACROSS FROM CHEVRON					-	$\vdash \vdash$	+	-	-	+			X	-	Х		 	-+			- v	-	-	
10.35 LAKE COUNTY JAIL				+	+	\vdash	+	-	+	+			~	-	v			-+			X	+	1	+
10.36 SUTTER LAKESIDE					+	\vdash	+	/	+	+	11 02 80 01 91 21		_ ^	-	۸		-+	+			+		1	+
1.03 MAIN ST & HWY 20				+	+	H			+	+			v	\vdash	×		- 	\dashv	— 	-	-	-	 	+
1.04 UPPER LAKE HIGH SCHOOL				+	+	\vdash	+	`	+	+	11.01, 00.02, 01.20				^		\dashv	-+			У	+	 	+
1.08 COLLIER				-	+	\vdash	+	+	+	+			Y	1	X	<u>_</u>	-	\dashv	-	-	+^	-		+
11.10 BAT HOUSE ACROSS FROM HINMAN PARK				_	+	\vdash	+	+	+	+		1	^	†	^	-	-+	-+	-+	-	+	+	 	+
1.10 MARINA GRILL				_	+	\vdash	+	+	+	+			-	\vdash		— h	x	-+		+	-	+	 	-
1.11 WORLD MARK-NICE POST OFFICE				+	+	\vdash	+	+	+	+			Y		×		^	-+			+	+	 	+
1.12 THE HARBOR				+	+	\vdash	+	+	+	+				 			-+	х	-	_	+	x	1	
1.13 1ST ST & HWY 20				-	+	H	+	+	+	+								^					1	
1.14 2ND & HWY 20 BETWEEN XWALK & ALPINE PARK SIGN X X X X X X X X X				+	+	H	+	+	+	+				\vdash		b		х	— h	-	+	х	†	+
1.15 STH AND HWY 20 NEAR FIRE HYDRANT IN X X X X X X X X X				\dashv	+	H	+	+	+	\vdash							- 		-f			 	х	+
1.16 FRONT OF THE WATER SERVICE COMPANY				\dashv	\top	\vdash	+	+	+	\vdash							=†	\neg	-t	_		1		T
1.17 9TH & HWY 20 LUCERNE HARBOR PARK X				\dashv	+	H	+	+	+	\vdash			_				- 	_	-f			1	<u> </u>	+
11.18 13TH & COUNTRY CLUB MARYMONT COLLEGE X Low X X X LOW 11.19 13TH & HWY 20 COMMUNITY GARDEN PARK X LOW LOW X X X X				\dashv	+	H	+	+	+	\vdash					^	х	- 	_	-f			1	<u> </u>	+
1.1.9 13TH & HWY 20 COMMUNITY GARDEN PARK X Low Low X				-	+	H	+	+	+	+			X		X	^		\dashv		_		1	1	+
				\dashv	+	H	+	+	+	\vdash							х	_	-f			1	<u> </u>	
					+	H	+	_	+	\Box			X		х		-	-	<u> </u>					+

																	Rec	omme	ended	Impr	oveme	ents			
													Si	gn		Pole		Ber	nch	Shel	lter				
					Rout	es Se	rved					Relative Ridership Over	~	Replace	~	Replace		>	Replace	~	Replace	Trim Vege-	Improve	Bus	AD Impr
ID# Bu	us Stop	1	2	3	4 4	A 7	8	10	11	12	Stop Shared With	All Routes	New	Rep	New	Rep	Ε̈́	New	Rep	New	Rep	tation	Lighting	Pullout	mei
11.22 JL	JST BEFORE BELL RAY	Χ										Low					Χ								
11.25 BF	RUNER DR-GRAVEL PULL OUT-KONA TAYHEE	Х										Low	Х		Х)
	LENHAVEN	Х										Low			Х									1	
11.27 IN	NDIAN BEACH RESORT	Х										Low	Х		Х									1	
11.28 BI	LUE FISH COVE	Х										Low					Χ							1	
11.29 LA	AKEVIEW	Х										Low	Х		Х									1	
11.30 TO	OWER MART	Х										Low												ſ	1
11.31 TH	HE BARN	Х										Low	Х		Х										T
	AKE ST	Х		_								Low	X		Х										
	AST LAKE SCHOOL	Х		_								Low			Х										1
	WY 20 BURGERS	X			\dashv	\dashv	+	1	1 1	\dashv		Low	Х		Х										+
	EYS BLVD	X	\vdash	\dashv	\dashv	+	+	1		-		Low	<u> </u>		X	\vdash			Х						t
	RCHARD SHORES	X	\vdash	\dashv	\dashv	+	+	1	Х	Х		Low	-		Ė	\vdash	Х		-						t
	VOODLAND COLLEGE	X	Х	\dashv	Х	х	+	\vdash			110.41, 120.02	Med										Х			+
	ITS CORNER	^	X	\dashv	^		+	1		-	21.24, 40.05, 41.18, 50.01, 51.19	Med	Х		Х				Х		Х	^	Х	i	+
	IAMOND DUST		X	\dashv	\dashv	+	+	1	H	-+	21.2 ., 40.03, 41.10, 30.01, 31.15	Low	X	\vdash	X	\vdash			^		X		^	—	+
	VILD CAT CANYON		X	\dashv	\dashv	+	+	1	H			Low	X	\vdash	X	\vdash					Α.			—	
	ALMINA	+	Х	-			+	1	H	-		Low	X		X									 	
	DMIRAL RD	+	X	-			+	1	H	-		Low	X		X									 	
	MARIAH MEADOWS	+	X	-+	-		+-	-	H			Low	X		X										
	OCH LOMOND	+	X	-+	-		+-	1	H			Low	X		X										
	ARRINGTON FLATS	+	X	+	-	+	+	+-	\vdash	-		Low	X		X										
	OBERGS RESORT	+	X	+	-	+	+	+-	\vdash	-			X		X										1
	UMMIT	+	X				+-	-	-			Low	X		X									├──	
		+	X				+-	-	-		24.42	Low	X		Х		٧.							├──	
	ARDESTERS	+					+-	-	-		21.12				· ·		Χ							├──	+
	URNOUT ACROSS FROM GIFFORD SPRINGS	\vdash	Х	-+		-	+-	-	-			Low	X		X										
	HE OLD TAVERN-MAPLE SHADOWS	\blacksquare	Х			_	_		-			Low	Х		Х									├	
	URNOUT PASSED THE LAST TURN OF WHISPERING PINES	\vdash	Х	-+		-	+-	-	-			Low	X		X										+
	NDERSON SPRINGS RD	\vdash	Х				4	-	┷			Low	Х		Х									Ь——	
	URNOUT JUST PAST DRY CREEK	\vdash	Х				4	-	┷			Low	Х		Х									Ь——	
	URNOUT BY SANTA CLARA RD	ш	Х	_	_	4	4	ļ	┷	_		Low	Х		Х									Ь——	
	1INI MALL-T&J AUTO PARTS	Ш	Х						$\sqcup \bot$			Low	Х		Х									└	↓
	IVE STAR TOWING	Ш	Х	4			4	1	\sqcup	_		Low	Х	1	Х	\sqcup									4—
	AKESIDE APPLIANCE	\vdash	Х	_	_		_		\sqcup			Low				Ш						Χ			
	WIN PINE CASINO	\vdash	Х		_		_					Low	Х		Х										₩
	ERRYS DELI	\vdash	Х	Х	_	_	4	1	\sqcup			Low				Ш								Х	
	HARTER SCHOOL	\vdash	Х	_	_	_	4	1	\sqcup		30.09, 31.06	Low	Х		Х	Ш									
	RMSTRONG RD		Х	4				1		_		Low	<u> </u>											—	1
	RI COUNTIES BANK		Х		_							Low												<u> </u>	
	WY 29 & YOUNG ST		Х						Щ			Low	Х		Х										
	WY 175 & MCKINLEY DR		Х						$\sqcup \downarrow$	_		Low	Х		Х										
	10NTE VISTA COURT DR		Х			_						Low	Х		Х										
	-TURN TO BUS STOP AT ROCK		Χ									Low	Х		Х										
	JST NORTH OF CASA GRANDE DR		Χ									Low					Χ								
	USTIN DR & SR 175		Χ									Low		Х			Х								
21.07 W	VHISPERING PINES		Χ									Low	Х		Х										
21.08 W	VATER CO SIGN		Χ									Low	Х		Х										
21.09 GI	IFFORD SPRINGS		Х									Low	Х		Х										T
	OLF RD		Х		T	1		1		T		Low	Х		Х										
	URNOUT ACROSS FROM FIRE DEPT		Х	T	1	\top		1		T		Low	X		Х									ſ	
	UMMIT	T	Х	T	\dashv	\top	1	1				Low	Х		Х									ſ	
	R 175 & ENTRANCE RD	+	Х		\dashv	\dashv	+	1	1 1	\dashv		Low	X		Х										
	OBERGS RESORT	\vdash	X	\dashv	-	+	+	1	H	-		Low	X	1	X	\vdash									
	R 175 & HARRINGTON FLATS	+	Х	-+	_	-	4—		-	_		LOW	X	1	_ ^										

Low

21.17 LOCH LOMOND

TABLE 1: Summary o	f Recommended Im	provements (6 Sheets)
--------------------	------------------	-----------------------

													_				Re	comm	ende	d Imp	rovem	ents			
													S	ign		Pole	•	Ве	nch	She	elter				
												Relative		e		e			e		e	Trim			ADA
					Rout							Ridership Over	>	Replace	>	Replace		>	Replace	lew	Replace	Vege-	Improve	Bus	Improve-
ID#	Bus Stop	1	2	3	4 4	A 7	7 8	10	11	12	Stop Shared With	All Routes	New	Re	New	Re	Ξ̈́	New	Re	Ne	Re	tation	Lighting	Pullout	ments
21.18	MARIAH MEADOWS		Х									Low	Х		Х										Х
21.19	ADMIRAL RD		Х									Low	Х		Х										Х
21.20	SALMINA		Х									Low	Х		Х										Х
21.21	WILD CAT CANYON		Х									Low	Х		Х										Х
21.22	DIAMOND DUST		Х									Low	Χ		Х						Х				Х
21.23	RED HILLS RD		Х									Low	Χ		Х										Х
30.02	JOB ZONE			Х	Х			Х		Χ	40.02, 100.37, 120.04	Low	Χ		Х									Х	Х
30.03	ACROSS FROM LAKE TRANSIT			Х	Х			Х		Χ	40.03, 100.38, 120.05	Low	Χ		Х										Х
30.04	TOWER MART- 53/29			Х								Low	Χ		Х										
30.05	TWIN LAKES			Х							31.1	Low	Χ		Х										Х
30.06	HIDDEN VALLEY WATER COMPANY			Х							31.08	Low	Х		Х										
30.07	MUG SHOTS- COYOTE VALLEY PHARM			Х							31.09	Low	Х		Х										Х
30.08	HWY 29 & YOUNG ST-TRI COUNTIES BANK			Х								Low													
30.10	FIVE STAR TOWING			Χ								Low	Х		Х										
30.11	LAKE COUNTY APPLIANCE			Χ								Low										Χ			Х
30.12	TWIN PINES CASINO			Χ								Low	Х		Х										
30.13	LINCOLN AVENUE BRIDGE			Χ								Low			Х										
	ST HELENA HOSPITAL			Χ							31.01	Low	Χ		Х										
31.02	LINCOLN AVENUE BRIDGE			Χ								Med			Х										
31.03	TWIN PINES CASINO			Х								Low	Χ		Х										
31.04	PERRYS DELI			Х								Low												Х	Х
31.05	ARMSTRONG RD			Х								Low													
31.07	HARDESTERS			Х								Low	Х		Х										Х
31.11	HWY 53 & HWY 29 (FOSTER FREEZE)			Х								Low	Х		Х										Х
31.12	LAKE TRANSIT YARD			Х	Х						41.2	Low					Х								
40.04	TOWER MART				Х							Low	Χ		Х										
40.06	KELSEYVILLE AUTO WRECKERS				Х							Low	Χ		Х										Х
	STORE 24				Х						41.16	Low	Χ		Х										Х
40.08	GAS HILL				Х							Low									Х				Х
40.09	4TH & MAIN				Х							Low	Χ		Х										Х
	PHARMACY				Х							Low													
40.11	ACROSS FROM KELSEYVILLE LUMBER				Х							Low	Х		Х										
40.12	MENDO COLLEGE					X	Х				50.16, 51.07, 80.27, 81.01	Low													
40.13	ACROSS FROM ROTTEN ROBBIES				Х							Low												Х	
40.14	STATE FARM (ACROSS FROM KMART)				Х							Low												Х	
	NURSERY & GROCERY OUTLET					X					50.12	Low												X	
	BOWLING ALLEY					Х					41.04, 50.13, 51.04	Low													
	SAFEWAY					X X	_	_			50.17, 50.18, 71.09, 81.07	Med													
	9TH & MAIN					Х	Х	_			50.19, 80.17	Low		<u> </u>	1					<u> </u>	<u> </u>				
40.19	3RD & MAIN					х	Х		Ш		50.08, 50.20, 80.18	Low		<u> </u>	1						<u> </u>				
	3RD & MAIN					х х	_	_			51.01, 70.01, 71.06, 81.05,	High		1_	1		1			1	<u> </u>				<u> </u>
	MAIN & MARTIN			_	Х		Х				80.19	Low		1_	1		1			1	<u> </u>				<u> </u>
	MAIN & D ST				Х							Low		1_	1		1			1	<u> </u>			X	ļ
	SOCIAL SECURITY					х					50.14, 51.05	Low	Х	1_	Х		1		Χ	1	<u> </u>				ļ
	TACO BELL BEFORE DRIVEWAY	_			_	Х	_	1	Ш	$\sqcup \downarrow$	50.15, 51.06	Low	Х	1	Х	1	1	1		1	<u> </u>				Х
	BRUNOS					Х	Х		Ш	<u> </u>	51.08, 80.23	Med	Х	1	Х	1	1	Х		1	<u> </u>				Х
	GROCERY OUTLET				_	Х	Х	_	Ш		51.09, 80.24	Med		1	1	1	<u> </u>		Х	1	Х			Х	
	HOSPICE	_			Х			Х	Ш	Χ	51.10, 110.18, 120.23	Low		1	1	1	<u> </u>				<u> </u>				
41.10	KMART	_			Х		_	1	Ш	$\sqcup \downarrow$		Med		1	1	1	1	Х		1	Х		Х		
41.11	ROTTEN ROBBIES				Х				Ш			Low	Х	1	Х	1	<u> </u>			1	<u> </u>			Х	Х
	KELSEYVILLE LUMBER	_			Х		_	1	Ш	$\sqcup \downarrow$		Low		1	1	1	1	1		1	<u> </u>				
	ACROSS FROM PHARMACY			_	Х	_ _						Med		<u> </u>	1					<u> </u>	<u> </u>				
	4TH & MAIN (WEST AMERICA BANK)	_			Х			1	Ш	$\sqcup \downarrow$		Low		1	1	1	<u> </u>				<u> </u>				
41.15	BEFORE LIVE OAK				Х							Low		1			1	1		1	<u> </u>				<u> </u>

TABLE 1: Summary of Recommended Improvements (6 Sheet	:s)

														Çi	ign		Pole			nch	I Impr She					
												Relative		3		1			Del		Jile		Trim			AD
					Rout	es Se	rvec	t				Ridership Over			ace		ace			ace		ace		Improve	Bus	Impr
ID#	Bus Stop	1	2	3	4 4				11	12	Stop Shared With	All Routes		New	Replace	Vew	Replac	.≚	New	Replace	New	Replace	Vege- tation			
1.19	HWY 29 & HWY 53- FOSTERS		T		Х		T					Low		Ī	T	_	Ī		_							1
0.02	RIVIERA SHOPPING CENTER					Х						Low	1	Х		Х)
0.03	BAYVIEW ESTATES					Х						Low	1					Х								
0.04	MONTEZUMA WAY					Х						Low	1					Х								
0.05	RIVIERA WEST					Х						Low	1					Х								
0.06	BUCKINGHAM					Х						Low	1													
0.07	SODA BAY STORE					Х						Low	1					Х								
0.09	FINLEY POST OFFICE					Х						Low	1	Х		Х										
0.10	KONOCTI VISTA CASINO					Х					51.13	Low	1					Х								
0.11	KMART					Х						Low	1													
1.02	MAIN & D ST					Х						Low	1													
1.03	D STREET		1		_	X	T	1	T	T		Low	1			t										t
1.11	KMART		1		_	X	Х		T	T	80.25	Low	1			1										1
1.12	ROTTEN ROBBIES		1			X	Х		T	T	80.26	Low	1			1										1
1.14	FINLEY POST OFFICE		1		_	X	T	1	T	T		Low	1			1										1
1.15	SODA BAY STORE		1			X	$^{+}$	+		\dagger		Low	1		1	1	1									1
1.16	RIVERA WEST		†	\Box		X	T	1		\Box		Low	1		1	1										1
1.17	MONTEZUMA WAY		†	\Box	_	X	T	1		\Box		Low	1		1	1										1
1.18	RIVERA SHOPPING CENTER		†	\Box	_	X	T	1		\Box		Low	1		1	1										1
0.02	9TH & MAIN (NATURAL HIGH)		†	\Box	-	^ >		1		T	71.10, 81.06	Low	1		1	1		Х								1
0.05	1ST & MAIN UPPER LAKE		†	\Box	\dashv	>		1		\Box	71.06	Low	1	Х	1	Х										1
0.06	BLUE LAKES		1		-)		+		\dagger	. =	Low	1	X	1	Х	1									1
0.07	MENDOCINO COLLEGE UKIAH		1		-)	_	+		\dagger	71.04	Low	1	X	1	X	1									1
0.08	PEAR TREE)	_		1		71.03	Low	1	<u> </u>		Х										
0.09	VETERANS CLINIC)	_		1		71.02	Low	1	Х		Х										
0.10	AIRPORT)			1		71.01	Low	1	<u> </u>												
1.05	BLUE LAKES)			1		, 1.01	Low	1	Х		Х										
0.03	LAKESIDE HEALTH CLINIC					Ť	. х		1		81.19	Low	1	X		X										
0.04	NORTHPORT MOBILE HOME PARK						X	_	1		81.18	Low	1	<u> </u>				Х								
0.05	EL DORADO MOTEL						X	_	1		01.10	Low	1		Х											
0.06	PEOPLE SERVICES-WALNUT DR		+			_	X					Low	1													
0.07	ELKS LODGE		+			_	X	_				Low	1													
0.08	RAINBOW MOBILE HOME PARK		+			_	X					Low	1													
0.09	PARK WAY		+			-	X	_	1			Low	1	Х		Х										
0.10	TOWER MART		+			-	X	_	1			Low	1	X		X										
0.11	CRYSTAL LAKE DR		+			_	X					Low	1													
0.12	BEACH LN-RAINBOW LODGE		+	\vdash	\dashv	+	X		\vdash	+		Low	1	\vdash	1	1		Х			H					
0.12	LAKESHORE & LANGE		1		\dashv	+	X			+		Low	1	-	1		1	X								
0.14	HIGH ST VILLAGE		1		-+	-	X	_		+		Low	1	-	1		1	^							х	
0.15	LIBRARY		+	\vdash	\dashv	+	X	_	\vdash	+		Low	1	\vdash	1	1					H				X	1
0.16	N.FORBES ST		1		-+	-	X	_		+		Low	1	-	1		Х								<u> </u>	1
0.20	STARR & MARTIN (BELLA VISTA)		1		-+	-	X	_		+		Low	1	-	1											1
0.20	TRIBAL HEALTH		+	\vdash	-+	+	T _X		H	+		Low	1	Х	1	Х	1	1	1	1	\vdash				 	1
0.21	BEVINS ACROSS FROM WIC		+	\vdash	-+	+	X	_	H	+		Low	1		1	+^	1	1	1	1	\vdash				 	1
1.02	AAA		1		-+	-	X			+		Low	1	Х	1	Х	1									
1.03	SENIOR CENTER		1		-+	-	X	_		Х	110.24, 120.30	Med	1	X	1	X	1		Х					Х		1
1.03	MARTIN ST (BELLA VISTA)		+	\vdash	-+	+	X	_	H	<u> </u>	210.27, 120.30	Low	1	X	1	X	1	1	_	1	\vdash			^	 	1
1.04	VIA DEL LAGO		+	\vdash	-+	+	X		H	+		Low	1		1	+^	1	Х	1	1	\vdash				х	
1.08	LAKESHORE & LANGE		+	\vdash	-	+	X	_		+		Low	ł	\vdash	1	1	1	X			\vdash				^	
1.10	BEACH LN-RAINBOW LODGE		+	\vdash	+	+	X		1	+		Low	1	Х	1	Х		^			\vdash				-	
1.11	THE CHATEAU		+	\vdash	+	+	X	_	1	+		Low	1	^	1	_^		Х			\vdash		Х		-	
1.11	TOWER MART		+	\vdash	+	+	X	_	\vdash	+		Low	1	Х	1	Х	1	_^	 	-	\vdash		٨		1	1-
1.12	PARK WAY		+-	\vdash	-	-	X		1	+		Low	1	^	1	+^	1		-		\vdash					
1.13	ACROSS FROM RAINBOW MOBILE HOME		+-	\vdash		_	X		1	+			ł	<u> </u>	1	1-	1	-	<u> </u>	-	\vdash	\vdash			 	
1.14	INCLUSS LYCINI KAIINROM MORITE HOIME	1	1	i l		1	l X	١.	1	1 1		Low	1	i	1	1	i	l	l	l				ı		1

TABLE 1: Summary o	f Recommended Im	provements	(6 Sheets)
--------------------	------------------	------------	------------

														Si	ign	l	Pole	Red		ende nch		rovem elter	ents			1
													Relative		_								Trim			ADA
10.0	D. Gran	_	_		Rou								Ridership Over	New	Replace	New	Replace	×	New	Replace	Vew	Replace	Vege-	Improve	Bus	Improve-
ID# 81.16	Bus Stop ACROSS FROM PEOPLE SERVICES	1	_	3	4 4	4A	_	х	10 1	1 :	12	Stop Shared With	All Routes Low	ž	ž	ž	ž	Α̈́	ž	ž	ž	ž	tation	Lighting	Pullout	ments
81.17	ACROSS FROM PERKS MOBILE HOME						_	_	Х	+			Low			-		Х								Х
100.02	CLEARLAKE APTS			t				_	X	1	Х	120.13	Med					^	Х		1			Х	Х	^
100.03	J&L MARKET			- 1		-		_	X	_	X	120.13	Low												X	Х
100.04	CROSSROADS CHURCH								X	_	Х	120.15	Low	Х							1				X	
100.05	CYPRESS							_	Х	_	Х	120.16	Low	Х		Х									Х	Х
100.06	MENDO MILL								Х				Low	Х		Х										Х
100.07	OLD HWY 53 & LAKESHORE								Х				Med						Х					Х	Х	Х
100.08	OLD RED CROSS								Х				Low					Х								Х
100.09	HILL AVE								Х				Low					Х								Х
100.10	RIDGE LAKE APTS-COMMONS								Х				Med					Х				Χ				
100.11	BURNS VALLEY MALL								Х				Low				Х								X	Х
100.12	CLEARLAKE POST OFFICE								Х				Med		Х			Х	Х							
100.13	BABY STORE (ACROSS FROM LOCUST)								Х				Low	Χ		Х										Х
									Х				Low					Χ								
100.15	OLD BOWLING ALLEY							_	Х				Low					Χ								
									Х	_			Low	Χ		Х									Х	Х
100.17	BOXWOOD & ARROWHEAD	<u> </u>	Ш		_	_	ļ_		Х				Med		<u> </u>	<u> </u>			Х	<u> </u>	1			Х		Х
100.18	TOYON	<u> </u>	Ш	_	_	_	_	_	Х	4	_		Low	<u> </u>	Х	<u> </u>				<u> </u>	1					Х
100.19	MODOC								Х	_			Low					Х								
100.20	2ND ST (HALFWAY DOWN BLOCK)					_			Х	_	_		Low					Х			<u> </u>		Х			Х
									Х	_			Med					Χ						Х		Х
								_	Х	_			Low													Х
	11TH & BUSH					_	_	_	Х	4	_		Low	Х		X										X
100.24	13TH & COUNTRY CLUB					_	_		Х	4	_		Low	Х		Х										X
100.25	COUNTRY CLUB & ARROWHEAD			+					Х	_			Low			-										Х
100.26	CLEARLAKE PARK POST OFFICE	_				4	-		X X	+	-		Low	Х		٧.					1		Х			Х
	AMERICAS BEST VALUE INN LAKESHORE & POMO	_				4	-		X	+	-		Med	Х		Х			Х		1					
100.28	CITY HALL					-			X	-	-		Low			-		X								Х
	AUSTIN PARK	-			-	+	+	_	X	+	+		Low			-		^			1		-			
100.30	BAYLIS & LAKEHORE	1				\dashv	-	_	X	+	-		Med		_				Х		1			Х		Х
100.31	HIGHLANDS PARK (CASTLE DONUTS)	-			-	+	+		X	+	+		Low			-			^		1		-	^		^
						-			X	+	-		Med	Х		Х			Х		_				Х	х
100.33	NOTT'S LIQUOR	1		- 1	-	+	+		X	+	-		Low	^	1	^			^		1					X
100.35	VETERANS CLINIC	1		- 1	-	+	+	_	<u>х</u> х	,	-	110.3	Med	Х	1	Х					1					^
100.36	VALERO			- 1		-		_	X X	_		110.31	Low	X		X										Х
100.30	SOCIAL SERVICES		H	+	\dashv	-	+		X	+	-	110.01	Low	X		X					t					X
				_	\dashv	+	-	_	X	+	Х	120.06	Low	X	1	X	l		l		1					X
100.41	BETWEEN LAKE & 2ND ST			t	T t	T	<u> </u>		X	T	Ť		Med	<u> </u>	1	Ħ		Х			1					
100.42	LOWER LAKE HIGH SCHOOL			t	T t	T	<u> </u>		X	T	Х	120.08	High		1						1					
	CEMETERY			1	\dashv	1	1		X	_	Х	120.09	Low	Х		Х					1			1		
	BRYANT RD			T	7	1	T	_	X	_	Х	120.1	Low	Х		Х										
100.45	CACHE CREEK APTS			İ					Х	T	Х	120.11	Low		1											
110.02	ST.HELENA CLEARLAKE				T			T	×	_	T		Low	Х		Х										
110.03	IRVING & 18TH				T	T			X	(T		Low					Х								Х
110.04	BOYLES & 18TH								X	(Low			L		Χ								Х
110.05	BOYLES & 25TH								X	(Low		Ĺ											Х
110.06	BOYLES BETWEEN 30TH & 31ST								X	<			Low													Х
110.07	33RD & PHILLIPS								X	(Low					Χ								Х
110.08	36TH & PHILLIPS								X				Low					Χ								Х
110.09	PHILLIPS & 40TH (40TH STORE)								X	<			Low					Χ								Х
	45TH -THE DUMP DAVIS ST								X	_			Low					Χ								Х
110.11	MOSS (FIRST DRIVE WAY)								X	(Low					Χ								Х
110.12	WEST AMERICA BANK					I			>	< □	I		Med					Х	Х							Х

TABLE	1: Summary of Recommended Improve	mei	nts	(6.	Shee	ets)																				
																		Re	comn	nend	ed Im	prove	ments			
														9	ign		Pol	е	В	ench	SI	elter				
													Relative		e		e			e		9	Trim			ADA
					Rout								Ridership Over	≥		>	Replace		>	Replac	. >		Vege-	Improve	Bus	Improve-
ID#	Bus Stop	1	2	3	4 4	A 7	8	10	11	1.	2	Stop Shared With	All Routes	New	Re	New	Re	Ξ	New	Re	New	Re	tation	Lighting	Pullout	ments
110.13	CLEARLAKE FAMILY CLINIC								Х				Med	Х		Х			Х					Х	Х	X
110.14	NAPA AUTO PARTS								Х	Х	(120.19	Low													
110.15	NOTT'S LIQUOR								Х				Low	Х		Х								Х		
110.16	CATFISH COFFEE								Х	Х	(120.21	Med						Х						Х	Х
110.17	BURGER TIME								Х	Х	(120.22	Low													Х
110.19	OLD FIREHOUSE								Х	Х	(120.24	Low													Х
110.20	AUSTIN PARK								Х	Х	(120.25	Low												Х	X
110.21	HAVERTY FIELD								Х	Х	(120.26	Low		Х											X
110.22	CLEARLAKE POST OFFICE								Х	Х	(120.27	Low	Х		Х									Х	Х
110.23	BURNS VALLEY MALL								Х				Low				Х								Х	Х
110.25	SHELTER AT WALNUT GROVE APTS								Х	Х	(120.31	Low	Х		Х						Х				
110.26	SAFEWAY								Х	Х	(120.32	Low	Х		Х									Х	
110.27	OLD HWY 53 PAST RITE AID								Х	Х	(120.33	Low										Х			X
110.28	HIGHLANDS WAY								Х	Х	(120.34	Low					Х								X
110.29	HILLCREST								Х	Х	(120.35	Low	Х		Х										X
110.32	MOSS & DAVIS (BEFORE 35MPS SIGN)								Х				Low	Х		Х										Х
110.33	PHILLIPS & 44TH								Х				Low					Х								
110.34	PHILLIPS & 39TH								Х			·	Low	Χ		Х										
110.35	32ND & PHILLIPS								Х			·	Low					Х								Х
110.36	BOYLES & 29TH								Х			·	Low	Χ		Х										
110.37	BETWEEN 26TH & 25TH								Χ			·	Low	Χ		Х										
	BOYLES AND 21ST								Х				Low		Х			Х					Х			Х
110.39	IRVING & 18TH								Х				Low					Х					Х			Х

120.37 MENDO MILL Х Χ Х Х Low 120.38 KING FISHER Х Χ Low 120.39 CEDAR VILLAGE APTS Х Х Low 120.40 HIGHLANDS APTS Х Low 120.41 CLEARLAKE APTS Х Low Total # of Improvements 141 8 149 5 58 17 5 0 12 13 17 34 146

Х

Х

Х

Х

Х

Х

Χ

Х

Χ

Х

Х

Х

Χ

Χ

х х

Χ

Х

Χ

Х

Х

Low

Low

Low

Low

Low

Low

Low

Low

Low

110.40 ST.HELENA CLEARLAKE

120.07 BETWEEN LAKE ST & SECOND ST

120.18 OLD HWY 53 & LAKESHORE

120.17 MENDO MILL (ACROSS THE STREET)

120.36 BALLPARK-OLD HWY 53-LAKESHORE

120.03 SOCIAL SERVICES

120.20 NOTT'S LIQOUR

120.29 B&G TIRES

120.28 BURNS VALLEY MALL

Table F-2: Recommended Pullout Locations and Priority

Source: LSC Transportation Consultants, Inc.

		Routes								Allow Passing Without Impinging on Oncoming Weighted								
Stop ID	Stop	Street	Side	1	2	3	4	4a	7	8	10	11	12	Ridership	Lane	ADT	Score	Priority
10.08	LAKEVIEW DR	SR-20	North	Х										Low	Υ	5,135	4	Low
10.12	BRUNER DR	SR-20	East	Х										Low	N	7,409	8	Medium
10.15	BELL RAY	SR-20	East	Х										Low	N	7,063	8	Medium
11.14	2ND & HWY 20 BTN XWALK & ALPINE PARK SIGN	SR-20	West	Х										Low	Υ	9,598	8	Medium
20.22	PERRYS DELI	SR-29	West		Х									Low	N	10,518	10	High
30.02	JOB ZONE	SR-53	West			Χ	Χ				Χ		Х	Low	N	10,500	11	High
31.04	PERRYS DELI	SR-29	East			Χ								Low	N	10,518	10	High
40.13	ACROSS FROM ROTTEN ROBBIES	S Main St	East				Χ							Low	Υ	5,740	4	Low
40.14	STATE FARM (ACROSS FROM KMART)	S Main St	East				Χ							Low	Υ	5,740	4	Low
40.15	NURSERY & GROCERY OUTLET	S Main St	East				Χ	Χ						Low	Υ	9,300	9	High
41.03	MAIN & D ST	S Main St	West				Χ							Low	Υ	12,100	8	Medium
41.08	GROCERY OUTLET	S Main St	West				Χ	Χ		Χ				Med	Υ	9,300	11	High
41.11	ROTTEN ROBBIES	S Main St	West				Χ	Χ		Χ				Low	Υ	5,740	5	Low
80.14	HIGH ST VILLAGE	N High St	West							Χ				Low	Υ	8,200	6	Low
80.15	LIBRARY	N High St	West							Χ				Low	Υ	6,600	6	Low
81.08	VIA DEL LAGO	N High St	East							Χ				Low	Υ	8,200	6	Low
100.02	CLEARLAKE APTS	Old Hwy 53	East								Χ		Х	Med	N	5,240	9	High
100.03	J&L MARKET	Old Hwy 53	East								Χ		Х	Low	N	5,240	7	Medium
100.04	CROSSROADS CHURCH	Old Hwy 53	East								Χ		Х	Low	N	5,240	7	Medium
100.05	CYPRESS	Old Hwy 53	East								Χ		Х	Low	N	5,265	7	Medium
100.07	OLD HWY 53 & LAKESHORE	Old Hwy 53	East								Χ			Med	N	5,265	8	Medium
100.11	BURNS VALLEY MALL	Olympic Dr	North								Χ			Low	Υ	5,870	6	Low
100.16	POMO & WOODLAND	Lakeshore Dr	East								Χ			Low	N	5,950	8	Medium
100.33	CATFISH COFFEE	Lakeshore Dr	Southwest								Χ			Med	N	7,258	10	High
110.13	CLEARLAKE FAMILY CLINIC	Lakeshore Dr	North									Χ		Med	Υ	8,130	8	Medium
110.16	CATFISH COFFEE	Lakeshore Dr	Northeast									Χ	Х	Med	N	7,694	11	High
110.20	AUSTIN PARK	Lakeshore Dr	East									Χ	Х	Med	N	7,694	11	High
110.22	CLEARLAKE POST OFFICE	Olympic Dr	South									Χ	Х	Low	Υ	5,200	5	Low
110.23	BURNS VALLEY MALL	Olympic Dr	South									Χ		Low	Υ	5,870	6	Low
110.26	SAFEWAY	Burns Valley Rd	West									Χ	Χ	Low	N	5,010	7	Medium
120.17	MENDO MILL (ACROSS THE STREET)	Old Hwy 53	East										Χ	Low	Υ	5,265	4	Low
120.20	NOTT'S LIQUOR	Lakeshore Dr	North										Χ	Low	N	8,130	8	Medium
120.36	BALLPARK-OLD HWY 53-LAKESHORE	Old Hwy 53	West										Χ	Low	N	5,265	6	Low
120.37	MENDO MILL	Old Hwy 53	West										Χ	Low	Υ	5,265	4	Low


Width Adequate to


Table F-3: Review of Bus Stop Locations on Major Roadways in Clearlake

				Routes	5		Exis	sting Amen	ities	Distance From	Meets Spacing
	Stop ID	Stop Location	10	11	12	Ridership	Pullout	Shelter	Bench	Previous Stop (Ft.) ¹	Standard?
Lak	ceshore Dr	ive									
	110.12	West America Bank		Х		Med				790	Yes
	110.13	Foods Etc., Clearlake Family Clinics		Х		Med	х		Х	1,260	Too Far
	110.14	Napa Auto Parts		х	х	Low				1,245	Too Far
اع	110.15	Notts Liquor		х	х	Low				880	Yes
Northbound	110.16	Catfish Coffee		х	х	Med	х			970	Too Far
۱	110.17	Burger Time		х	х	Low				800	Yes
ŧ	110.18	Hospice		х	х	Med			х	1,540	Too Far
2	110.19	Old Firehouse		х	х	Low				1,100	Too Far
	110.20	Lakeshore Drive and Austin Road		х	х	Low		х		1,300	Too Far
	100.15	Old Bowling Alley	х			Low				920	Too Far
	100.16	Lakeshore Drive and Woodland Drive	х			Low	х			1,200	Too Far
	100.26	Clearlake Post Office	х			Low				1,950	Too Far
	100.27	Best Value Inn	х			Med				3,150	Too Far
	100.28	Lakeshore Drive and Pomo Road	х			Low	х			620	Too Close
ᄝ	100.29	City Hall Lakeshore and Olympic	х			Low	х			1,750	Too Far
	100.30	Austin Park West	х			Low		Х		870	Yes
١٩	100.31	Bayliss/Lakeshore Old Firehouse	х			Med				1,100	Too Far
Southbound	100.32	Highlands Park (Castle Donuts)	х			Low				1,600	Too Far
So	100.33	Catfish Coffee	х			Med	х			2,000	Too Far
	100.34	Knott's Liquor	х			Med				910	Too Far
	100.35	Veteran's Clinic Lakeshore	х	X		Low		х	х	1,110	Too Far
	100.36	Valero (across from Verizon)	х	Х		Low			Х	1,180	Too Far
Oly	mpic Drive	e									
	110.21	Haverty Field		Х	Х	Low	Х			1,400	Too Far
EB	110.22	Clearlake Post Office		х	х	Low	х			1,780	Too Far
	110.23	Burns Valley Mall		Х	х	Low	х			1,700	Too Far
	100.11	Burns Valley Mall	х			Low	х			2,000	Too Far
8	100.12	Post Office	х			Med				1,600	Too Far
WB	100.13	Olympic Drive and Locust Street	х			Low	х			1,150	Too Far
	100.14	City Hall Olympic and Lakeshore	х			Low	х			1,560	Too Far
Old	d Highway	53									
	100.02	Clearlake Apartments	х		Х	Med	х		Х	2,150	Too Far
	100.03	J&L Market	х		Х	Low	х			1,930	Too Far
٥	100.04	Crossroads Church/Crawford Street	х		Х	Low	х			1,280	Too Far
l E	100.05	Cypress	х		Х	Low	х			1,720	Too Far
Northbound	100.06	Mendo Mill	х		Х	Low				1,050	Too Far
뒤	100.07	Old 53 and Lakeshore	х			Med	Х			1,750	Too Far
Πġ	100.08	Old Red Cross (Opposite Hillcrest)	х			Low				1,190	Too Far
	100.09	Hill Ave	х			Low				520	Too Close
	100.10	Clearlake Commons	Х			Med		Х	Х	1,650	Too Far
	100.11	B&G Tire		Х	Х	Low	Х			1,720	Too Far
	110.26	Safeway		х	Х	Low	х			1,470	Too Far
	110.27	Old 53 past Rite Aid		Х	Х	Low				860	Yes
ğ	110.28	Highlands Way		Х	Х	Low				1,790	Too Far
ΙĮ	110.29	Hillcrest		Х	Х	Low				1,280	Too Far
Southbound	120.36	Old 53 and Lakeshore			Х	Low	X			1,550	Too Far
불	120.37	Mendo Mill			Х	Low	X	Х	х	1,215	Too Far
So	120.38	Kingfisher			Х	Low	Х			1,700	Too Far
	120.39	Cedar Village Apartments			Х	Low	,			1,020	Too Far
	120.40	Highlands Village Apartments			X	Low	X	X		680	Yes Too Far
Ш	120.41	Clearlake Apartments			Х	Low	Х	Х		2,800	Too Far

Note 1: Standard is to provide stops in urbanized areas between 660 and 880 apart. Source: LSC Transportation Consultants, Inc.

Appendix G
Conceptual Design Plans and Cost Estimates for Three
Primary Bus Stops





LEGEND



STREET LIGHT

BUS SHELTER WITH BENCH



BIKE RACK



BUS STOP SIGN

TRASH CAN



220 MONTGOMERY STREET, SUITE 346 SAN FRANCISCO, CA 94104 PHONE (415) 392-9688

LAKE TRANSIT AUTHORITY

BUS PASSENGER FACILITY PLAN CONCEPTUAL DESIGN

LAKEPORT BUS STATION **OPTION 1 - BUS ISLAND**




Intersection: Lakeport Blvd/S Main St (Bus Island)


Date: 2/1/2019

Author/Reviewer: CL/SK

Bid Item No.	Bid Items	Unit	Unit Cost	Quantity	Total
1	Mobilization	EA	\$ 10,000.00	1	\$ 10,000.00
2	Traffic Control	EA	\$ 10,000.00	1	\$ 10,000.00
3	Storm Water Management and Erosion Control	EA	\$ 10,000.00	1	\$ 10,000.00
4	Clearing and Grubbing	LS	\$ 10,000.00		\$ -
5	Remove Asphalt Concrete	SF	\$ 6.00	4715	\$ 28,290.00
6	Remove Existing Curb	LF	\$ 10.00		\$ -
7	Remove Existing Curb and Gutter	LF	\$ 12.00		\$ -
8	Remove Concrete - Sidewalk	SF	\$ 10.00		\$ -
9	Remove Existing Storm Drain Inlet	EA	\$ 2,000.00		\$ -
10	Remove and Salvage Existing Bus Shelter	EA	\$ 500.00	1	\$ 500.00
11	Remove Existing Wooden Shelter	EA	\$ 300.00		\$ -
12	Remove Bollard	EA	\$ 100.00	7	\$ 700.00
13	Remove Striping and Pavement Markings	LS	\$ 1,000.00	1	\$ 1,000.00
14	Remove Sign and Post	EA	\$ 100.00	2	\$ 200.00
15	Remove Tree	EA	\$ 1,000.00	2	\$ 2,000.00
16	Relocate Existing Sign and Posts	EA	\$ 500.00	1	\$ 500.00
17	Relocate Existing Utility Pole and Guy Wire	EA	\$ 50,000.00		\$ -
18	Vertical Curb	LF	\$ 40.00		\$ -
19	Curb and Gutter	LF	\$ 40.00		\$ -
20	New Median	SF	\$ 20.00	570	\$ 11,400.00
21	Asphalt Concrete Type A	TON	\$ 400.00		\$ -
22	Aggregate Base Class 2	TON	\$ 250.00		\$ -
23	Concrete Sidewalk	SF	\$ 10.00		\$ -
24	New Curb Ramp	EA	\$ 2,000.00	2	\$ 4,000.00
25	Concrete Bus Pad	SF	\$ 10.00	4000	\$ 40,000.00
26	Concrete Driveway	SF	\$ 40.00		\$ -
27	Thermoplastic Pavement Striping	LS	\$ 2,000.00	1	\$ 2,000.00
28	Thermoplastic Pavement Markings	SF	\$ 10.00	238	\$ 2,380.00
29	Furnish & Install New Storm Drain inlet	EA	\$ 10,000.00		\$ -
30	Furnish & Install Luminaire and Pole	EA	\$ 4,500.00	1	\$ 4,500.00
31	Furnish & Install Luminaire Pole Foundation	EA	\$ 1,500.00	1	\$ 1,500.00
32	Furnish & Install Pull Box	EA	\$ 1,000.00	1	\$ 1,000.00
33	Install Conduit and Conductors	LS	\$ 5,000.00	1	\$ 5,000.00
34	Furnish & Install Bollard	EA	\$ 200.00	15	\$ 3,000.00
35	New Sign and Post	EA	\$ 300.00	2	\$ 600.00
36	Furnish & Install Bus Shelter with Bench (5'x10')	EA	\$ 8,000.00	1	\$ 8,000.00
37	Furnish & Install Bike Rack	EA	\$ 500.00	1	\$ 500.00
38	Furnish & Install Trash Can Enclosure	EA	\$ 500.00	1	\$ 500.00
39					
40					
				Subtotal	\$ 147,570.00
	Cc	ntingency	25%		\$ 36,892.50
				TOTAL	\$ 184,462.50

Note: This estimate reflects probable construction costs based on the project location. Where possible, the estimate is based upon actual measurements of certain items. Unit costs were obtained from projects of similar nature.





¤ ·······

LEGEND

STREET LIGHT

BUS SHELTER WITH BENCH

— E

BIKE RACK



BUS STOP SIGN





LAKE TRANSIT AUTHORITY

BUS PASSENGER FACILITY PLAN CONCEPTUAL DESIGN

LAKEPORT BUS STATION OPTION 2 - SB BUS PULL-OUT



Lake Transit Bus Passenger Facility Study Project:

Intersection: Lakeport Blvd/S Main St (SB Pull-out) Date: 2/1/2019

Author/Reviewer: CL/SK

2	Mobilization Traffic Control Storm Water Management and Erosion Control Clearing and Grubbing Remove Asphalt Concrete Remove Existing Curb Remove Existing Curb and Gutter Remove Concrete - Sidewalk Remove Existing Storm Drain Inlet Remove and Salvage Existing Bus Shelter Remove Existing Wooden Shelter Remove Bollard Remove Striping and Pavement Markings Remove Sign and Post	EA EA EA LS SF LF LF SF EA EA EA	\$ \$ \$ \$ \$ \$	Unit Cost 10,000.00 10,000.00 10,000.00 10,000.00 6.00 10.00 12.00 10.00	1 1 1 2350	\$ \$ \$ \$ \$	10,000.0 10,000.0 10,000.0 - 14,100.0
3 S S S S S S S S S S S S S S S S S S S	Storm Water Management and Erosion Control Clearing and Grubbing Remove Asphalt Concrete Remove Existing Curb Remove Existing Curb and Gutter Remove Concrete - Sidewalk Remove Existing Storm Drain Inlet Remove and Salvage Existing Bus Shelter Remove Existing Wooden Shelter Remove Bollard Remove Striping and Pavement Markings Remove Sign and Post	EA LS SF LF LF SF EA EA	\$ \$ \$ \$ \$ \$	10,000.00 10,000.00 10,000.00 6.00 10.00 12.00	2350	\$ \$ \$ \$	10,000.0 10,000.0
4	Clearing and Grubbing Remove Asphalt Concrete Remove Existing Curb Remove Existing Curb and Gutter Remove Concrete - Sidewalk Remove Existing Storm Drain Inlet Remove and Salvage Existing Bus Shelter Remove Existing Wooden Shelter Remove Bollard Remove Striping and Pavement Markings Remove Sign and Post	LS SF LF LF SF EA EA	\$ \$ \$ \$ \$	10,000.00 10,000.00 6.00 10.00 12.00	2350	\$ \$ \$ \$	-
4 (0 5 F 6 F 7 F 8 F 9 F 10 F 11 F 12 F 13 F 16 F 17 F 18 V	Clearing and Grubbing Remove Asphalt Concrete Remove Existing Curb Remove Existing Curb and Gutter Remove Concrete - Sidewalk Remove Existing Storm Drain Inlet Remove and Salvage Existing Bus Shelter Remove Existing Wooden Shelter Remove Bollard Remove Striping and Pavement Markings Remove Sign and Post	SF LF LF SF EA EA	\$ \$ \$ \$ \$	10,000.00 6.00 10.00 12.00		\$ \$ \$	-
5 F 6 F 7 F 8 F 9 F 10 F 11 F 12 F 13 F 14 F 15 F 16 F 17 F	Remove Asphalt Concrete Remove Existing Curb Remove Existing Curb and Gutter Remove Concrete - Sidewalk Remove Existing Storm Drain Inlet Remove and Salvage Existing Bus Shelter Remove Existing Wooden Shelter Remove Bollard Remove Striping and Pavement Markings Remove Sign and Post	SF LF LF SF EA EA	\$ \$ \$ \$ \$	6.00 10.00 12.00		\$ \$	14,100.0
6 F 7 F 8 F 9 F 10 F 11 F 12 F 13 F 14 F 15 F 16 F 17 F	Remove Existing Curb Remove Existing Curb and Gutter Remove Concrete - Sidewalk Remove Existing Storm Drain Inlet Remove and Salvage Existing Bus Shelter Remove Existing Wooden Shelter Remove Bollard Remove Striping and Pavement Markings Remove Sign and Post	LF SF EA EA	\$ \$ \$	12.00		\$	
7 F 8 F 9 F 10 F 11 F 12 F 13 F 14 F 15 F 16 F 17 F 18	Remove Existing Curb and Gutter Remove Concrete - Sidewalk Remove Existing Storm Drain Inlet Remove and Salvage Existing Bus Shelter Remove Existing Wooden Shelter Remove Bollard Remove Striping and Pavement Markings Remove Sign and Post	SF EA EA	\$		215		-
8 F 9 F 10 F 11 F 12 F 13 F 14 F 15 F 16 F 17 F	Remove Concrete - Sidewalk Remove Existing Storm Drain Inlet Remove and Salvage Existing Bus Shelter Remove Existing Wooden Shelter Remove Bollard Remove Striping and Pavement Markings Remove Sign and Post	EA EA EA	\$	10.00		\$	2,580.0
10 F 11 F 12 F 13 F 14 F 15 F 16 F 17 F	Remove and Salvage Existing Bus Shelter Remove Existing Wooden Shelter Remove Bollard Remove Striping and Pavement Markings Remove Sign and Post	EA EA			1050	\$	10,500.
10 F 11 F 12 F 13 F 14 F 15 F 16 F 17 F	Remove and Salvage Existing Bus Shelter Remove Existing Wooden Shelter Remove Bollard Remove Striping and Pavement Markings Remove Sign and Post	EA	4	2,000.00		\$	
11 F 12 F 13 F 14 F 15 F 16 F 17 F 18 \(\)	Remove Existing Wooden Shelter Remove Bollard Remove Striping and Pavement Markings Remove Sign and Post	+	\$	500.00	1	\$	500.
12 F 13 F 14 F 15 F 16 F 17 F	Remove Bollard Remove Striping and Pavement Markings Remove Sign and Post	+	\$	300.00		\$	
13 F 14 F 15 F 16 F 17 F 18 \(\)	Remove Sign and Post	L/	\$	100.00	10	\$	1,000.
14 F 15 F 16 F 17 F 18 V	Remove Sign and Post	LS	\$	500.00	1	\$	500.
15 F 16 F 17 F 18 \		EA	\$	100.00	1	\$	100.
16 F 17 F 18 \	Remove Tree	EA	\$	1,000.00		\$	
17 F	Relocate Existing Sign and Post	EA	\$	200.00	2	\$	400.
18 \	Relocate Existing Utility Pole and Guy Wire	EA	\$	50,000.00	1	\$	50,000.
+	Vertical Curb	LF	\$	40.00		\$	-
	Curb and Gutter	LF	\$	40.00	220	\$	8,800.
	New Median	SF	\$	20.00		\$	
	Asphalt Concrete Type A	TON	\$	400.00		\$	
	Aggregate Base Class 2	TON	\$	250.00	140	\$	35,000.
+	Concrete Sidewalk	SF	\$	10.00	2190	\$	21,900.
	New Curb Ramp	EA	\$	2,500.00	1	\$	2,500.
+	Concrete Bus Pad	SF	\$	10.00	2440	\$	24,400.
	Concrete Driveway	SF	\$	40.00	1	\$	40.
	Thermoplastic Pavement Striping	LS	\$	600.00	1	\$	600.
	Thermoplastic Pavement Markings	SF	\$	10.00	126	\$	1,260.
	Furnish & Install New Storm Drain inlet	EA	\$	10,000.00		\$	
	Furnish & Install Luminaire and Pole	EA	\$	4,500.00	1	\$	4,500.
	Furnish & Install Luminaire Pole Foundation	EA	\$	1,500.00	1	\$	1,500.
	Furnish & Install Pull Box	EA	\$	1,000.00	1	\$	1,000.
	Install Conduit and Conductors	LS	\$	5,000.00	1	\$	5,000.
	Furnish & Install Bollard	EA	\$	200.00	10	\$	2,000.
	New Sign and Post	EA	\$	300.00	2	\$	600.
	Furnish & Install Bus Shelter with Bench (5'x10')	EA	\$	8,000.00	2	\$	16,000.
	Furnish & Install Bike Rack	EA	\$	500.00	1	\$	500.
	Furnish & Install Trash Can Enclosure	EA	\$	500.00	2	\$	1.000.
39	. arrish a nistan mash can Endosare	LA	٧	550.00		۲	1,000.
40			 			\vdash	
40			1	1			
					Subtotal	¢	236 290
		Contingency		25%	Subtotal	\$	236,280. 59,070.

Note: This estimate reflects probable construction costs based on the project location. Where possible, the estimate is based upon actual measurements of certain items. Unit costs were obtained from projects of similar nature.





LEGEND



BUS SHELTER WITH BENCH



BIKE RACK



BUS STOP SIGN





220 MONTGOMERY STREET, SUITE 346 SAN FRANCISCO, CA 94104 PHONE (415) 392-9688

LAKE TRANSIT AUTHORITY

BUS PASSENGER FACILITY PLAN CONCEPTUAL DESIGN

KIT'S CORNER BUS FACILITY
LAYOUT


ser Facility Study_AECOM — 18-1018\CAD\18-1018 Exhibit 2.dwa 02 01, 2019 3:05pm BY: ffena




Location: Kit's Corner Bus Stop Date: 2/1/2019
Author/Reviewer: CL/SK

Bid Item No.	Bid Items	Unit	Unit Cost	Quantity	Total
1	Mobilization	EA	\$ 10,000.00	1	\$ 10,000.00
2	Traffic Control	EA	\$ 5,000.00	1	\$ 5,000.00
3	Storm Water Management and Erosion Control	EA	\$ 10,000.00	1	\$ 10,000.00
4	Clearing and Grubbing	LS	\$ 15,000.00	1	\$ 15,000.00
5	Remove Asphalt Concrete	SF	\$ 6.00	1635	\$ 9,810.00
6	Remove Existing Curb	LF	\$ 10.00		\$ -
7	Remove Existing Curb and Gutter	LF	\$ 12.00		\$ -
8	Remove Concrete - Sidewalk	SF	\$ 10.00		\$ -
9	Remove Existing Storm Drain Inlet	EA	\$ 2,000.00		\$ -
10	Remove and Salvage Existing Bus Shelter	EA	\$ 500.00		\$ -
11	Remove Existing Wooden Shelter	EA	\$ 300.00	1	\$ 300.00
12	Remove Bollard	EA	\$ 100.00		\$ -
13	Remove Striping and Pavement Markings	LS	\$ 1,000.00		\$ -
14	Remove Sign and Post	EA	\$ 100.00		\$ -
15	Remove Tree	EA	\$ 1,000.00		\$ -
16	Relocate Existing Sign and Posts	EA	\$ 500.00		\$ -
17	Relocate Existing Utility Pole and Guy Wire	EA	\$ 50,000.00		\$ -
18	Vertical Curb	LF	\$ 40.00		\$ -
19	Curb and Gutter	LF	\$ 40.00		\$ -
20	New Median	SF	\$ 20.00	3335	\$ 66,700.00
21	Asphalt Concrete Type A	TON	\$ 400.00		\$ -
22	Aggregate Base Class 2	TON	\$ 250.00		\$ -
23	Concrete Sidewalk	SF	\$ 10.00		\$ -
24	New Curb Ramp	EA	\$ 2,000.00	1	\$ 2,000.00
25	Concrete Bus Pad	SF	\$ 10.00	960	\$ 9,600.00
26	Concrete Driveway	SF	\$ 40.00		\$ -
27	Thermoplastic Pavement Striping	LS	\$ 1,500.00		\$ -
28	Thermoplastic Pavement Markings	SF	\$ 10.00		\$ -
29	Furnish & Install New Storm Drain inlet	EA	\$ 10,000.00		\$ -
30	Furnish & Install Luminaire and Pole	EA	\$ 4,500.00	3	\$ 13,500.00
31	Furnish & Install Luminaire Pole Foundation	EA	\$ 1,500.00	3	\$ 4,500.00
32	Furnish & Install Pull Box	EA	\$ 1,000.00	3	\$ 3,000.00
33	Install Conduit and Conductors	LS	\$ 6,000.00	1	\$ 6,000.00
34	Furnish & Install Bollard	EA	\$ 200.00		\$ -
35	New Sign and Post	EA	\$ 300.00		\$ -
36	Furnish & Install Bus Shelter with Bench (5'x10')	EA	\$ 8,000.00	3	\$ 24,000.00
37	Furnish & Install Bike Rack	EA	\$ 500.00	3	\$ 1,500.00
38	Furnish & Install Trash Can Enclosure	EA	\$ 500.00	3	\$ 1,500.00
39					
40					
		•		Subtotal	\$ 182,410.00
	C	ontingency	25%		\$ 45,602.50
				TOTAL	\$ 228,012.50

Note: This estimate reflects probable construction costs based on the project location. Where possible, the estimate is based upon actual measurements of certain items. Unit costs were obtained from projects of similar nature.





LEGEND



BUS SHELTER WITH BENCH

BIKE RACK

BUS STOP SIGN

TRASH CAN



LAKE TRANSIT AUTHORITY

BUS PASSENGER FACILITY PLAN CONCEPTUAL DESIGN

AUSTIN PARK BUS STOP BUS PULLOUT



Location: Lakeshore Drive Bus Pull-out Date: 10/8/2019

Author/Reviewer: CL/AK

Bid Item No.	Bid Items	Unit		Unit Cost	Quantity		Tota
1	Mobilization	EA	\$	10,000.00	1	\$	10,000.00
2	Traffic Control	EA	\$	5,000.00	1	\$	5,000.00
3	Storm Water Management and Erosion Control	EA	\$	5,000.00	1	\$	5,000.00
4	Clearing and Grubbing	LS	\$	10,000.00		\$	-
5	Remove Asphalt Concrete	SF	\$	6.00	570	\$	3,420.00
6	Remove Existing Curb	LF	\$	10.00		\$	-
7	Remove Existing Curb and Gutter	LF	\$	12.00	145	\$	1,740.00
8	Remove Concrete - Sidewalk	SF	\$	10.00	725	\$	7,250.00
9	Remove Existing Storm Drain Inlet	EA	\$	2,000.00		\$	-
10	Remove Fence	LS	\$	500.00	1	\$	500.00
11	Remove Striping and Pavement Markings	LS	\$	300.00		\$	-
12	Remove Sign Panel	EA	\$	100.00		\$	-
13	Remove Bench	EA	\$	100.00	1	\$	100.00
14	Relocate Existing Sign and Post	EA	\$	200.00	1	\$	200.00
15	Adjust Existing Utility to Finished Grade	EA	\$	5,000.00		\$	-
16	Adjust Existing Manhole to Finished Grade	LF	\$	15,000.00		\$	-
17	Vertical Curb	LF	\$	40.00		\$	-
18	Curb and Gutter	LF	\$	40.00	145	\$	5,800.00
19	Asphalt Concrete Type A	TON	\$	400.00		\$	-
20	Aggregate Base Class 2	TON	\$	250.00		\$	-
21	Concrete Sidewalk	SF	\$	10.00	960	\$	9,600.00
22	New Curb Ramp	EA	\$	2,000.00		\$	-
23	Concrete Bus Pad	SF	\$	10.00	1150	\$	11,500.00
24	Furnish & Install New Fence	LS	\$	2,000.00	1	\$	2,000.00
25	Thermoplastic Pavement Striping	LS	\$	700.00		\$	-
26	Thermoplastic Pavement Markings	SF	\$	10.00	50	\$	500.00
27	Connect Existing SD to New SD Inlet Location	LS	\$	10,000.00		\$	-
28	Furnish & Install New Storm Drain Inlet	EA	\$	10,000.00		\$	-
29	Furnish & Install Luminaire and Pole	EA	\$	4,500.00	1	\$	4,500.00
30	Furnish & Install Luminaire Pole Foundation	EA	\$	1,500.00	1	\$	1,500.00
31	Furnish & Install Pull Box	EA	\$	1,000.00	1	\$	1,000.00
32	Install Conduit and Conductors	LS	\$	6,000.00	1	\$	6,000.00
33	Furnish & Install Bollard	EA	\$	200.00		\$	-
34	New Sign and Post	EA	\$	300.00		\$	-
35	Furnish & Install Bus Shelter with Bench (5'x10')	EA	\$	8,000.00	1	\$	8,000.00
36	Furnish & Install Bike Rack	EA	\$	500.00		\$	-
37	Furnish & Install Trash Can Enclosure	EA	\$	500.00		\$	_
38	ROW Acquisition	SF	\$	500.00		\$	-
39	- 24400000		7	200.00		7	
40							
	!				Subtotal	\$	83,610.00
		Contingency		25%		\$	20,902.50
				2370		Ψ.	_0,502.50

Note: This estimate reflects probable construction costs based on the project location. Where possible, the estimate is based upon actual measurements of certain items. Unit costs were obtained from projects of similar nature.

Appendix H Estimated Unit Costs for Systemwide Recommended Improvements at Individual Bus Stops



Item: Bus Stop Improvement Recommendation Cost Estimate Date: 4/16/2019

Author/Reviewer: FF/AK

						1		
Bid Item No.		Unit	Unit	t Cost	Quantity	Tota	ıl	Assumptions
	Bus Stop signs							
1	New Sign Panel	EA	\$	100.00	141	\$	14,100.00	\$300 total for sign and pole
2	Replace Sign Panel	EA	\$	200.00	8	\$	1,600.00	\$100 for removing sign panel
	Sign Poles							
3	New Sign Pole	EA	\$	200.00	149	\$		\$300 for sign and pole together
4	Replace Sign Pole	EA	\$	300.00	5	\$	1,500.00	\$100 for removing sign pole; \$200 for installing
5	Repair Sign Pole	EA	\$	100.00	58	\$	5,800.00	Repair costs half as a new pole
	Benches							
6	New Bench	EA	\$	800.00	17	\$	13,600.00	10% cost of a bus shelter
7	Replace Bench	EA	\$	900.00	5	\$	4,500.00	\$100 for removing existing bench
	Shelters							
8	Replace Shelter	EA	\$	8,000.00	12	\$	96,000.00	\$8000 total for each shelter with bench
	Bus Pullouts						•	
9	New Bus Pullouts	EA	\$ 5	6,180.00	34	\$	1,910,120.00	See Bus Pullout tab
	Vegetation		T .					
10	Tree Trimming	EA	\$	300.00	13	\$	3,900.00	See <u>Reference</u> tab
	Lighting		Ť					
11	Install Lighting	EA	\$ 1	3,000.00	17	Ś	221.000.00	See <u>Lighting</u> tab
	ADA Accessibility		1	-,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			,	<u> </u>
12	New Passenger Waiting	EA	\$ 2	0,562.50	146	Ś	3.002.125.00	See Reference tab
	The transfer traiting		7	,		7		tus increases tus
			1					
						1		
		+				-		
		+				-		
			1					
			1					
		-	+-			-		
			-			1		
			+					
		-	1-			1		
		-	╂—			_		
		-	-			-		
			1			1		
						ļ.,		
					TOTAL	\$	5,304,045.00	

Note: This estimate reflects probable construction costs based on a typical project location. Where possible, the estimate is based upon actual measurements of certain items. Unit costs were obtained from projects of similar nature.



Item: Bus Pull-out Date: 4/16/2019
Author/Reviewer: FF/AK

Bid Item No.	Bid Items		Unit Cost		Quantity	Total		
1	Mobilization	EA	\$	10,000.00				
2	Traffic Control	EA	\$	10,000.00				
3	Storm Water Management and Erosion Control	EA	\$	10,000.00				
4	Clearing and Grubbing	LS	\$	10,000.00				
5	Remove Asphalt Concrete	SF	\$	6.00	280	\$	1,680.00	
6	Remove Existing Curb	LF	\$	10.00				
7	Remove Existing Curb and Gutter	LF	\$	12.00				
8	Remove Concrete - Sidewalk	SF	\$	10.00				
9	Remove Existing Storm Drain Inlet	EA	\$	2,000.00				
10	Remove Bollard	EA	\$	100.00				
11	Remove Striping and Pavement Markings	LS	\$	300.00				
12	Remove Sign Panel	EA	\$	100.00				
13	Remove Bench	EA	\$	100.00				
14	Relocate Existing Sign and Post	EA	\$	200.00		1		
15	Adjust Existing Utility to Finished Grade	EA	\$	5,000.00				
16	Adjust Existing Manhole to Finished Grade	LF	\$	15,000.00				
17	Vertical Curb	LF	\$	40.00	140	\$	5,600.00	
18	Curb and Gutter	LF	\$	40.00	160	\$	6,400.00	
19	Asphalt Concrete Type A	TON	\$	400.00		Ť	.,	
20	Aggregate Base Class 2	TON	\$	250.00	30	\$	7,500.00	
21	Concrete Sidewalk	SF	\$	10.00	1050	\$	10,500.00	
22	New Curb Ramp	EA	\$	2,000.00		Ť	.,	
23	Concrete Bus Pad	SF	\$	10.00	450	\$	4,500.00	
24	Concrete Driveway	SF	\$	40.00		Ť	,	
25	Thermoplastic Pavement Striping	LS	\$	700.00				
26	Thermoplastic Pavement Markings	SF	\$	10.00				
27	Connect Existing SD to New SD Inlet Location	LS	\$	10,000.00	1	\$	10,000.00	
28	Furnish & Install New Storm Drain Inlet	EA	\$	10,000.00	1	\$	10,000.00	
29	Furnish & Install Luminaire and Pole	EA	\$	4,500.00	_	1		
30	Furnish & Install Luminaire Pole Foundation	EA	\$	1,500.00				
31	Furnish & Install Pull Box	EA	\$	1,000.00				
32	Install Conduit and Conductors	LS	\$	6,000.00				
33	Furnish & Install Bollard	EA	\$	200.00				
34	New Sign and Post	EA	\$	300.00		1		
35	Furnish & Install Bus Shelter with Bench (5'x10')	EA	\$	8,000.00		\top		
36	Furnish & Install Bike Rack	EA	\$	500.00		+		
37	Furnish & Install Trash Can Enclosure	EA	\$	500.00		+		
38	ROW Acquisition	SF	\$	100.00		+		
39		 	Ť	100.00		+		
40	1					+		
-+0					Total	\$	56,180.00	



Item: Lighting Date: 4/16/2019
Author/Reviewer: FF/AK

Bid Item No.	Bid Items	Unit	Uni	t Cost	Quantity	Tota	al
1	Mobilization	EA	\$	10,000.00			
2	Traffic Control	EA	\$	10,000.00			
3	Storm Water Management and Erosion Control	EA	\$	10,000.00			
4	Clearing and Grubbing	LS	\$	10,000.00			
5	Remove Asphalt Concrete	SF	\$	6.00			
6	Remove Existing Curb	LF	\$	10.00			
7	Remove Existing Curb and Gutter	LF	\$	12.00			
8	Remove Concrete - Sidewalk	SF	\$	10.00			
9	Remove Existing Storm Drain Inlet	EA	\$	2,000.00			
10	Remove Bollard	EA	\$	100.00			
11	Remove Striping and Pavement Markings	LS	\$	300.00			
12	Remove Sign Panel	EA	\$	100.00			
13	Remove Bench	EA	\$	100.00			
14	Relocate Existing Sign and Post	EA	\$	200.00			
15	Adjust Existing Utility to Finished Grade	EA	\$	5,000.00			
16	Adjust Existing Manhole to Finished Grade	LF	\$	15,000.00			
17	Vertical Curb	LF	\$	40.00			
18	Curb and Gutter	LF	\$	40.00		<u> </u>	
19	Asphalt Concrete Type A	TON	\$	400.00			
20	Aggregate Base Class 2	TON	\$	250.00		<u> </u>	
21	Concrete Sidewalk	SF	\$	10.00			
22	New Curb Ramp	EA	\$	2,000.00			
23	Concrete Bus Pad	SF	\$	10.00			
24	Concrete Driveway	SF	\$	40.00			
25	Thermoplastic Pavement Striping	LS	\$	700.00			
26	Thermoplastic Pavement Markings	SF	\$	10.00			
27	Connect Existing SD to New SD Inlet Location	LS	\$	10,000.00			
28	Furnish & Install New Storm Drain Inlet	EA	\$	10,000.00			
29	Furnish & Install Luminaire and Pole	EA	\$	4,500.00	1	\$	4,500.00
30	Furnish & Install Luminaire Pole Foundation	EA	\$	1,500.00	1	\$	1,500.00
31	Furnish & Install Pull Box	EA	\$	1,000.00	1	\$	1,000.00
32	Install Conduit and Conductors	LS	\$	6,000.00	1	\$	6,000.00
33	Furnish & Install Bollard	EA	\$	200.00	-	7	0,000.00
34	New Sign and Post	EA	\$	300.00			
35	Furnish & Install Bus Shelter with Bench (5'x10')	EA	\$	8,000.00			
36	Furnish & Install Bike Rack	EA	\$	500.00		+	
37	Furnish & Install Trash Can Enclosure	EA	\$	500.00		+	
38	ROW Acquisition	SF	\$	100.00		+	
39	NOW Acquisition	اد	۲	100.00			
40							
40			_		Total	\$	13,000.00



Item: Sidewalk/Bus Passenger Waiting Area Date: 6/25/2019

Author/Reviewer: FF/CL

Bid Item No.	Bid Items	Unit	Uni	it Cost	Quantity	Tot	al
1	Mobilization	EA	\$	5,000.00	1	\$	5,000.00
2	Traffic Control	EA	\$	5,000.00	1	\$	5,000.00
3	Storm Water Management and Erosion Control	EA	\$	10,000.00		\$	-
4	Clearing and Grubbing	LS	\$	10,000.00		\$	-
5	Remove Asphalt Concrete	SF	\$	6.00		\$	-
6	Remove Existing Curb	LF	\$	10.00		\$	-
7	Remove Existing Curb and Gutter	LF	\$	12.00		\$	-
8	Remove Concrete - Sidewalk	SF	\$	10.00		\$	-
9	Remove Existing Storm Drain Inlet	EA	\$	2,000.00		\$	-
10	Remove and Salvage Existing Bus Shelter	EA	\$	500.00		\$	-
11	Remove Existing Wooden Shelter	EA	\$	300.00		\$	-
12	Remove Bollard	EA	\$	100.00		\$	-
13	Remove Striping and Pavement Markings	LS	\$	500.00		\$	-
14	Remove Sign and Post	EA	\$	100.00		\$	-
15	Tree Trimming	EA	\$	300.00		\$	-
16	Relocate Existing Sign and Post	EA	\$	200.00		\$	-
17	Relocate Existing Utility Pole and Guy Wire	EA	\$	50,000.00		\$	-
18	Vertical Curb	LF	\$	40.00	35	\$	1,400.00
19	Curb and Gutter	LF	\$	40.00		\$	-
20	New Median	SF	\$	20.00		\$	-
21	Asphalt Concrete Type A	TON	\$	400.00		\$	-
22	Aggregate Base Class 2 (6 inch high)	TON	\$	250.00	9.45	\$	2,362.50
23	Concrete Sidewalk	SF	\$	10.00	280	\$	2,800.00
24	New Curb Ramp	EA	\$	2,000.00	2	\$	4,000.00
25	Concrete Bus Pad	SF	\$	10.00		\$	-
26	Concrete Driveway	SF	\$	40.00		\$	-
27	Thermoplastic Pavement Striping	LS	\$	600.00		\$	-
28	Thermoplastic Pavement Markings	SF	\$	10.00		\$	-
29	Furnish & Install New Storm Drain inlet	EA	\$	10,000.00		\$	-
30	Furnish & Install Luminaire and Pole	EA	\$	4,500.00		\$	-
31	Furnish & Install Luminaire Pole Foundation	EA	\$	1,500.00		\$	-
32	Furnish & Install Pull Box	EA	\$	1,000.00		\$	-
33	Install Conduit and Conductors	LS	\$	5,000.00		\$	-
34	Furnish & Install Bollard	EA	\$	200.00		\$	-
35	New Sign and Post	EA	\$	300.00		\$	-
36	Furnish & Install Bus Shelter with Bench (5'x10')	EA	\$	8,000.00		\$	-
37	Furnish & Install Bike Rack	EA	\$	500.00		\$	-
38	Furnish & Install Trash Can Enclosure	EA	\$	500.00		\$	-
39							
40							



Item: Cost Reference Date: 4/16/2019
Author/Reviewer: FF/AK

Bid Item No.	Bid Items	Unit	Uni	t Cost	Quantity	Total	
1	Mobilization	EA	\$	10,000.00		\$	-
2	Traffic Control	EA	\$	10,000.00		\$	-
3	Storm Water Management and Erosion Control	EA	\$	10,000.00		\$	-
4	Clearing and Grubbing	LS	\$	10,000.00		\$	-
5	Remove Asphalt Concrete	SF	\$	6.00		\$	-
6	Remove Existing Curb	LF	\$	10.00		\$	-
7	Remove Existing Curb and Gutter	LF	\$	12.00		\$	-
8	Remove Concrete - Sidewalk	SF	\$	10.00		\$	-
9	Remove Existing Storm Drain Inlet	EA	\$	2,000.00		\$	-
10	Remove and Salvage Existing Bus Shelter	EA	\$	500.00		\$	
11	Remove Existing Wooden Shelter	EA	\$	300.00		\$	-
12	Remove Bollard	EA	\$	100.00		\$	-
13	Remove Striping and Pavement Markings	LS	\$	500.00		\$	-
14	Remove Sign and Post	EA	\$	100.00		\$	-
15	Tree Trimming	EA	\$	300.00		\$	_
16	Relocate Existing Sign and Post	EA	\$	200.00		\$	
17	Relocate Existing Utility Pole and Guy Wire	EA	\$	50,000.00		\$	
18	Vertical Curb	LF	\$	40.00		\$	
19	Curb and Gutter	LF	\$	40.00		\$	
20	New Median	SF	\$	20.00		\$	-
21	Asphalt Concrete Type A	TON	\$	400.00		\$	-
22	Aggregate Base Class 2	TON	\$	250.00		\$	
23	Concrete Sidewalk	SF	\$	10.00		\$	_
24	New Curb Ramp	EA	\$	2,000.00		\$	_
25	Concrete Bus Pad	SF	\$	10.00		\$	-
26	Concrete Driveway	SF	\$	40.00		\$	_
27	Thermoplastic Pavement Striping	LS	\$	600.00		\$	-
28	Thermoplastic Pavement Markings	SF	\$	10.00		\$	-
29	Furnish & Install New Storm Drain inlet	EA	\$	10,000.00		\$	_
30	Furnish & Install Luminaire and Pole	EA	\$	4,500.00		\$	-
31	Furnish & Install Luminaire Pole Foundation	EA	\$	1,500.00		\$	-
32	Furnish & Install Pull Box	EA	\$	1,000.00		\$	
33	Install Conduit and Conductors	LS	\$	5,000.00		\$	-
34	Furnish & Install Bollard	EA	\$	200.00		\$	-
35	New Sign and Post	EA	\$	300.00		\$	-
36	Furnish & Install Bus Shelter with Bench (5'x10')	EA	\$	8,000.00		\$	-
37	Furnish & Install Bike Rack	EA	\$	500.00		\$	-
38	Furnish & Install Trash Can Enclosure	EA	\$	500.00		\$	-
39			Ť				
40							
					Total	\$	